

20 Viaduct Harbour Avenue, Auckland 1010 Private Bag 92250, Auckland 1142, New Zealand **Phone** 09 355 3553 **Website** www.AT.govt.nz

NOTICE OF REQUIREMENT FOR DESIGNATION OF LAND UNDER \$168(2) OF THE RESOURCE MANAGEMENT ACT 1991

TO: Auckland Council

FROM: Auckland Transport

Auckland Transport (AT) (an Auckland Council Controlled Organisation) as a Requiring Authority under section 167 of the Resource Management Act 1991 (RMA) gives notice of requirement (NoR) for a designation in the Auckland Unitary Plan for a public work, being the construction, operation and maintenance of an upgrade to Dairy Flat Highway to an urban arterial corridor with active mode facilities between Silverdale Interchange and Durey Road, Dairy Flat.


1. SUMMARY

AT is proposing future strategic transport corridors and stations as part of Te Tupu Ngātahi Supporting Growth Alliance in the North area of Auckland. These projects form the North Projects, under the Te Tupu Ngātahi Supporting Growth Programme. The North Projects are intended to support future urban growth in the North area of Auckland and protect land for future development of these transport corridors/stations over the next 30 years or more.

This form is for NoR 8 which is for the construction, operation and maintenance of an upgrade to a transport corridor and associated activities on Dairy Flat Highway (between Silverdale and Dairy Flat). NoR 8 is located in Silverdale West and Dairy Flat. The extent of the project, designation and boundary of NoR 8 is outlined below.

1





The purpose of the designation is for the construction, operation and maintenance of an upgrade to Dairy Flat Highway to an arterial transport corridor and associated facilities. The activities to be enabled by the designation include environmental mitigation, temporary construction areas, ancillary structure and other activities required for the Project.

The Project objectives for NoR 8 are to:







Provide for an upgrade to Dairy Flat Highway between Silverdale interchange and Durey Road that:

- a) Improves connectivity
- b) Is safe
- c) is efficient, resilient and reliable
- d) Integrates with and supports planned urban growth
- e) Integrates with and supports the existing and future transport network
- f) Improves travel choice and contributes to mode shift

As an approved Requiring Authority under section 176 of the RMA via section 47(1) of the Local Government (Auckland Council) Act 2009, Auckland Transport may designate to construct, operate and maintain a road and undertake ancillary activities.

2. THE SITE TO WHICH THE REQUIREMENT APPLIES IS AS FOLLOWS:

The area of the proposed NoR 8 designation is shown on the Designation Plans included in Attachment A of this Notice. NoR 8 applies to an area of land of approximately 680,346 square metres located in Silverdale West and Dairy Flat in the North growth area. The requirement applies to 230 land parcels (not including legal roads). The land directly affected by NoR 8 is identified in the Schedule of Directly Affected Property included in Attachment B of this Notice.

3. THE NATURE OF THE PROPOSED WORKS IS:

The nature of the proposed work is described in Section 8.8 – NoR 8 – Upgrade to Dairy Flat Highway between Silverdale and Dairy Flat, and in Section 6.4 - Approach to Construction Methodology of the accompanying Assessment of Effects on the Environment (AEE) Report.

In summary, the proposed work includes:

- a) The upgrade of Dairy Flat Highway to an urban arterial corridor with active mode facilities between Silverdale and Dairy Flat
- b) Tie-ins with existing roads and localised widening around the existing intersections to accommodate new intersection forms.
- c) New or upgraded stormwater management systems, bridges and culverts (where applicable).
- d) Batter slopes, and associated cut and fill earthworks.
- e) Vegetation removal.
- f) Other construction related activities required outside the permanent corridor including the regrade of driveways, construction traffic manoeuvring and construction laydown areas.

4. THE NATURE OF THE PROPOSED CONDITIONS THAT WOULD APPLY ARE:

The proposed conditions that will apply to the work are included in Attachment C of this Notice.







5. THE EFFECTS THAT THE PROPOSED WORK WILL HAVE ON THE ENVIRONMENT, AND THE WAYS IN WHICH ANY ADVERSE EFFECTS WILL BE MITIGATED ARE:

The AEE Report contains a description of the existing and likely future environment (Sections 7 and 8.8), an assessment of the effects on the environment from the Project (Sections 9 - 20), and the proposed measures to avoid, remedy or mitigate the adverse effects of the Project (Sections 10 - 22).

Positive Effects

The Project will generate a range of positive effects. The nature and degree of these positive effects are elaborated on in the AEE Part D in particular Sections 9 and 10.1.2 and in the Traffic and Transport Assessment Report. However, they are summarised as follows:

- The project will provide an upgraded transport corridor to support, connect and integrate with planned urban growth in Silverdale West and Dairy Flat.
- The project will provide new safe and attractive walking and cycling, improving safety for active modes and supporting mode shift.
- The project will provide a safe, reliable transport corridor that enables sustainable travel choice and improves access to employment and social amenities.
- The project is part of the wider future transport network for the North, which will collectively provide an efficient, resilient and reliable multi-modal transport network servicing existing urban areas and future growth areas across Auckland's north.

Adverse Effects

There will be a range of potential adverse effects during the construction and operational phases of the Project, which are assessed in the following sections of the AEE Report:

- Traffic and Transportation (Section 10)
- Māori Culture, Values and Aspirations (Section 11)
- Landscape and Visual (Section 12)
- Natural Hazards Flooding (Section 13)
- Terrestrial Ecology (Section 14)
- Archaeology and Built Heritage (Section 15)
- Traffic Noise and Vibration (Section 16)
- Construction Noise and Vibration (Section 16)
- Network Utilities (Section 17)
- Arboricultural (Section 18)
- Community and Social (Section 19)
- Property, Business and Amenity Effects (Section 20)
- Urban Design Evaluation Framework (Section 6).

The AEE Report draws on information provided in the supporting technical documents (contained in Volume 4 of the AEE).

6. ALTERNATIVE SITES, ROUTES, AND METHODS HAVE BEEN CONSIDERED TO THE FOLLOWING EXTENT:

A wide range of alternatives have been investigated for addressing the future transport needs of the North growth area. Alternatives were assessed at all stages of Project development, commencing at a broad scale and systematically narrowing the geographic area from potential corridors down to the indicative alignment.







The process by which AT considered alternative sites, routes and methods of NoR 8 is detailed in Appendix A of the AEE: Assessment of Alternatives Report. Development of NoR 8 was based on a comprehensive and robust optioneering process taking into account Mana Whenua, stakeholder and landowner feedback and specialist assessment inputs.

7. THE PROPOSED WORK AND DESIGNATION ARE REASONABLY NECESSARY FOR ACHIEVING THE OBJECTIVES OF THE REQUIRING AUTHORITY BECAUSE:

The works and designation are reasonably necessary to meet the objectives of AT. Refer to Section 3.3 - Project Objectives and Section 27 – Whether the Work and Designations are Reasonably Necessary for Achieving the Objectives of the AEE report.

AT's purpose under section 39 of the Local Government (Auckland Council) Act 2009 (LGA) is "to contribute to an effective, efficient, and safe Auckland land transport system in the public interest". The Project will assist AT in meeting this objective.

The AT objectives for the Project are to:

Provide for an upgrade to Dairy Flat Highway between Silverdale interchange and Durey Road that:

- a) Improves connectivity.
- b) Is safe.
- c) Is efficient, resilient and reliable.
- d) Integrates with and supports planned urban growth.
- e) Integrates with and supports the existing and future transport network.
- f) Improves travel choice and contributes to mode shift.

The Project achieves these objectives because it will:

- Provide an upgraded transport corridor that connects the Silverdale West and Dairy Flat future urban areas and is integrated with the surrounding urban growth areas.
- Support mode shift and improve safety by providing dedicated active mode facilities which separate vulnerable users from conflict with vehicles, and room for bus priority lanes.
- Support Vision Zero and road safety outcomes.
- Enable access to economic and social opportunities by providing an integrated multi-modal corridor.
- Integrate and support the future transport network including other North Projects, like the NoR 4 SH1 Improvements and NoR 9 Upgrade to Dairy Flat Highway between Dairy Flat and Albany.
- Support the development of an efficient, resilient and reliable multi-modal transport network for the North growth area.

The proposed designation is reasonably necessary as a planning tool, as it identifies and protects land required for the Project and will enable AT to carry out the proposed work.







8. THE FOLLOWING RESOURCE CONSENTS ARE NEEDED FOR THE PROPOSED ACTIVITY AND HAVE NOT BEEN APPLIED FOR:

NoR 8 will require resource consents relating to regional planning and National Environmental Standard matters for a number of activities to enable the proposed works. The resource consents are not sought at this time and will be sought when detailed design is complete and closer to the time of construction. The future resource consents likely to be required for NoR 8 are summarised below.

- Resource consents for the disturbance of contaminated, or potentially contaminated land under the Resource Management (National Environmental Standard for Assessing and Managing Contaminants in Soil to Protect Human Health) Regulations 2011.
- Resource consents for specified infrastructure works within and in proximity to rivers, streams and natural wetlands under the Resource Management (National Environmental Standards for Freshwater) Regulations 2020.
- Resource consents for the following activities under the Auckland Unitary Plan:
 - o Bulk earthworks and associated discharge of sediment
 - o Vegetation removal
 - o Stormwater discharge to land or water
 - Discharge of contaminants to land
 - Activities (including structures and associated works) in, on, under or over the bed of rivers, streams, wetlands
 - Water take, use and diversion.

9. THE FOLLOWING CONSULTATION HAS BEEN UNDERTAKEN WITH PARTIES THAT ARE LIKELY TO BE AFFECTED:

Consultation and engagement is ongoing with various parties who are directly affected by or have an interest in the Project including Mana Whenua, property owners, Auckland Council, Waka Kotahi, network utility operators, business and community representative groups and the wider community. Engagement activities include online video meetings, phone calls, face to face meetings, workshops, hui, newsletters and online information.

The consultation undertaken is detailed in Section 23 of the AEE Report.

10. EXTENDED LAPSE PERIOD PROPOSED:

Under section 184(1) of the RMA a designation lapses on the expiry of 5 years after the date on which it is included in the district plan unless it is given effect to, substantial progress or effort has been made to give effect to, or a different period is specified when incorporated into the plan. There is a need for long term route protection to protect the corridor from inappropriate development until such time as the transport corridor is required to support and facilitate the planned urban growth and funding is allocated. Therefore, pursuant to section 184(1)(c) of the RMA, AT proposes an extended lapse period of 20 years for implementation of the proposed designation.

11. INFORMATION REQUIRED TO BE INCLUDED IN THIS NOTICE BY THE AUCKLAND UNITARY PLAN OR ANY REGULATION MADE UNDER THE RESOURCE MANAGEMENT ACT 1991:

AT attaches the following information required to be included in this notice by the Auckland Unitary Plan, or any regulations made under the Resource Management Act 1991.







- Volume 2: Assessment of Effects on the Environment
- Volume 3: Drawings
- Volume 4: Supporting Technical Assessment Reports

Signed on behalf of Auckland Transport

Jane Small

Group Manager Strategic Programmes and Property, pursuant to authority delegated by Auckland Transport

20 October 2023

Attachment A - Designation Plans

Attachment B - Schedule of Directly Affected Property

Attachment C - Proposed Conditions for the Designation





Attachment A **Designation Plan[s]**























































Attachment B Schedule of Directly Affected Property





Attachment B Schedule of Directly Affected Property

Parcel ID	Legal Description	Certificate of Title	Location	Required Area (m²)(approx.)
402164	Lot 3 DP 174931	NA107C/779	69 Crossbridge Road	130
402156	Lot 6 DP 66869	NA42A/193	928 Dairy Flat Highway	137
402174	Lot 3 DP 66869	NA22D/1204	926 Dairy Flat Highway	140
402368	Lot 1 DP 65346	NA20D/976	807 Dairy Flat Highway	8779
402267	Lot 2 DP 211202	NA138C/317	19 Kennedy Road	6330
402354	Lot 2 DP 205552	NA134A/14	841 Dairy Flat Highway	1228
402346	Lot 1 DP 59104	NA14A/768	867 Dairy Flat Highway	2060
402370	Lot 1 DP 205552	NA134A/13	845 Dairy Flat Highway	2096
402351	Lot 1 DP 89523	NA46D/54	825 Dairy Flat Highway	1337
402330	Lot 1 DP 145108	NA86A/410	859 Dairy Flat Highway	2576
402328	Lot 1 DP 65590	NA35B/1149	883 Dairy Flat Highway	2571
402278	Lot 2 DP 205592	NA134A/96	55 Kennedy Road	2243
401331	Lot 9 DP 64752	NA26A/155	1561 Dairy Flat Highway	4101
401367	Lot 14 DP 64752	NA26A/160	1549 Dairy Flat Highway	2583
401409	Lot 6 DP 52889	NA6C/370	1546 Dairy Flat Highway	3864
401316	Lot 8 DP 64752	NA26A/154	1579 Dairy Flat Highway	3577
401399	Lot 4 DP 71565	NA27D/550	2 Wilks Road West	8054

Parcel ID	Legal Description	Certificate of Title	Location	Required Area (m²)(approx.)
401197	Lot 1 DP 74321	NA30B/736	1646 Dairy Flat Highway	669
401355	Lot 13 DP 64752	NA26A/159	1559 Dairy Flat Highway	4485
401222	Lot 1 DP 178414	NA110A/235	1617 Dairy Flat Highway	916
401350	Lot 9 DP 52889	NA4A/1497	1584 Dairy Flat Highway	1800
401272	Lot 6 DP 64752	NA26A/152	1591 Dairy Flat Highway	226
401285	Lot 7 DP 64752	NA26A/153	1583 Dairy Flat Highway	13787
401326	Lot 10 DP 52889	NA5C/848	1596 Dairy Flat Highway	1921
401163	Lot 3 DP 64752	NA26A/149	1603 Dairy Flat Highway	142
401162	Lot 7 DP 119318	NA68C/467	1667 Dairy Flat Highway	9694
401135	Lot 2 DP 131154	NA76D/510	1669 Dairy Flat Highway	415
401195	Lot 2 DP 74321	NA30B/737	1660 Dairy Flat Highway	3312
401117	Lot 1 DP 131154	NA76D/509	1687 Dairy Flat Highway	5763
401467	Lot 5 DP 62877	NA49C/1320	1455 Dairy Flat Highway	3847
401441	Lot 7 DP 62877	NA19D/1046	1491 Dairy Flat Highway	2327
401429	Lot 3 DP 63879	NA20C/1272	1509 Dairy Flat Highway	2566
401478	Lot 4 DP 62877	NA49C/1319	1453 Dairy Flat Highway	412
401568	Lot 2 DP 173067	NA106A/800	1412 Dairy Flat Highway	5714
401583	Part Allot S264 PSH OF Pukeatua	NA578/246	1397 Dairy Flat Highway	6597

Parcel ID	Legal Description	Certificate of Title	Location	Required Area (m²)(approx.)
401544	Lot 8 DP 198826	NA127C/704	1424 Dairy Flat Highway	3136
401491	Lot 2 DP 67982	NA49C/1318	24 Kahikatea Flat Road	204
401530	Lot 1 DP 183372	NA114B/398	1431 Dairy Flat Highway	411
401510	Lot 2 DP 137389	NA81B/881	1443 Dairy Flat Highway	79
401858	Lot 2 DP 106816	NA59C/418	1248 Dairy Flat Highway	98
401551	Lot 2 DP 183372	NA114B/399	2 Horseshoe Bush Road	1120
401704	Lot 6 DP 128889	NA75A/678	1321 Dairy Flat Highway	710
401686	Part Allot 189 PSH OF Pukeatua	NA579/33	1350 Dairy Flat Highway	2881
401735	Lot 4 DP 128889	NA75A/677	1317 Dairy Flat Highway	71
401742	Lot 2 DP 66181	NA22B/481	Lot 2 DP 66181, Dairy Flat Highway	120
401623	Part Allot S264 PSH OF Pukeatua	NA975/245	Pt Allot 189 SO 1118A, Dairy Flat Highway	1814
401652	Part Allot 189 PSH OF Pukeatua	NA975/245	Pt Allot 189 SO 1118A, Dairy Flat Highway	879
401645	Lot 2 DP 205875	NA134A/846	1355 Dairy Flat Highway	565
401866	Part Allot 192 PSH OF Pukeatua	767699	<null></null>	278
401390	Lot 2 DP 198748	NA126B/37	1550 Dairy Flat Highway	1712
401148	Lot 1 DP 69561	NA25C/412	1686 Dairy Flat Highway	981

Parcel ID	Legal Description	Certificate of Title	Location	Required Area (m²)(approx.)
401369	Lot 1 DP 198748	NA126B/36	1564 Dairy Flat Highway	1610
401188	Lot 2 DP 178414	NA110A/236	1623 Dairy Flat Highway	6106
401539	Lot 6 DP 198826	NA127C/702	1432 Dairy Flat Highway	736
401511	Lot 4 DP 198826	NA127C/700	1440 Dairy Flat Highway	2475
401526	Lot 5 DP 198826	NA127C/701	1436 Dairy Flat Highway	1953
401466	Lot 2 DP 138891	NA82B/200	34 Lascelles Drive	1705
412859	Lot 3 DP 71565	NA27D/549	18 Wilks Road West	196
401413	Lot 2 DP 63879	NA20C/1271	31 Wilks Road West	4375
401483	Lot 1 DP 198826	NA127C/697	1452 Dairy Flat Highway	3374
401575	Lot 1 DP 203960	NA132D/55	1414 Dairy Flat Highway	143
401236	Lot 5 DP 64752	NA26A/151	1595 Dairy Flat Highway	193
401296	Lot 10 DP 64752	NA26A/156	1587 Dairy Flat Highway	257
401191	Lot 4 DP 64752	NA26A/150	1599 Dairy Flat Highway	171
401512	Lot 3 DP 42890	NA1167/70	2 Kahikatea Flat Road	134
401460	Lot 2 DP 170275	NA103D/559	1487 Dairy Flat Highway	2467
401448	Lot 4 DP 138891	NA82B/202	10 Lascelles Drive	3530
401434	Lot 5 DP 138891	NA82B/203	4 Lascelles Drive	6941
401476	Lot 1 DP 138891	NA82B/199	38 Lascelles Drive	6943

Parcel ID	Legal Description	Certificate of Title	Location	Required Area (m²)(approx.)
401595	Lot 5 DP 61243	NA16C/326	1373 Dairy Flat Highway	8097
401454	Lot 3 DP 138891	NA82B/201	28 Lascelles Drive	2194
401450	Lot 1 DP 170275	NA103D/558	1489 Dairy Flat Highway	156
401591	Lot 2 DP 203960	NA132D/56	1416 Dairy Flat Highway	106
402216	Lot 2 DP 205098	NA133B/732	934 Dairy Flat Highway	1039
402205	Lot 1 DP 205098	NA133B/731	Lot 1 DP 205098, Dairy Flat Highway	5268
402187	Lot 2 DP 197040	NA124C/921	958 Dairy Flat Highway	421
402252	Lot 1 DP 195731	NA124C/26	6 Kennedy Road	2485
402173	Lot 7 DP 66869	NA24B/1325	Lot 7 DP 66869, Crossbridge Road	135
402196	Lot 1 DP 155542	NA92D/741	960 Dairy Flat Highway	7413
402020	Lot 1 DP 192798	NA122C/194	4 Postman Road	2268
401970	Lot 13 DP 59985	NA17C/1219	1153 Dairy Flat Highway	3999
402039	Lot 2 DP 192798	NA122C/195	12 Postman Road	4699
401998	Lot 2 DP 204486	NA133A/536	5 Postman Road	3507
402074	Lot 5 DP 185357	NA115C/909	Lot 5 DP 185357, Blackbridge Road	5638
401960	Lot 2 DP 109753	NA61C/1190	1 Richards Road	5950
402083	Allot 414 PSH OF Pukeatua	NA42B/648	20A Jeffs Road	2003
402089	Part Allot 195 PSH OF Pukeatua	NA42B/647	20 Jeffs Road	6375
402240	Lot 1 DP 96635	NA52C/519	957 Dairy Flat Highway	3142

Parcel ID	Legal Description	Certificate of Title	Location	Required Area (m²)(approx.)
402180	Lot 2 DP 196103	NA124C/184	9 Bawden Road	6494
402169	Lot 3 DP 149710	NA89A/773	1006 Dairy Flat Highway	4167
402232	Lot 16 DP 65509	NA24D/890	Lot 16 DP 65509, Dairy Flat Highway	5173
402171	Lot 1 DP 149710	NA89A/771	1008 Dairy Flat Highway	1641
402149	Lot 2 DP 149710	NA89A/772	1014 Dairy Flat Highway	120
401840	Lot 1 DP 106816	NA59C/417	1248A Dairy Flat Highway	1594
401716	Lot 5 DP 66181	NA22B/484	1326 Dairy Flat Highway	2277
401697	Lot 6 DP 66181	NA22B/485	1338 Dairy Flat Highway	2910
401669	Lot 1 DP 56211	NA94D/745	1349 Dairy Flat Highway	394
401736	Lot 1 DP 66181	NA22B/480	1306 Dairy Flat Highway	2788
401719	Lot 4 DP 66181	NA42A/198	1320 Dairy Flat Highway	121
401876	Lot 1 DP 204436	NA133A/270	1215 Dairy Flat Highway	9587
401685	Lot 7 DP 128889	NA75A/679	1327 Dairy Flat Highway	3017
401847	Lot 2 DP 204436	NA133A/271	1215A Dairy Flat Highway	1162
401734	Lot 2 DP 61181	NA16D/710	1289 Dairy Flat Highway	2963
401819	Part Lot 1 DP 2119	NA16B/538	1247 Dairy Flat Highway	7401
401776	Lot 1 DP 61181	NA16D/709	1285 Dairy Flat Highway	4319
402114	Lot 5 DP 205776	NA134A/530	Lot 5 DP 205776, Blackbridge Road	5735

Parcel ID	Legal Description	Certificate of Title	Location	Required Area (m²)(approx.)
402153	Lot 2 DP 141823	NA84A/574	18 Green Road	2015
402144	Lot 30 DP 65509	NA24D/904	1 Green Road	4548
402148	Lot 6 DP 66507	NA55B/133	1016 Dairy Flat Highway	2887
402141	Lot 2 DP 205776	NA134A/527	69 Jean MacKay Place	6488
402131	Lot 4 DP 66507	NA91D/617	1032 Dairy Flat Highway	24008
402192	Lot 18 DP 65509	NA24D/892	47 Green Road	576
401524	Lot 1 DP 45358	NA1545/79	1433 Dairy Flat Highway	68
401524	Lot 1 DP 45358	639726	<null></null>	68
402352	Lot 1 DP 518872	813724	11 Durey Road	2572
402181	Lot 1000 DP 464604	617199	Lot 1000 DP 464604, Whiteways Drive	6274
402251	Lot 1 DP 373695	297526	906 Dairy Flat Highway	20202
402207	Part Lot 2 DP 66869	NA22D/1203	918 Dairy Flat Highway	2367
402154	Part Lot 4 DP 66869	NA22D/1205	64 Crossbridge Road	130
402374	Lot 1 DP 414241	453368	823 Dairy Flat Highway	228
402339	Lot 1 DP 424017	493330	851 Dairy Flat Highway	4588
402324	Lot 2 DP 510814	783114	905 Dairy Flat Highway	3739
402327	Lot 105 DP 328499	617199	Lot 1000 DP 464604, Whiteways Drive	13167
402371	Lot 1 DP 329098	118825	796 Dairy Flat Highway	3157
402365	Lot 1 DP 482999	680395	16 Durey Road	107

Parcel ID	Legal Description	Certificate of Title	Location	Required Area (m²)(approx.)
401347	Lot 1 DP 208687	NA136D/722	1636 Dairy Flat Highway	3619
401299	Lot 1 DP 318185	71145	1602A Dairy Flat Highway	938
401215	Lot 1 DP 530123	861184	1609 Dairy Flat Highway	2023
401139	Part Lot 2 DP 68886	NA25A/503	1732 Dairy Flat Highway	6153
401064	Part Lot 1 DP 101886	92357	1731 Dairy Flat Highway	28284
401042	Part Allot 16 PSH OF Okura	NA3C/1149	Pt Allot 16 SO 18072, Old Pine Valley Road	1545
401865	Lot 2 DP 208356	NA136C/663	1236 Dairy Flat Highway	429
401766	Lot 1 DP 211943	NA139D/645	1286 Dairy Flat Highway	1865
401796	Lot 1 DP 323028	92311	1270 Dairy Flat Highway	13536
401900	Lot 2 DP 418510	471067	1198B Dairy Flat Highway	1819
401617	Lot 7 DP 371632	289779	1361 Dairy Flat Highway	3084
401718	Lot 1 DP 56702	NA35C/236	1315 Dairy Flat Highway	155
415266	Lot 2 DP 563736	1002880	1314 Dairy Flat Highway	120
401371	Lot 8 DP 52889	NA3C/1498	1570 Dairy Flat Highway	1660
401208	Lot 1 DP 46158	NA1698/16	1638 Dairy Flat Highway	3702
401235	Lot 2 DP 530123	861185	1615 Dairy Flat Highway	1319
401318	Lot 2 DP 318185	71146	1602 Dairy Flat Highway	1149
401126	Part Lot 1 DP 68886	NA25A/502	1700 Dairy Flat Highway	5928

Parcel ID	Legal Description	Certificate of Title	Location	Required Area (m²)(approx.)
401416	Part Lot 1 DP 71373	NA27C/1417	9 Wilks Road	2441
402221	Lot 1 DP 212206	NA140A/631	987 Dairy Flat Highway	6663
402194	Part Lot 9 DP 66869	NA22D/1198	956 Dairy Flat Highway	2297
401985	Lot 1 DP 349138	201523	Lot 1 DP 349138, Postman Road	2288
401930	Lot 4 DP 418510	471069	1182 Dairy Flat Highway	16260
402007	Part Lot 12 DP 59985	NA17C/1218	14 Blackbridge Road	5243
402108	Lot 1 DP 346379	190620	15 Lower Jeffs Road	633
402188	Lot 1 DP 381042	324362	1005A Dairy Flat Highway	1219
401813	Lot 1 DP 207885	NA136B/540	1256 Dairy Flat Highway	2968
401910	Lot 1 DP 399787	398086	55 Postman Road	4775
401834	Lot 1 DP 469054	630656	1250 Dairy Flat Highway	264
401773	Lot 2 DP 211943	NA139D/646	1284 Dairy Flat Highway	2895
401661	Lot 8 DP 371632	289780	1351 Dairy Flat Highway	46
402167	Lot 1 DP 347269	194300	27 Green Road	5828
402124	Lot 2 DP 346379	190621	17 Lower Jeffs Road	10824
402211	Lot 2 DP 381042	324363	1005 Dairy Flat Highway	454
402166	Lot 2 DP 347269	194301	29 Green Road	5070
402175	Lot 2 DP 336798	150491	31 Green Road	1650
401619	Lot 1 DP 578552	1071146	1368 Dairy Flat Highway	8492

Parcel ID	Legal Description	Certificate of Title	Location	Required Area (m²)(approx.)
402279	Lot 200 DP 328499	116330	86 Goodland Drive	1902
402279	Lot 200 DP 328499	116337	146 Goodland Drive	1902
402279	Lot 200 DP 328499	116275	2 Lynwood Grove	1902
402279	Lot 200 DP 328499	116276	9 Goodland Drive	1902
402279	Lot 200 DP 328499	116277	6 Lynwood Grove	1902
402279	Lot 200 DP 328499	116278	16 Lynwood Grove	1902
402279	Lot 200 DP 328499	116279	22 Lynwood Grove	1902
402279	Lot 200 DP 328499	116280	24 Lynwood Grove	1902
402279	Lot 200 DP 328499	116281	26 Lynwood Grove	1902
402279	Lot 200 DP 328499	116282	28 Lynwood Grove	1902
402279	Lot 200 DP 328499	116283	25 Lynwood Grove	1902
402279	Lot 200 DP 328499	116285	23 Whiteways Drive	1902
402279	Lot 200 DP 328499	116286	33 Whiteways Drive	1902
402279	Lot 200 DP 328499	116287	37 Whiteways Drive	1902
402279	Lot 200 DP 328499	116288	39 Whiteways Drive	1902
402279	Lot 200 DP 328499	116289	40 Whiteways Drive	1902
402279	Lot 200 DP 328499	116290	38 Whiteways Drive	1902
402279	Lot 200 DP 328499	116291	36 Whiteways Drive	1902

Parcel ID	Legal Description	Certificate of Title	Location	Required Area (m²)(approx.)
402279	Lot 200 DP 328499	116292	34 Whiteways Drive	1902
402279	Lot 200 DP 328499	116293	20 Whiteways Drive	1902
402279	Lot 200 DP 328499	116294	18 Whiteways Drive	1902
402279	Lot 200 DP 328499	116295	12 Whiteways Drive	1902
402279	Lot 200 DP 328499	116296	10 Whiteways Drive	1902
402279	Lot 200 DP 328499	116297	24 Goodland Drive	1902
402279	Lot 200 DP 328499	116298	6 Langford Place	1902
402279	Lot 200 DP 328499	116299	16 Langford Place	1902
402279	Lot 200 DP 328499	116300	18 Langford Place	1902
402279	Lot 200 DP 328499	116301	24 Langford Place	1902
402279	Lot 200 DP 328499	116302	22 Langford Place	1902
402279	Lot 200 DP 328499	116303	20 Langford Place	1902
402279	Lot 200 DP 328499	116304	26 Langford Place	1902
402279	Lot 200 DP 328499	116305	32 Langford Place	1902
402279	Lot 200 DP 328499	116306	45 Langford Place	1902
402279	Lot 200 DP 328499	116307	43 Langford Place	1902
402279	Lot 200 DP 328499	116308	35 Langford Place	1902
402279	Lot 200 DP 328499	116309	33 Langford Place	1902

Parcel ID	Legal Description	Certificate of Title	Location	Required Area (m²)(approx.)
402279	Lot 200 DP 328499	116310	29 Langford Place	1902
402279	Lot 200 DP 328499	116311	19 Langford Place	1902
402279	Lot 200 DP 328499	116312	9 Langford Place	1902
402279	Lot 200 DP 328499	116313	11 Kingscliff Rise	1902
402279	Lot 200 DP 328499	116314	5 Kingscliff Rise	1902
402279	Lot 200 DP 328499	116315	Lot 41 DP 328499, Kingscliff Rise	1902
402279	Lot 200 DP 328499	116316	43 Kingscliff Rise	1902
402279	Lot 200 DP 328499	116317	45 Kingscliff Rise	1902
402279	Lot 200 DP 328499	116318	86 Kingscliff Rise	1902
402279	Lot 200 DP 328499	116319	78 Kingscliff Rise	1902
402279	Lot 200 DP 328499	116320	72 Kingscliff Rise	1902
402279	Lot 200 DP 328499	116321	133 Goodland Drive	1902
402279	Lot 200 DP 328499	116322	50 Kingscliff Rise	1902
402279	Lot 200 DP 328499	116323	6 Kingscliff Rise	1902
402279	Lot 200 DP 328499	116324	12B Kingscliff Rise	1902
402279	Lot 200 DP 328499	116325	12A Kingscliff Rise	1902
402279	Lot 200 DP 328499	116326	62 Goodland Drive	1902
402279	Lot 200 DP 328499	116327	48 Goodland Drive	1902

Parcel ID	Legal Description	Certificate of Title	Location	Required Area (m²)(approx.)
402279	Lot 200 DP 328499	116328	70 Goodland Drive	1902
402279	Lot 200 DP 328499	116329	82 Goodland Drive	1902
402279	Lot 200 DP 328499	116331	85 Goodland Drive	1902
402279	Lot 200 DP 328499	116332	103 Goodland Drive	1902
402279	Lot 200 DP 328499	116333	118 Goodland Drive	1902
402279	Lot 200 DP 328499	116334	Lot 60 DP 328499, Goodland Drive	1902
402279	Lot 200 DP 328499	116335	135 Goodland Drive	1902
402279	Lot 200 DP 328499	116336	143 Goodland Drive	1902
402279	Lot 200 DP 328499	617198	11 Whiteways Drive	1902
402279	Lot 200 DP 328499	617199	Lot 1000 DP 464604, Whiteways Drive	1902
402246	<null></null>	<null></null>	<null></null>	101
402362	Part Lot 2 DP 329098	118826	12 Durey Road	1599
401079	Section 5 SO 315843	92357	1731 Dairy Flat Highway	82
401087	Section 6 SO 315843	92357	1731 Dairy Flat Highway	484

Attachment C Proposed Designation Conditions







Auckland Transport North Conditions (NoRs 5-13)

Draft Conditions

Abbreviations and definitions

Acronym/Term	Definition
Activity sensitive to noise	Any dwelling, visitor accommodation, boarding house, marae, papakāinga, integrated residential development, retirement village, supported residential care, care centre, lecture theatre in a tertiary education facility, classroom in an education facility and healthcare facility with an overnight stay facility.
AUP	Auckland Unitary Plan.
BPO or Best Practicable Option	Has the same meaning as in section 2 of the RMA 1991.
CEMP	Construction Environmental Management Plan
Certification of material changes to management plans and CNVMP Schedules	Confirmation from the Manager that a material change to a plan or CNVMP Schedule has been prepared in accordance with the condition to which it relates.
	A material change to a management plan or CNVMP Schedule shall be deemed certified:
	 (a) where the Requiring Authority has received written confirmation from Council that the material change to the management plan is certified; (b) ten working days from the submission of the material change to the management plan where no written confirmation of certification has
	been received; or (c) five working days from the submission of the material change to a CNVMP Schedule where no written confirmation of certification has been received.
CNVMP	Construction Noise and Vibration Management Plan
CNVMP Schedule or Schedule	A schedule to the CNVMP
Completion of Construction	When construction of the Project (or part of the Project) is complete and it is available for use.
Confirmed Biodiversity Areas	Areas recorded in the Identified Biodiversity Area Schedule where the ecological values and effects have been confirmed through the ecological survey under Condition 24.
Construction Works	Activities undertaken to construct the Project excluding Enabling Works.
Council	Auckland Council
СТМР	Construction Traffic Management Plan
Developer	Any legal entity that intends to master plan or develop land adjacent to the designation
Development Agency	Public entities involved in development projects
EMP	Ecological Management Plan
EIANZ Guidelines	Ecological Impact Assessment: EIANZ guidelines for use in New Zealand: terrestrial and freshwater ecosystems, second edition, dated May 2018.
Enabling works	Includes, but is not limited to, the following and similar activities:
	 (a) geotechnical investigations (including trial embankments) (b) archaeological site investigations (c) formation of access for geotechnical investigations (d) establishment of site yards, site entrances and fencing







Acronym/Term	Definition
	 (f) demolition or removal of buildings and structures (g) relocation of services (h) establishment of mitigation measures (such as erosion and sediment control measures, temporary noise walls, earth bunds and planting)
HHMP	Historic Heritage Management Plan
HNZPT	Heritage New Zealand Pouhere Taonga.
HNZPTA	Heritage New Zealand Pouhere Taonga Act 2014
Identified Biodiversity Area	Means an area or areas of features of ecological value where the Project ecologist has identified that the project will potentially have a moderate or greater level of ecological effect, prior to implementation of impact management measures, as determined in accordance with the EIANZ guidelines.
Manager	The Manager – Resource Consents of the Auckland Council, or authorised delegate.
Mana Whenua	Mana Whenua as referred to in the conditions is considered to be the following (in no particular order), who at the time of Notice of Requirement expressed a desire to be involved in the Project: 1 Ngāti Manuhiri 2 Te Kawerau ā Maki 3 Te Ākitai Waiohua 4 Ngāti Whanaunga 5 Te Runanga o Ngāti Whātua 6 Ngāti Maru 7 Te Patu Kirikiri 8 Ngāti Whātua o Kaipara 9 Ngāti Tamaterā 10 Ngai Tai ki Tāmaki 11 Ngāti Paoa Iwi Trust 12 Ngāti Paoa Trust Board Note: Other iwi not identified above may have an interest in the Project and should be consulted
NIMP	Network Integration Management Plan
Network Utility Operator	Has the same meaning as set out in section 166 of the RMA
North Growth Area	Land for future urban development in the North of Auckland, including Future Urban zoned areas in Ara Hills, Ōrewa, Wainui East, Silverdale West, Redvale and Dairy Flat
NUMP	Network Utilities Management Plan
NOR	Notice of Requirement
NZAA	New Zealand Archaeological Association
Outline Plan	An outline plan prepared in accordance with section 176A of the RMA.
Project Liaison Person	The person or persons appointed for the duration of the Project's Construction Works to be the main point of contact for persons wanting information about the Project or affected by the Construction Works.







Acronym/Term	Definition
Protected Premises and Facilities (PPF)	Protected Premises and Facilities as defined in New Zealand Standard NZS 6806:2010: Acoustics – Road-traffic noise – New and altered roads.
Requiring Authority	Has the same meaning as section 166 of the RMA and, for this Designation is Auckland Transport.
RMA	Resource Management Act (1991)
SCEMP	Stakeholder Communication and Engagement Management Plan
Stage of Work	Any physical works that require the development of an Outline Plan.
Start of Construction	The time when Construction Works (excluding Enabling Works) start.
Suitably Qualified Person	A person (or persons) who can provide sufficient evidence to demonstrate their suitability, experience and competence in the relevant field of expertise.
ULDMP	Urban and Landscape Design Management Plan







NoR					
No.	No.	Condition			
Gener	eneral Conditions				
All	1. Activity in General Accordance with Plans and Information				
		 (a) Except as provided for in the conditions below, and subject to final design and Outline Plan(s), works within the designation shall be undertaken in general accordance with the Project description and concept plan in schedule 1: (b) Where there is inconsistency between: (i) the Project description and concept plan in schedule 1 and the requirements of the following conditions, the conditions shall prevail; (ii) the Project description and concept plan in schedule 1, and the management plans under the conditions of the designation, the requirements of the management plans shall prevail. 			
All	2.	Project Information			
		 (a) A project website, or equivalent virtual information source, shall be established within 12 months of the date on which this designation is included in the AUP. All directly affected owners and occupiers shall be notified in writing once the website or equivalent information source has been established. The project website or virtual information source shall include these conditions and shall provide information on: (i) the status of the Project; (ii) anticipated construction timeframes; (iii) contact details for enquiries; (iv) the implications of the designation for landowners, occupiers and business owners and operators within the designation and information on how/where they can receive additional support following confirmation of the designation; (v) a subscription service to enable receipt of project updates by email; (vi) the types of activities that can be undertaken by landowners without the need for written consent to be obtained under s176(1)(b) of the RMA; and (vii) when and how to apply for consent for works in the designation under s176(1)(b) of the RMA (i.e. for activities not covered by (vi) above). (b) At the start of detailed design for a Stage of Work, the project website or virtual information source shall be updated to provide information on the likely date for Start of Construction, and any staging of works. 			
All	3.	Designation Review			
		 (a) The Requiring Authority shall within 6 months of Completion of Construction or as soon as otherwise practicable: review the extent of the designation to identify any areas of designated land that it no longer requires for the on-going operation, maintenance or mitigation of effects of the Project; and give notice to Auckland Council in accordance with section 182 of the RMA for the removal of those parts of the designation identified above. 			
NoR	4.	Lapse			
s 5, 6, 7, 9, 12, 13		In accordance with section 184(1)(c) of the RMA, this designation shall lapse if not given effect to within 30 years from the date on which it is included in the AUP.			
NoR 11	4.	In accordance with section 184(1)(c) of the RMA, this designation shall lapse if not given effect to within 25 years from the date on which it is included in the AUP.			
NoR 8 and 10	4.	In accordance with section 184(1)(c) of the RMA, this designation shall lapse if not given effect to within 20 years from the date on which it is included in the AUP.			
All	5.	Network Utility Operators (Section 176 Approval)			
ΛII	J.	Network office Operators (Section 170 Approval)			







NoR			
No.	No.	Condition	
		 (a) Prior to the start of Construction Works, Network Utility Operators with existing infrastructure located within the designation will not require written consent under section 176 of the RMA for the following activities: (i) operation, maintenance and urgent repair works; (ii) minor renewal works to existing network utilities necessary for the on-going provision or security of supply of network utility operations; (iii) minor works such as new service connections; and (iv) the upgrade and replacement of existing network utilities in the same location with the same or similar effects as the existing utility. (b) To the extent that a record of written approval is required for the activities listed above, 	
		this condition shall constitute written approval.	
All	6.	 (a) Prior to the start of the formal acquisition process under the Public Works Act 1981 for a property, or submission of the Outline Plan to the Requiring Authority, persons on properties zoned Rural or Future Urban will not require written consent under section 176 of the RMA for the following activities: (i) Internal alterations; (ii) One extension to an existing structure as at 2023, up to 30m²; (iii) Temporary or relocatable structures, provided they are removed from the site and the land is reinstated (including closing and capping any associated services) at the landowner's expense prior to the start of Construction Works. The landowner shall be responsible for any resource consent required for the structures, their removal or relocation, (b) To the extent that a record of written approval is required for the activities listed above, this condition shall constitute written approval. 	
Pre-co	nstructio	n Conditions	
All	7.	Outline Plan (a) An Outline Plan (or Plans) shall be prepared in accordance with section 176A of the RMA. (b) Outline Plans (or Plan) may be submitted in parts or in stages to address particular activities (e.g. design or construction aspects), or a Stage of Work of the Project. (c) Outline Plans shall include any management plan or plans that are relevant to the management of effects of those activities or Stage of Work, which may include: (i) Construction Environmental Management Plan (CEMP); (ii) Construction Traffic Management Plan (CTMP); (iii) Construction Noise and Vibration Management Plan (CNVMP); (iv) Urban and Landscape Design Management Plan (ULDMP); (v) Historic Heritage Management Plan (HHMP); (vi) Ecological Management Plan (EMP); (vii) Tree Management Plan (TMP); and (viii) Network Utilities Management Plan (NUMP).	
All	8.	(a) Any management plan shall: (i) Be prepared and implemented in accordance with the relevant management plan condition; (ii) Be prepared by a Suitably Qualified Person(s); (iii) Include sufficient detail relating to the management of effects associated with the relevant activities and/or Stage of Work to which it relates. (iv) Summarise comments received from Mana Whenua and other stakeholders as required by the relevant management plan condition, along with a summary of where comments have: a. Been incorporated; and b. Where not incorporated, the reasons why. (v) Be submitted as part of an Outline Plan pursuant to s176A of the RMA, with	







NoR No.	No.	Condition
		 (vi) Once finalised, uploaded to the Project website or equivalent virtual information source. (b) Any management plan developed in accordance with Condition 8 may: (i) Be submitted in parts or in stages to address particular activities (e.g. design or construction aspects) a Stage of Work of the Project, or to address specific activities authorised by the designation. (ii) Except for material changes, be amended to reflect any changes in design, construction methods or management of effects without further process. (iii) If there is a material change required to a management plan which has been submitted with an Outline Plan, the revised part of the plan shall be submitted to the Council as an update to the Outline Plan or for Certification as soon as practicable following identification of the need for a revision; (c) Any material changes to the SCEMPs, are to be submitted to the Council for information.
All	9.	Cultural Advisory Report
		 (a) At least six (6) months prior to the start of detailed design for a Stage of Work, Mana Whenua shall be invited to prepare a Cultural Advisory Report for the Project. (b) The objective of the Cultural Advisory Report is to assist in understanding and identifying Ngā Taonga Tuku lho ('treasures handed down by our ancestors') affected by the Project, to inform their management and protection. To achieve the objective, the Requiring Authority shall invite Mana Whenua to prepare a Cultural Advisory Report that: (i) Identifies the cultural sites, landscapes and values that have the potential to be affected by the construction and operation of the Project; (ii) Sets out the desired outcomes for management of potential effects on cultural sites, landscapes and values; (iii) Identifies traditional cultural practices within the area that may be impacted by the Project; (iv) Identifies opportunities for restoration and enhancement of identified cultural sites, landscapes and values within the Project area; (x) Taking into account the outcomes of (i) to (iv) above, identify cultural matters and principles that should be considered in the development of the Urban and Landscape Design Management Plan (Condition 11) and Historic Heritage Management Plan Condition 23), and the Cultural Monitoring Plan referred to in Condition 17. (v) Identifies and (if possible) nominates traditional names along the Project alignment. Noting there may be formal statutory processes outside the project required in any decision-making. (c) The desired outcomes for management of potential effects on cultural sites, landscapes and values identified in the Cultural Advisory Report shall be discussed with Mana Whenua and those outcomes reflected in the relevant management plans where practicable. (d) Conditions 9(b) and (c) above will cease to apply if: (ii) Mana Whenua have been invited to prepare a Cultural Advisory Report by a date at least 6 mo
All	10.	Land use Integration Process (LIP)
		The Requiring Authority shall set up a Land use Integration Process for the period between confirmation of the designation and the Start of Construction. The purpose of this process is to encourage and facilitate the integration of master planning and land use development activity on land directly affected or adjacent to the designation. To achieve this purpose: (a) Within twelve (12) months of the date on which this designation is included in the
		Auckland Unitary Plan, the Requiring Authority shall include the contact details of a nominated contact on the project website (or equivalent information source) required to be established by Condition 2(a)(iii).







NoR		
No.	No.	Condition
		 (b) The nominated contact shall be the main point of contact for a Developer or Development Agency wanting to work with the Requiring Authority to integrate their development plans or master planning with the designation. (c) At any time prior to the Start of Construction, the nominated contact will be available to engage with a Developer or Development Agency for the purpose of: (i) responding to requests made to the Requiring Authority for information regarding design details that could assist with land use integration; and (ii) receiving information from a Developer or Development Agency regarding master planning or land development details that could assist with land use integration. (d) Information requested or provided under Condition 9(c) above may include but not be limited to the following matters: (i) design details including but not limited to: A. boundary treatment (e.g. the use of retaining walls or batter slopes); B. the horizontal and vertical alignment of the road (levels); C. potential locations for mid-block crossings; and D. integration of stormwater infrastructure. (ii) a process for the Requiring Authority to undertake a technical review of or provide comments on any master planning or development proposal advanced by the Developer or Development Agency as it relates to integration with the Project; and (iii) details of how to apply for written consent from the Requiring Authority for any development proposal that relates to land is within the designation under section 176(1)(b) of the RMA. (e) Where information is requested from the Requiring Authority and is available, the nominated contact shall provide the information unless there are reasonable grounds for not providing it. (f) The nominated contact shall maintain a record of the engagement between the Requiring Authority and Developers and Development Agencies for the period following the da
All	11.	 (a) A ULDMP shall be prepared prior to the Start of Construction for a Stage of Work. Mana Whenua shall be invited to participate in the development of the ULDMP(s) to provide input into relevant cultural landscape and design matters including how desired outcomes for management of potential effects on cultural sites, landscapes and values identified and discussed in accordance with Condition 9(c) may be reflected in the ULDMP. The objective of the ULDMP(s) is to: Enable integration of the Project's permanent works into the surrounding landscape and urban context; and Ensure that the Project manages potential adverse landscape and visual effects as far as practicable and contributes to a quality urban environment. The ULDMP shall be prepared in general accordance with: Auckland Transport's Urban Roads and Streets Design Guide; Waka Kotahi Urban Design Guidelines: Bridging the Gap (2013) or any subsequent updated version; Waka Kotahi Landscape Guidelines (2013) or any subsequent updated version; Waka Kotahi P39 Standard Specification for Highway Landscape Treatments (2013) or any subsequent updated version; and Auckland's Urban Ngahere (Forest) Strategy or any subsequent updated version. To achieve the objective, the ULDMP(s) shall provide details of how the project: Is designed to integrate with the adjacent urban (or proposed urban) and landscape context, including the surrounding existing or proposed topography,







NoR		
No.	No.	Condition
		urban environment (i.e. centres and density of built form), natural environment, landscape character and open space zones; (ii) Provides appropriate walking and cycling connectivity to, and interfaces with, existing or proposed adjacent land uses, public transport infrastructure and walking and cycling connections; (iii) Promotes inclusive access (where appropriate); and (iv) Promotes a sense of personal safety by aligning with best practice guidelines, such as: a. Crime Prevention Through Environmental Design (CPTED) principles; b. Safety in Design (SID) requirements; and
		 c. Maintenance in Design (MID) requirements and anti-vandalism/anti-graffiti measures. (v) has responded to matters identified through the Land Use Integration Management Process (Condition 10). (d) The ULDMP(s) shall include: (i) A concept plan – which depicts the overall landscape and urban design concept, and explain the rationale for the landscape and urban design proposals:
		and explain the rationale for the landscape and urban design proposals; (ii) Developed design concepts, including principles for walking and cycling facilities and public transport; and (iii) Landscape and urban design details – that cover the following: a. Road design – elements such as intersection form, carriageway gradient and associated earthworks contouring including cut and fill batters and the interface with adjacent land uses and existing roads (including slip lanes), benching, spoil disposal sites, median width and treatment, roadside width and treatment; b. Roadside elements – such as lighting, fencing, wayfinding and signage; c. Architectural and landscape treatment of all major structures, including bridges and retaining walls; d. Architectural and landscape treatment of noise barriers; e. Landscape treatment of permanent stormwater control wetlands and swales; f. Integration of passenger transport; g. Pedestrian and cycle facilities including paths, road crossings and dedicated pedestrian/ cycle bridges or underpasses; h. Historic heritage places with reference to the HHMP (Condition 23); and i. Re-instatement of construction and site compound areas, driveways, accessways and fences.
		(e) The ULDMP shall also include the following planting details and maintenance requirements: (i) planting design details including: a. Identification of existing trees and vegetation that will be retained with reference to the Tree Management Plan. Where practicable, mature trees and native vegetation should be retained; b. Street trees, shrubs and ground cover suitable for the location; c. treatment of fill slopes to integrate with adjacent land use, streams, Riparian margins and open space zones; d. planting of stormwater wetlands; e. Identification of vegetation to be retained and any planting requirements under the Ecological Management Plan (Condition 25) and Tree Management Plan (Condition 26); f. Integration of any planting requirements required by conditions of any resource consents for the project; and g. Re-instatement planting of construction and site compound areas as appropriate. (ii) A planting programme including the staging of planting in relation to the construction programme which shall, as far as practicable, include provision for planting within each planting season following completion of works in each Stage of Work; and (iii) Detailed specifications relating to the following:
		a. Weed control and clearance;b. Pest animal management (to support plant establishment);







NoR No.	No.	Condition
No.	No.	c. Ground preparation (top soiling and decompaction); d. Mulching; and e. Plant sourcing and planting, including hydroseeding and grassing, and use of eco-sourced species. Advice Note: This designation is for the purpose of construction, operation and maintenance of an arterial transport corridor and it is not for the specific purpose of "road widening". Therefore, it is not intended that the front yard definition in the Auckland Unitary Plan which applies a set back from a designation for road widening purposes applies to this designation. A set back is not required to manage effects between the designation boundary and any proposed adjacent sites or lots.
Specif	fic Outline	e Plan Requirements
AII	N/A	Flood Hazard For the purpose of Condition 12: (a) ARI – means Average Recurrence Interval (b) AEP – Means Annual Exceedance Probability (c) Existing authorised habitable floor – means the floor level of any room (floor) in a residential building which is authorised by building consent and exists at the time the outline plan is submitted, excluding a laundry, bathroom, toilet or any room used solely as an entrance hall, passageway or garage. (d) Flood prone area – means a potential ponding area that relies on a single culvert for drainage and does not have an overland flow path. (e) Maximum Probable Development – is the design case for consideration of future flows allowing for development within a catchment that takes into account the maximum impervious surface limits of the current zone or if the land is zoned Future Urban in the AUP, the probable level of development arising from zone changes. (f) Pre-Project development – means existing site condition prior to the Project (including existing buildings and roadways). (g) Post-Project development – means site condition after the Project has been completed (including existing and new buildings and roadways).
All	12.	 (a) The Project shall be designed to achieve the following flood risk outcomes: (i) no increase in flood levels in a 1% AEP event for existing authorised habitable floors that are already subject to flooding or have a freeboard less than 150mm; (ii) no more than a 10% reduction in freeboard in a 1% AEP event for existing authorised habitable floors with a freeboard over 150mm; (iii) no increase in 1% AEP flood levels for existing authorised community, commercial and industrial building floors that are already subject to flooding; (iv) no more than a 10% reduction in freeboard in a 1% AEP event for existing authorised community, commercial and industrial building floors; (v) no increase of more than 50mm in flood level in a 1% AEP event on land zoned for urban or future urban development where there is no existing dwelling; (vi) no new flood prone areas; and (vii) no more than a 10% average increase of flood hazard (defined as flow depth times velocity) for main access to authorised habitable dwellings existing at time the Outline Plan is submitted. The assessment shall be undertaken for the 1% AEP rainfall event. (b) Compliance with this condition shall be demonstrated in the Outline Plan, which shall include flood modelling of the pre-Project and post-Project 10% and 1% AEP flood levels (for Maximum Probable Development land use and including climate change). (c) Where the above outcomes can be achieved through alternative measures outside of the designation such as flood stop banks, flood walls, raising existing authorised







NoR No.	No.	Condition
		habitable floor level and new overland flow paths or varied through agreement with the relevant landowner, the Outline Plan shall include confirmation that any necessary landowner and statutory approvals have been obtained for that work or alternative outcome.
All	13.	Existing property access
		Prior to submission of the Outline Plan, consultation shall be undertaken with landowners and occupiers whose vehicle access to their property will be altered by the project. The Outline Plan shall demonstrate how safe reconfigured or alternate access will be provided, unless otherwise agreed with the landowner.
Const	ruction Co	onditions
All	14.	Construction Environmental Management Plan (CEMP)
		 (a) A CEMP shall be prepared prior to the Start of Construction for a Stage of Work. The objective of the CEMP is to set out the management procedures and construction methods to be undertaken to, avoid, remedy or mitigate any adverse effects associated with Construction Works as far as practicable. To achieve the objective, the CEMP shall include: (i) the roles and responsibilities of staff and contractors; (ii) details of the site or project manager and the Project Liaison Person, including their contact details (phone and email address); (iii) the Construction Works programmes and the staging approach, and the proposed hours of work; (iv) details of the proposed construction yards including temporary screening when adjacent to residential areas, locations of refuelling activities and construction lighting; (v) methods for controlling dust and the removal of debris and demolition of construction materials from public roads or places; (vi) methods for providing for the health and safety of the general public; (vii) measures to mitigate flood hazard effects such as siting stockpiles out of floodplains, minimising obstruction to flood flows, actions to respond to warnings of heavy rain; (viii) procedures for the refuelling and maintenance of plant and equipment to avoid discharges of fuels or lubricants to Watercourses; (x) measures to address the storage of fuels, lubricants, hazardous and/or dangerous materials, along with contingency procedures to address emergency spill response(s) and clean up; (xi) procedures for responding to complaints about Construction Works; and methods for amending and updating the CEMP as required.
All	15.	Stakeholder and Communication and Engagement Management Plan (SCEMP)
		 (a) A SCEMP shall be prepared prior to the Start of Construction for a Stage of Work. The objective of the SCEMP is to identify how the public and stakeholders (including directly affected and adjacent owners and occupiers of land) will be engaged with throughout the Construction Works. To achieve the objective, the SCEMP shall include: (i) the contact details for the Project Liaison Person. These details shall be on the Project website, or equivalent virtual information source, and prominently displayed at the main entrance(s) to the site(s); (ii) the procedures for ensuring that there is a contact person available for the duration of Construction Works, for public enquiries or complaints about the Construction Works; (iii) methods for engaging with Mana Whenua, to be developed in consultation with Mana Whenua;







NoR No.	No.	Condition
		 (iv) a list of stakeholders, organisations (such as community facilities) and businesses who will be engaged with; (v) Identification of the properties whose owners will be engaged with; (vi) Methods and timing to engage with landowners whose access is directly affected (vii) methods to communicate key project milestones and the proposed hours of construction activities including outside of normal working hours and on weekends and public holidays, to the parties identified in (iv) and (v) above; and (viii) linkages and cross-references to communication and engagement methods set out in other conditions and management plans where relevant. (b) Any SCEMP prepared for a Stage of Work shall be submitted to Council for information ten working days prior to the Start of Construction for a Stage of Work.
All	16.	Complaints Register (a) At all times during Construction Works, a record of any complaints received about the Construction Works shall be maintained. The record shall include: (i) The date, time and nature of the complaint; (ii) The name, phone number and address of the complainant (unless the complainant wishes to remain anonymous); (iii) Measures taken to respond to the complaint (including a record of the response provided to the complainant) or confirmation of no action if deemed appropriate; (iv) The outcome of the investigation into the complaint; (v) Any other activities in the area, unrelated to the Project that may have contributed to the complaint, such as non-project construction, fires, traffic accidents or unusually dusty conditions generally. (b) A copy of the Complaints Register required by this condition shall be made available to the Manager upon request as soon as practicable after the request is made.
AII	17.	Cultural Monitoring Plan (a) Prior to the start of Construction Works, a Cultural Monitoring Plan shall be prepared by a Suitably Qualified Person(s) identified in collaboration with Mana Whenua. The objective of the Cultural Monitoring Plan is to identify methods for undertaking cultural monitoring to assist with management of any cultural effects during Construction works. The Cultural Monitoring Plan shall include: (i) Requirements for formal dedication or cultural interpretation to be undertaken prior to start of Construction Works in areas identified as having significance to Mana Whenua; (ii) Requirements and protocols for cultural inductions for contractors and subcontractors; (iii) Identification of activities, sites and areas where cultural monitoring is required during particular Construction Works; (iv) Identification of personnel to undertake cultural monitoring, including any geographic definition of their responsibilities; and (v) Details of personnel to assist with management of any cultural effects identified during cultural monitoring, including implementation of the Accidental Discovery Protocol (b) If Enabling Works involving soil disturbance are undertaken prior to the start of Construction Works, an Enabling Works Cultural Monitoring Plan shall be prepared by a Suitably Qualified Person identified in collaboration with Mana Whenua. This plan may be prepared as a standalone Enabling Works Cultural Monitoring Plan or







NoR							
No.	No.	Condition					
		Advice Note: Where appropriate, the Cultural Monitoring Plan shall align with the requirements of other conditions of the designation and resource consents for the Project which require monitoring during Construction Works.					
All	18.	Construction Traffic Management Plan (CTMP)					
		(a) A CTMP shall be prepared prior to the Start of Construction for a Stage of Work. The objective of the CTMP is to avoid, remedy or mitigate, as far as practicable, adverse construction traffic effects. To achieve this objective, the CTMP shall include: (i) methods to manage the effects of temporary traffic management activities on traffic; (ii) measures to ensure the safety of all transport users; (iii) the estimated numbers, frequencies, routes and timing of traffic movements, including any specific non-working or non-movement hours to manage vehicular and pedestrian traffic near schools or to manage traffic congestion; (iv) site access routes and access points for heavy vehicles, the size and location of parking areas for plant, construction vehicles and the vehicles of workers and visitors; (v) identification of detour routes and other methods to ensure the safe management and maintenance of traffic flows, including pedestrians and cyclists; (vi) methods to maintain access to property and/or private roads where practicable, or to provide alternative access arrangements when it will not be; (vii) the management approach to loads on heavy vehicles, including covering loads of fine material, the use of wheel-wash facilities at site exit points and the timely removal of any material deposited or spilled on public roads; (viii) methods that will be undertaken to communicate traffic management measures to affected road users (e.g. residents/public/stakeholders/emergency services); (ix) Auditing, monitoring and reporting requirements relating to traffic management activities shall be undertaken in accordance with the New Zealand Guide to Temporary Traffic Management or any subsequent version; (x) details of minimum network performance parameters to be achieved during the construction phase, including any measures to monitor compliance with the performance parameters; and					
All	19.	Construction Noise Standards (a) Construction noise shall be measured and assessed in accordance with NZS6803:1999 Acoustics – Construction Noise and shall comply with the noise standards set out in the following table as far as practicable: Table 19.1: Construction noise standards					
		Day of week Time period L _{Aeq(15min)} L _{AFmax}					
		Occupied activity sensitive to noise					







NoR No.	No.	Condition							
		Weekday		h - 0730h h - 1800h	55 dB 70 dB		75 d 85 d	· <u> </u>	
				h - 2000h	65 dB		80 d	IB	
			2000	h - 0630h	45 dB		75 d	IB	
		Saturday	0630	h - 0730h	55 dB		75 d	В	
			0730	h - 1800h	70 dB		85 d	В	
				h - 2000h	45 dB		75 d	_	
			2000	h - 0630h	45 dB		75 d	IB .	
		Sunday and Public		h - 0730h	45 dB		75 d	IB	
		Holidays		h - 1800h	55 dB		85 d		
				h - 2000h h - 0630h	45 dB 45 dB		75 d 75 d		
			20001	11 - 063011	45 UD		75 u	lD .	
		Other occupi	ied build	dings	ı				
		All	0730	h – 1800h	70 dB				
			1800h – 0730h						
								is not practicable, and gy in Condition 22	
All	20.	measuremen	vibration ibration a t of vibra tion stan	shall be meas and shock – Vi tions and evaludards set out i	bration of uation of the follon	of fixed structure	es – G struc	Guidelines for the stures and shall comply	
		Receiver		Details		Category A		Category B	
		Occupied Activi sensitive to nois		Night-time 20 0630h	000h -	0.3mm/s ppv		2mm/s ppv	
				Daytime 063 2000h	Oh -	2mm/s ppv		5mm/s ppv	
		Other occupied buildings		Daytime 063 2000h	Oh -	2mm/s ppv		5mm/s ppv	
		All other building	At all other times Tables 1 and		3 of D	DIN4150-3:1999			
		*Category A criteria adopted from Rule E25.6.30.1 of the AUP **Category B criteria based on DIN 4150-3:1999 building damage criteria for daytime (b) Where compliance with the vibration standards set out in Table CNV2 is not practical and unless otherwise provided for in the CNVMP as required by Condition 21(c)(x), the							
All	21.	the methodology in Condition 22 shall apply Construction Noise and Vibration Management Plan (CNVMP) (a) A CNVMP shall be prepared prior to the Start of Construction for a Stage of Work. (b) A CNVMP shall be implemented during the Stage of Work to which it relates.							







NoR		
No.	No.	Condition
	No.	(c) The objective of the CNVMP is to provide a framework for the development and implementation of the Best Practicable Option for the management of construction noise and vibration effects to achieve the construction noise and vibration standards set out in Conditions 19 and 20 to the extent practicable. To achieve this objective, the CNVMP shall be prepared in accordance with Annex E2 of the New Zealand Standard NZ56803:1999 /acoustics – Construction Noise' (NZ56803:1999) and shall as a minimum, address the following: (i) Description of the works and anticipated equipment/processes; (ii) Hours of operation, including times and days when construction activities would occur; (iii) The construction noise and vibration standards for the project; (iv) Identification of receivers where noise and vibration standards apply; (v) A hierarchy of management and mitigation options, including any requirements to limit night works and works during other sensitive times, including Sundays and public holidays as far practicable; (vi) Methods and frequency for monitoring and reporting on construction noise and vibration; (vii) Procedures for communication and engagement with nearby residents and stakeholders, including notification of proposed construction activities, the period of construction activities, and management of noise and vibration complaints. (viii) Contact details of the Project Liaison Person; (ix) Procedures for the regular training of the operators of construction equipment to minimise noise and vibration as well as expected construction site behaviours for all workers; (x) Identification of areas where compliance with the noise [Condition 19] and/or vibration standards [Condition 20, Category A or Category B] will not be practicable and the specific management controls to be implemented and consultation requirements with owners and occupiers of affected sites; (xi) Procedures and requirements for the preparation of a Schedule to the CNVMP (Schedule) for those areas where compliance with the noise [
		damage has occurred as a result of construction vibration; (xiv) Methodology and programme of desktop and field audits and inspections to be undertaken to ensure that CNVMP, Schedules and the best practicable option for management of effects are being implemented; and
		(xv) Requirements for review and update of the CNVMP
All	22.	Schedule to a CNVMP
		(a) Unless otherwise provided for in a CNVMP, a Schedule to the CNVMP (Schedule) shall be prepared prior to the start of the construction to which it relates by a Suitably Qualified Person, in consultation with the owners and occupiers of sites subject to the Schedule, when:
		 (i) Construction noise is either predicted or measured to exceed the noise standards in Condition 19, except where the exceedance of the L_{Aeq} criteria is no greater than 5 decibels and does not exceed:
		a. 0630 – 2000: 2 period of up to 2 consecutive weeks in any 2 months, or b. 2000 - 0630: 1 period of up to 2 consecutive nights in any 10 days.







NoR		
No.	No.	Condition
		(ii) Construction vibration is either predicted or measured to exceed the Category B standard at the receivers in Condition 20. (b) The objective of the Schedule is to set out the Best Practicable Option measures to manage noise and/or vibration effects of the construction activity beyond those measures set out in the CNVMP. The Schedule shall include details such as: (i) Construction activity location, start and finish dates; (ii) The nearest neighbours to the construction activity; (iii) The predicted noise and/or vibration level for all receivers where the levels are predicted or measured to exceed the applicable standards and predicted duration of the exceedance; (iv) The proposed mitigation options that have been selected, and the options that have been discounted as being impracticable and the reasons why; (v) The consultation undertaken with owners and occupiers of sites subject to the Schedule, and how consultation has and has not been taken into account; and (vi) Location, times and types of monitoring; (c) The Schedule shall be submitted to the Manager for certification at least 5 working days (except in unforeseen circumstances) in advance of Construction Works that are covered by the scope of the Schedule and shall form part of the CNVMP. (d) Where material changes are made to a Schedule required by this condition, the Requiring Authority shall consult the owners and/or occupiers of sites subject to the Schedule prior to submitting the amended Schedule to the Manager for certification in accordance with (c) above. The amended Schedule shall document the consultation undertaken with those owners and occupiers, and how consultation outcomes have and have not been taken into account.
All	23.	Historic Heritage Management Plan (HHMP) (a) A HHMP shall be prepared in consultation with Council, HNZPT and Mana Whenua prior to the Start of Construction for a Stage of Work. (b) The objective of the HHMP is to protect historic heritage and to remedy and mitigate any residual effects as far as practicable. To achieve the objective, the HHMP shall identify: (i) Any adverse direct and indirect effects on historic heritage sites and measures to appropriately avoid, remedy or mitigate any such effects, including a tabulated summary of these effects and measures; (ii) Methods for the identification and assessment of potential historic heritage places within the Designation to inform detailed design; (iii) Known historic heritage places and potential archaeological sites within the Designation, including identifying any archaeological sites for which an Archaeological Authority under the HNZPTA will be sought or has been granted; (iv) Any unrecorded archaeological sites or post-1900 heritage sites within the Designation, which shall also be documented and recorded; (v) Roles, responsibilities and contact details of Project personnel, Council and HNZPT representatives, Mana Whenua representatives, and relevant agencies involved with heritage and archaeological matters including surveys, monitoring of Construction Works, compliance with AUP accidental discovery rule, and monitoring of conditions; (vi) Specific areas to be investigated, monitored and recorded to the extent these are directly affected by the Project; (vii) The proposed methodology for investigating and recording post-1900 historic heritage sites (including buildings) that need to be destroyed, demolished or relocated, including details of their condition, measures to mitigate any adverse effects and timeframe for implementing the proposed methodology,







NoR		
No.	No.	Condition
NO.	NO.	Investigation and Recording of Buildings and Standing Structures (November 2018), or any subsequent version; (viii) Methods to acknowledge cultural values identified through Condition 9 where archaeological sites also involve ngā taonga tuku iho (treasures handed down by our ancestors) and where feasible and practicable to do so; (ix) Methods for avoiding, remedying or mitigating adverse effects on historic heritage places and sites within the Designation during Construction Works as far as practicable. These methods shall include, but are not limited to: a. security fencing or hoardings around historic heritage places to protect them from damage during construction or unauthorised access b. measures to mitigate adverse effects on historic heritage sites that achieve positive historic heritage outcomes such as increased public awareness and interpretation signage; and c. Training requirements and inductions for contractors and subcontractors on historic heritage places within the Designation, and legal obligations relating to accidental and/or unexpected discoveries, the AUP Accidental Discovery Rule (E11.6.1). The training shall be undertaken prior to the Start of Construction, under the guidance of a Suitably Qualified Person and Mana Whenua representatives (to the extent the training relates to cultural values identified under Condition 9. (c) Electronic copies of all historic heritage reports relating to historic heritage investigations (evaluation, excavation and monitoring), shall be submitted to the Manager within 12 months of completion. Accidental Discoveries Advice Note:
		The requirements for accidental discoveries of heritage items are set out in Rule E11.6.1 of the AUP
All	24.	Pre-Construction Ecological Survey (a) At the start of detailed design for a Stage of Work, an updated ecological survey shall be undertaken by a Suitably Qualified Person. The purpose of the survey is to inform the detailed design of the ecological management plan by: (i) Confirming whether the species of value within the Identified Biodiversity Areas recorded in the <i>Identified</i> Biodiversity <i>Area Schedule</i> [2] are still present; (ii) Confirming whether the project will or may have a moderate or greater level of ecological effect on ecological species of value, prior to implementation of impact management measures, as determined in accordance with the EIANZ guidelines. (b) If the ecological survey confirms the presence of ecological features of value in accordance with Condition 24(a)(i) and that effects are likely in accordance with Condition 24(a)(ii) then an Ecological Management Plan (or Plans) shall be prepared in accordance with Condition 25 for these areas (Confirmed Biodiversity Areas).
All	25.	Ecological Management Plan (EMP)
		(a) An EMP shall be prepared for any Confirmed Biodiversity Areas (confirmed through Condition 24) prior to the Start of Construction for a Stage of Work. The objective of the EMP is to minimise effects of the Project on the ecological features of value of Confirmed Biodiversity Areas as far as practicable. The EMP shall set out the methods that will be used to achieve the objective which may include:
NoR s 5, 6, 7, 8, 9, 10, 12,	25	 (b) If an EMP is required in accordance with (a) for the presence of long tail bats: (i) Measures to minimise as far as practicable, disturbance from construction activities within the vicinity of any active long tail bat roosts (including maternity) that are discovered through survey until such roosts are confirmed to be vacant of bats. (ii) How the timing of any construction work in the vicinity of any maternity long tail bat roosts will be limited to outside the bat maternity period (between December and March) where reasonably practicable;







NoR No.	No.	Condition
		 (iii) Details of areas where vegetation is to be retained where practicable for the purposes of the connectivity of long tail bats; (iv) Details of how bat connectivity will be provided and maintained (e.g. through the presence of suitable indigenous or exotic trees or artificial alternatives). (v) Details of measures to minimise any operational disturbance from light spill
NoR s 6, 7, 10	25	 (c) If an EMP is required in accordance with (a) for the presence of threatened or at risk birds (excluding wetland birds): (i) How the timing of any Construction Works shall be undertaken outside of the bird breeding season (September to February) where practicable; and (ii) Where works are required within the area identified in the Confirmed Biodiversity Area during the bird breeding season, methods to minimise adverse effects on Threatened or At-Risk birds.
NoR s 6, 7, 8, 9, 10, 11, 12, 13	25	 (d) If an EMP is required in accordance with (a) for the presence of threatened or at risk wetland birds: (i) How the timing of any Construction Works shall be undertaken outside of the bird breeding season (September to February) where practicable; (ii) Where works are required within the Confirmed Biodiversity Area during the bird season, methods to minimise adverse effects on Threatened or At-Risk wetland birds; (iii) Undertaking a nesting bird survey of Threatened or At-Risk wetland birds prior to any Construction Works taking place within a 50m radius of any identified Wetlands (including establishment of construction areas adjacent to Wetlands). Surveys should be repeated at the beginning of each wetland bird breeding season and following periods of construction inactivity; (iv) What protection and buffer measures will be provided where nesting Threatened or At-Risk wetland birds are identified within 50m of any construction area (including laydown areas). Measures could include: (v) A 20 m buffer area around the nest location and retaining vegetation. The buffer areas should be demarcated where necessary to protect birds from encroachment. This might include the use of marker poles, tape and signage; (vi) Monitoring of the nesting Threatened or At-Risk wetland birds. Construction works within the 20m nesting buffer areas should not occur until the Threatened or At-Risk wetland birds have fledged from the nest location (approximately 30 days from egg laying to fledging); (vii) Minimising the disturbance from the works if construction works are required within 50 m of a nest; (viii) Adopting a 10m setback where practicable, between the edge of Wetlands and construction areas (along the edge of the stockpile/laydown area); and (ix) Minimising light spill from construction areas into Wetlands
NoR s 6, 10	25	(x) Details of measures to minimise any operational disturbance from light spill.
NoR 9	25	 (e) If an EMP is required in accordance with (a) for the presence of native herpetofauna: (i) A description of the methodology and timing for survey, trapping and relocation of lizards rescued; (ii) A description of the relocation site(s), including: a. any measures to ensure the relocation site remains available; b. any weed and pest management to ensure the relocation site is maintained as appropriate habitat; (iii) A post vegetation clearance search for remaining lizards; and (iv) Any proposed monitoring.







NoR No.	No.	Condition
All	25	 (f) The EMP shall be consistent with any ecological management measures to be undertaken in compliance with conditions of any regional resource consents granted for the Project. Advice Note: Depending on the potential effects of the Project, the regional consents for the Project may include the following monitoring and management plans: a. Stream and/or wetland restoration plans; b. Vegetation restoration plans; and c. Fauna management plans (eg avifauna, herpetofauna, bats).
NoR	26.	Tree Management Plan
s 8, 9, 10, 13		 (a) Prior to the Start of Construction for a Stage of Work, a Tree Management Plan shall be prepared. The objective of the Tree Management Plan is to avoid, remedy or mitigate effects of construction activities on trees identified in Schedule 3. (b) The Tree Management Plan shall: (i) confirm that the trees listed in Schedule 3 still exist; and (ii) demonstrate how the design and location of project works has avoided, remedied or mitigated any effects on any tree listed in Schedule 3. This may include: a. Any opportunities to relocate listed trees where practicable; b. planting to replace trees that require removal (with reference to the ULDMP planting design details in Condition 11); c. tree protection zones and tree protection measures such as protective fencing, ground protection and physical protection of roots, trunks and branches; and d. methods for work within the rootzone of trees that are to be retained in line with accepted arboricultural standards. (iii) demonstrate how the tree management measures (outlined in a. – d. above) are consistent with conditions of any resource consents granted for the project in relation to managing construction effects on trees.
		 Network Utility Management Plan (NUMP) (a) A NUMP shall be prepared prior to the Start of Construction for a Stage of Work. (b) The objective of the NUMP is to set out a framework for protecting, relocating and working in proximity to existing network utilities. The NUMP shall include methods to: (i) Provide access for maintenance at all reasonable times, or emergency works at all times during construction activities; (iii) Protect and where necessary, relocate existing network utilities; (iiii) Manage the effects of dust and any other material potentially resulting from construction activities and able to cause material damage, beyond normal wear and tear to overhead transmission lines in the Project area; (iv) Demonstrate compliance with relevant standards and Codes of Practice including, where relevant, the NZECP 34:2001 New Zealand Electrical Code of Practice for Electrical Safe Distances 2001; AS/NZS 4853:2012 Electrical hazards on Metallic Pipelines. (c) The NUMP shall be prepared in consultation with the relevant Network Utility Operator(s) who have existing assets that are directly affected by the Project. (d) The development of the NUMP shall consider opportunities to coordinate future work programmes with other Network Utility Operator(s) where practicable. (e) The NUMP shall describe how any comments from the Network Utility Operator in relation to its assets have been addressed. (f) Any comments received from the Network Utility Operator shall be considered when finalising the NUMP. (g) Any amendments to the NUMP related to the assets of a Network Utility Operator shall be prepared in consultation with that asset owner.
All	28.	Network Integration Management Plan (NIMP)







NoR						
No.	No.	Condition				
		 (a) At least six (6) months prior to the start of detailed design for a Stage of Work, the Requiring Authority shall prepare, in collaboration with other relevant road controlling authorities, a Network Integration Management Plan (NIMP). (b) The objective of the NIMP is to identify how the Project will integrate with the planned transport network in the North growth area to achieve an effective, efficient and safe land transport system. To achieve this objective, the NIMP shall include details of the: (i) Project implementation approach and any staging of the Project, including both design, management and operational matters; and (ii) Sequencing of the Project with the planned transport network, including both design, management and operational matters 				
Opera	tional Co	onditions				
All	29.	 (a) Asphaltic concrete surfacing (or equivalent low noise road surface) shall be implemented within 12 months of Completion of Construction of the project. (b) Any future resurfacing works of the Project shall be undertaken in accordance with the Auckland Transport Reseal Guidelines, Asset Management and Systems 2013 and asphaltic concrete surfacing (or equivalent low noise road surface) shall be implemented where: (i) The volume of traffic exceeds 10,000 vehicles per day; or (ii) The road is subject to high wear and tear (such as cul de sac heads, roundabouts and main road intersections); or (iii) It is in an industrial or commercial area where there is a high concentration of truck traffic; or (iv) It is subject to high usage by pedestrians, such as town centres, hospitals, shopping centres and schools. (c) Prior to commencing any future resurfacing works, the Requiring Authority shall advise the Manager if any of the triggers in Condition 29(c)(i) – (iv) are not met by the road or a section of it and therefore where the application of asphaltic concrete surfacing (or equivalent low noise road surface) is no longer required on the road or a section of it. Such advice shall also indicate when any resealing is to occur. 				
All	N/A	Traffic Noise				
		 For the purposes of Conditions 30 to 35: (a) Building-Modification Mitigation – has the same meaning as in NZS 6806; (b) Design year has the same meaning as in NZS 6806; (c) Detailed Mitigation Options – means the fully detailed design of the Selected Mitigation Options, with all practical issues addressed; (d) Habitable Space – has the same meaning as in NZS 6806; (e) Identified Noise Criteria Category – means the Noise Criteria Category for a PPF identified in Schedule 4: Identified PPFs Noise Criteria Categories; (f) Mitigation – has the same meaning as in NZS 6806:2010 Acoustics – Road-traffic noise – New and altered roads; (g) Noise Criteria Categories – means the groups of preference for sound levels established in accordance with NZS 6806 when determining the Best Practicable Option for noise mitigation (i.e. Categories A, B and C); (h) NZS 6806 – means New Zealand Standard NZS 6806:2010 Acoustics – Road-traffic noise – New and altered roads; (i) Protected Premises and Facilities (PPFs) – means only the premises and facilities identified in green, orange or red in Schedule 4: PPFs Noise Criteria Categories; (j) Selected Mitigation Options – means the preferred mitigation option resulting from a Best Practicable Option assessment undertaken in accordance with NZS 6806 taking into account any low noise road surface to be implemented in accordance with Condition 29; and (k) Structural Mitigation – has the same meaning as in NZS 6806. 				







NoR No.	No.	Condition		
All	30.	The Noise Criteria Categories identified in <i>Schedule 4: PPFs Noise Criteria Categories</i> at each of the PPFs shall be achieved where practicable and subject to Conditions 30 to 35 (all traffic noise conditions).		
		The Noise Criteria Categories do not need to be complied with at a PPF where:		
		(a) The PPF no longer exists; or		
		(b) Agreement of the landowner has been obtained confirming that the Noise Criteria Category does not need to be met.		
		Achievement of the Noise Criteria Categories for PPFs shall be by reference to a traffic forecast for a high growth scenario in a design year at least 10 years after the programmed opening of the Project.		
AII	31.	As part of the detailed design of the Project, a Suitably Qualified Person shall determine the Selected Mitigation Options for the PPFs identified on <i>Schedule 4 PPFs Noise Criteria Categories</i> .		
		For the avoidance of doubt, the low noise road surface implemented in accordance with Condition 29 may be (or be part of) the Selected Mitigation Option(s).		
All	32.	Prior to construction of the Project, a Suitably Qualified Person shall develop the Detailed Mitigation Options for the PPFs identified in <i>Schedule 4 PPFs Noise Criteria Categories</i> , taking into account the Selected Mitigation Options.		
All	33.	If the Detailed Mitigation Options would result in the Identified Noise Criteria Category changing to a less stringent Category, e.g. from Category A to B or Category B to C, at any relevant PPF, a Suitably Qualified Person shall provide confirmation to the Manager that the Detailed Mitigation Option would be consistent with adopting the Best Practicable Option in accordance with NZS 6806 prior to implementation.		
All	34.	The Detailed Mitigation Options shall be implemented prior to completion of construction of the Project, with the exception of any low-noise road surfaces, which shall be implemented within twelve months of completion of construction.		
All	35.	The Detailed Mitigation Options shall be maintained so they retain their noise reduction performance as far as practicable		







Attachments

Schedule 1: General Accordance Plans and Information







<u>NoR 8</u>

Project Description

The proposed work is the construction, operation and maintenance of an upgrade to Dairy Flat Highway to an urban arterial corridor between Silverdale Interchange and Durey Road, Dairy Flat, including public transport and active transport facilities and associated infrastructure.

The proposed work is shown in the following Concept Plan and includes:


- Upgrading the corridor to an urban arterial with public transport and walking and cycling facilities.
- Tie-ins with existing roads and localised widening around the existing intersections to accommodate new intersection forms.
- New or upgraded stormwater management systems, bridges and culverts (where applicable).
- Batter slopes, and associated cut and fill activities (earthworks).
- Vegetation removal.
- Other construction related activities required outside the permanent corridor including the regrade of driveways, construction traffic manoeuvring and construction laydown areas.

NOR Concept Plan
















Schedule 2: Identified Biodiversity Areas








NOR 8


























Schedule 3: Trees to be included in the Tree Management Plan








NOR 8

Tree number	Vegetation type	Protection	Location	Species	Age
805	Single tree	Open space	4 Postman Road	Chinese Poplar (Populus chinensis)	Semi- mature
806	Hedge	Open space	4 Postman Road	Titoki (Alectryon excelsus), Tarata (Pittosporum tenuifolium) Bottlebrush (Callistemon sp.) Oleander	Semi- mature
807	Hedge	Open space	4 Postman Road	Leyland Cypress (Cupressus x leylandii), weed species	Semi- mature















Schedule 4: Identified PPFs Noise Criteria Categories







NOR 8

Address	New or Altered Road	Noise Criteria Category
1686 Dairy Flat Highway	Altered	A
1680 Dairy Flat Highway	Altered	A
1321 Dairy Flat Highway	Altered	A
1349 Dairy Flat Highway	Altered	A
1338 Dairy Flat Highway	Altered	A
1008 Dairy Flat Highway	Altered	A
12 Durey Road	Altered	A
1564A Dairy Flat Highway	Altered	A
1570 Dairy Flat Highway	Altered	A
1258 Dairy Flat Highway	Altered	A
1306 Dairy Flat Highway	Altered	A
1284 Dairy Flat Highway	Altered	A
1286 Dairy Flat Highway	Altered	A
2 Horseshoe Bush Road	Altered	A
1285 Dairy Flat Highway	Altered	A
957 Dairy Flat Highway	Altered	A
1731 Dairy Flat Highway	Altered	A
1424 Dairy Flat Highway	Altered	A
1361 Dairy Flat Highway	Altered	A
1452 Dairy Flat Highway	Altered	А
41 Durey Road	Altered	A
1315 Dairy Flat Highway	Altered	A
1182 Dairy Flat Highway	Altered	A







Address	New or Altered Road	Noise Criteria Category
11 Durey Road	Altered	А
1700 Dairy Flat Highway	Altered	А
825 Dairy Flat Highway	Altered	A
1355 Dairy Flat Highway	Altered	A
1584 Dairy Flat Highway	Altered	A
5 Postman Road	Altered	A
4 Lascelles Drive	Altered	A
25 Lynwood Grove	Altered	A
1 Richards Road	Altered	A
1636 Dairy Flat Highway	Altered	А
1596 Dairy Flat Highway	Altered	A
1646 Dairy Flat Highway	Altered	A
17 Lower Jeffs Road	Altered	A
1550 Dairy Flat Highway	Altered	А
859 Dairy Flat Highway	Altered	A
1215 Dairy Flat Highway	Altered	A
16 Durey Road	Altered	A
1016 Dairy Flat Highway	Altered	A
18 Wilks Road West	Altered	A
1005A Dairy Flat Highway	Altered	A
956 Dairy Flat Highway	Altered	A
15 Wilks Road	Altered	A
1615 Dairy Flat Highway	Altered	A
12 Postman Road	Altered	А







Address	New or Altered Road	Noise Criteria Category
1153 Dairy Flat Highway	Altered	A
1564 Dairy Flat Highway	Altered	A
1006 Dairy Flat Highway	Altered	A
1250 Dairy Flat Highway	Altered	A
18 Langford Place	Altered	A
27 Green Road	Altered	A
22 Langford Place	Altered	A
18 Green Road	Altered	A
20 Jeffs Road	Altered	A
883 Dairy Flat Highway	Altered	A
792 Dairy Flat Highway	Altered	A
1617 Dairy Flat Highway	Altered	A
9 Lower Jeffs Road	Altered	A
6 Lynwood Grove	Altered	A
6 Kennedy Road	Altered	A
7 Lower Jeffs Road	Altered	A
851 Dairy Flat Highway	Altered	A
16 Langford Place	Altered	А
55 Kennedy Road	Altered	A
1327 Dairy Flat Highway	Altered	A
2 Lynwood Grove	Altered	A
1412 Dairy Flat Highway	Altered	A
22 Lynwood Grove	Altered	A
1579A Dairy Flat Highway	Altered	A







Address	New or Altered Road	Noise Criteria Category
31 Green Road	Altered	А
1602A Dairy Flat Highway	Altered	A
1660 Dairy Flat Highway	Altered	A
16 Lynwood Grove	Altered	A
38 Jeffs Road	Altered	A
26 Langford Place	Altered	A
20 Langford Place	Altered	А
987 Dairy Flat Highway	Altered	А
1349A Dairy Flat Highway	Altered	А
6 Langford Place	Altered	А
823 Dairy Flat Highway	Altered	А
1236 Dairy Flat Highway	Altered	А
1623 Dairy Flat Highway	Altered	А
19 Richards Road	Altered	А
21 Postman Road	Altered	A
28 Lynwood Grove	Altered	А
785 Dairy Flat Highway	Altered	А
1005 Dairy Flat Highway	Altered	А
841 Dairy Flat Highway	Altered	А
32 Jeffs Road	Altered	A
26 Lynwood Grove	Altered	A
1602 Dairy Flat Highway	Altered	A
918 Dairy Flat Highway	Altered	A
1414 Dairy Flat Highway	Altered	А







Address	New or Altered Road	Noise Criteria Category
1270B Dairy Flat Highway	Altered	A
807 Dairy Flat Highway	Altered	A
14 Blackbridge Road	Altered	A
18 Kennedy Road	Altered	A
22 Postman Road	Altered	A
15 Lower Jeffs Road	Altered	A
851B Dairy Flat Highway	Altered	А
1491 Dairy Flat Highway	Altered	А
1326 Dairy Flat Highway	Altered	А
30 Wilks Road	Altered	А
11 Lascelles Drive	Altered	А
1687 Dairy Flat Highway	Altered	А
1509 Dairy Flat Highway	Altered	А
10 Lascelles Drive	Altered	А
1248 Dairy Flat Highway	Altered	A
1487 Dairy Flat Highway	Altered	А
1667 Dairy Flat Highway	Altered	А
17 Kahikatea Flat Road	Altered	А
19 Kennedy Road	Altered	А
958 Dairy Flat Highway	Altered	А
11 Jeffs Road	Altered	А
28 Blackbridge Road	Altered	A
1198A Dairy Flat Highway	Altered	А
10 Bawden Road	Altered	А







Address	New or Altered Road	Noise Criteria Category
34 Lascelles Drive	Altered	A
1448 Dairy Flat Highway	Altered	A
989 Dairy Flat Highway	Altered	A
785 Dairy Flat Highway	Altered	A
24 Goodland Drive	Altered	A
8 Kennedy Road	Altered	A
934 Dairy Flat Highway	Altered	A
37 Whiteways Drive	Altered	A
1416 Dairy Flat Highway	Altered	A
1256 Dairy Flat Highway	Altered	A
28 Lascelles Drive	Altered	A
20 Kennedy Road	Altered	A
1428 Dairy Flat Highway	Altered	A
1455 Dairy Flat Highway	Altered	A
32 Langford Place	Altered	A
9 Goodland Drive	Altered	A
31 Wilks Road West	Altered	A
25 Postman Road	Altered	A
19 Langford Place	Altered	A
1014 Dairy Flat Highway	Altered	A
36 Blackbridge Road	Altered	A
9 Langford Place	Altered	A
24 Lynwood Grove	Altered	A
29 Langford Place	Altered	А







Address	New or Altered Road	Noise Criteria Category
1198C Dairy Flat Highway	Altered	А
38 Wilks Road West	Altered	A
30 Wilks Road West	Altered	А
1440 Dairy Flat Highway	Altered	А
783 Dairy Flat Highway	Altered	А
1444 Dairy Flat Highway	Altered	А
26 Postman Road	Altered	А
12 Kahikatea Flat Road	Altered	А
1432 Dairy Flat Highway	Altered	А
10 Kahikatea Flat Road	Altered	А
16 Kahikatea Flat Road	Altered	A







