

**Appendix A:**  
**Site Location and Aerial Photo**  
**Utilities location plans**






Date Printed:  
24/05/2021

**DISCLAIMER:** This map/plan is illustrative only and all information should be independently verified on site before taking any action. Copyright: Auckland Council. Land Parcel Boundary Information from LINZ (Grown Copyright Reserved). Whilst due care has been taken, Auckland Council gives no warranty as to the accuracy and plan completeness of any information on this map/plan and accepts no liability for any error, omission or use of the information. Height datum: Auckland 1946





## DISCLAIMER:

This map/plan is illustrative only and all information should be independently verified on site before taking any action. Copyright Auckland Council. Land Parcel Boundary information from LINZ (Crown Copyright Reserved). Whilst due care has been taken, Auckland Council gives no warranty as to the accuracy and plan completeness of any information on this map/plan and accepts no liability for any error, omission or use of the information. Height datum: Auckland 1946.

## 36A Eaglehurst Road

0 100 200 300  
Meters


Scale @ A4  
= 1:15,000

Date Printed:  
24/05/2021









# Watercare

An Auckland Council Organisation

Sequence Number: 9392594

Address: 36A Eaglehurst Road  
Ellerslie, Auckland, 1060



- Waste Water
- Water
- Electrical/Cathodic Protection
- Waste Water Proposed
- Water Proposed

- V Valve
- H Hydrant
- M Water Meter
- ⊙ Manhole

Scale: 1:1000



Watercare Services Ltd accepts no responsibility for incomplete or inaccurate information contained on this map. Use of this data is subject to, and constitutes acceptance of the conditions set out in our disclaimer. Topographic information is derived from Land Information New Zealand, CROWN COPYRIGHT RESERVED.

**OVERVIEW NOT TO SCALE.**




WARNING: Buried services are widespread and it should be assumed that they are present until it is proven otherwise.  
Cables should be expected to be found at ANY depth.  
In most instances Chorus plans do NOT show house service feeds on private property.  
Refer to cover letter provided with your request for additional information use all plans provided in conjunction with each other.  
You are responsible for interpreting the information provided and should refer to Worksafe.govt.nz for the 'Guide for safety with underground services'  
For assistance contact Chorus Network Protection on 0800 822 003 or if you suspect damage has occurred contact 0800 463 896 opt 2




Plan Name	Gold
Plan ID	
Version	
Current at	24/05/2021









© Vector Limited. This plan is the property of Vector Limited. All rights reserved. The contents of this document may not be reproduced either in whole or in part by any means whatsoever without the prior written consent of Vector Limited.

**WARNING! Special conditions apply for high pressure gas pipelines (HP Pipe, IP20, IP10, MP7)**

A permit/consent is required for any excavation within 2 metres of this pipeline. A MINIMUM of 3 working days notice is required when applying for a permit/consent. Refer to attached covering letter for additional information.

**DISCLAIMER:** Whilst care has been taken in the preparation of this plan, Vector Limited and its subsidiaries do not accept any liability for its accuracy and completeness and do not make any representation or warranty, express or implied, in relation to the same. These drawings are not to scale and may not show customer connections or obsolete lines. Works may have occurred in the vicinity which may not be represented in this plan at the date of issue. The information contained in this plan is supplied for reference purposes only; actual dimensions and locations on site may differ from those indicated. Without limiting the foregoing, where plans are more than 28 days old they should not be used; a new plan should be requested from Vector.

**Vector reminds you of your responsibilities under the Health and Safety at Work Act 2015, whereby you must establish the location of underground services before commencing excavation.**

If you hit an electricity cable or overhead line please call us immediately on 0508 VECTOR (0508 832 867). If you hit any gas pipeline call the Fire Service first on 111. If you hit a gas distribution pipe in the Auckland area call us on 0800 764 764. If you hit a gas pipeline in the rest of the North Island call FIRST GAS on 0800 800 393. If you hit a gas transmission pipeline call FIRST GAS on 0800 734 567. If you hit a communications cable (all areas) call us immediately on 0800 826 436 (select option 1).

<b>Title:</b>	
Request Title:	
Company Name:	
Usage:	Request ID: 9392596
Request for:	Scale: 1:400
Customer Contact:	Printed by:
Phone:	Date printed: 24. May 2021
Client Reference:	Page: 3 of 4

**PIPE COLOUR BY PRESSURE**

- LP Pipe
- LPG Pipe
- MP1 Pipe
- MP2 Pipe
- MP4 Pipe
- MP7 Pipe
- IP10 Pipe
- IP20 Pipe
- HP Pipe
- 0 kPa

**WARNING! Live service within this property.**

**WORK MANAGEMENT**


- In Progress
- On Hold
- Planned

**WARNING! Indication only additional data is required**

Transmission Pipeline (ex - NGC)  
Please contact Vector - New Plymouth on 0800 734 567 for On-Site Location and Work Permits. A minimum of 48 hours notice is required.


**OTHER GAS FEATURES**

- Fibre Optic
- Gate
- PRS
- Closed Valve
- Open Valve
- Reducer
- Riser
- Service Regulator






Plan Name	Z72
Plan ID	87670
Version	HF
Current at	24/05/2021



Z72


Re-Order Filemaster "D"  
REORDER FILEMASTER "D"  
REORDER FILEMASTER "D"



DATE TO BE EXERCISED WHEN WORKING IN THE VICINITY OF THE NOTED PORTION OF CABLE	DATE TO BE EXERCISED WHEN WORKING IN THE VICINITY OF THE NOTED PORTION OF CABLE
DATE TO BE EXERCISED WHEN WORKING IN THE VICINITY OF THE NOTED PORTION OF CABLE	DATE TO BE EXERCISED WHEN WORKING IN THE VICINITY OF THE NOTED PORTION OF CABLE
DATE TO BE EXERCISED WHEN WORKING IN THE VICINITY OF THE NOTED PORTION OF CABLE	DATE TO BE EXERCISED WHEN WORKING IN THE VICINITY OF THE NOTED PORTION OF CABLE
DATE TO BE EXERCISED WHEN WORKING IN THE VICINITY OF THE NOTED PORTION OF CABLE	DATE TO BE EXERCISED WHEN WORKING IN THE VICINITY OF THE NOTED PORTION OF CABLE


A3000  
Z72





**CABLE COLOUR CODE**  
CABLES IN USE  
110,000 - 22,000 volt subtransmission  
22,000 volt  
11,000 - 6,600 volt  
400 volt  
Streetlight  
Pilot / Fibre Optic  
CABLES NOT IN USE  
110,000 - 22,000 volt subtransmission  
22,000 volt  
11,000 - 6,600 volt  
400 volt  
Streetlight  
Pilot / Fibre Optic  
JOINTS & SEALING ENDS  
110,000 - 22,000 volt subtransmission  
22,000 volt  
11,000 - 6,600 volt  
400 volt  
Streetlight  
Pilot / Fibre Optic  
NOT IN USE

**SYMBOL LEGEND**  
TUNNEL  
DUCT BANK  
FIBRE OPTIC DUCT  
TRENCH  
PILLAR  
PIT  
DISTRIBUTION SUBSTATION  
POLES  
LAMP  
CESSPIT  
MANHOLE  
FIRE HYDRANT  
DRAIN  
FIBRE OPTIC PIT  
EARTHWIRE & RODS  
DUCT CROSS SECTIONS mm  
25 50 80 100 150  
200 250 300  
WORK MANAGEMENT  
IN PROGRESS  
ON HOLD  
PLANNED



© Vector Limited. This plan is the property of Vector Limited. "Vector" and the "V device" are registered trade marks of Vector Limited. All rights reserved. The contents of this document may not be reproduced either in whole or in part by any means whatsoever without the prior written consent of Vector Limited.

**22kV, 33kV, 110kV SUB TRANSMISSION CABLES-SPECIAL CONDITIONS APPLY:**  
Vector Limited provides a free standover service that requires 2 working days notice. Hand digging is required when excavating within 1 metre of the cable. Replacement trench backfill material must be the same as that removed and it must be replaced to the same level of compaction. Refer to attached covering letter for additional information.

**DISCLAIMER:** Whilst care has been taken in the preparation of this plan, Vector Limited and its subsidiaries do not accept any liability for its accuracy and completeness and do not make any representation or warranty, express or implied, in relation to the same. These drawings are not to scale and may not show customer connections or obsolete lines. Works may have occurred in the vicinity which may not be represented in this plan at the date of issue. The information contained in this plan is supplied for reference purposes only; actual dimensions and locations on site may differ from those indicated. Without limiting the foregoing, where plans are more than 28 days old they should not be used; a new plan should be requested from Vector.

**Vector reminds you of your responsibilities under the Health and Safety at Work Act 2015, whereby you must establish the location of underground services before commencing excavation.**

If you hit an electricity cable or overhead line please call us immediately on 0508 VECTOR (0508 832 867). If you hit any gas pipeline call the Fire Service first on 111. If you hit a gas distribution pipe in the Auckland area call us on 0800 764 764. If you hit a gas pipeline in the rest of the North Island call FIRST GAS on 0800 800 393. If you hit a gas transmission pipeline call FIRST GAS on 0800 734 567. If you hit a communications cable (all areas) call us immediately on 0800 826 436 (select option 1).

<b>Title:</b>	
Request Title:	
Company Name:	
Usage:	Request ID: 9392595
Request for:	Scale: 1:400
Customer Contact:	Printed by: swadmin
Phone:	Date printed: 24. May 2021
Client Reference:	Page: 3 of 4

**A3 ELECTRICITY OBSTRUCTION PLAN**






## **Appendix B:**

### **Scheme Plan and Architectural Plans**





EAGLEHURST ROAD

LOT 1  
DP 167980

### MEMORANDUM OF EASEMENTS

PURPOSE	SHOWN	SERVIENT TENEMENT	DOMINANT TENEMENT
PARTY WALL	A	LOT 1	LOT 2
	B	LOT 2	LOT 1
	C	LOT 2	LOT 3
	D	LOT 3	LOT 2
	E	LOT 3	LOT 4
	F	LOT 4	LOT 3
	H	LOT 5	LOT 6
	I	LOT 6	LOT 5
	J	LOT 6	LOT 7
	K	LOT 7	LOT 6
	L	LOT 7	LOT 8
	M	LOT 8	LOT 7
	N	LOT 8	LOT 9
	O	LOT 9	LOT 8
	P	LOT 9	LOT 10
	Q	LOT 10	LOT 9
	R	LOT 10	LOT 11
	S	LOT 11	LOT 10
	T	LOT 11	LOT 12
	U	LOT 12	LOT 11
PARKING	V	LOT 13	LOT 14
	W	LOT 14	LOT 13
	X	LOT 14	LOT 15
	Y	LOT 15	LOT 14
	Z	LOT 15	LOT 16
	AA	LOT 16	LOT 15
	AB	LOT 16	LOT 17
	AC	LOT 17	LOT 16
	AD	LOT 17	LOT 18
	AE	LOT 18	LOT 17
	AF	LOT 18	LOT 19
	AG	LOT 19	LOT 18
	AH	LOT 20	LOT 1
	AI	LOT 20	LOT 2
	AJ	LOT 20	LOT 3
	AK	LOT 20	LOT 4
	AL	LOT 20	LOT 5
	AM	LOT 20	LOT 6
	AN	LOT 20	LOT 7
	AO	LOT 20	LOT 8
	AP	LOT 20	LOT 9
RIGHT TO DRAIN WATER	AQ	LOT 20	LOT 10
	AR	LOT 20	LOT 11
	AS	LOT 20	LOT 12
	AT	LOT 20	LOT 13
	AU	LOT 20	LOT 14
	AV	LOT 20	LOT 15
	AW	LOT 20	LOT 16
	AX	LOT 20	LOT 17
	AY	LOT 20	LOT 18
	AZ	LOT 20	LOT 19
	BE	LOT 20	LOT 1
	BF	LOT 20	LOT 2
	BG	LOT 20	LOT 3
	BH	LOT 20	LOT 4
	BI	LOT 20	LOT 5

### MEMORANDUM OF EASEMENTS

PURPOSE	SHOWN	SERVIENT TENEMENT	DOMINANT TENEMENT
RIGHT TO DRAIN WATER	BJ	LOT 20	LOT 6
	BJ	LOT 20	LOT 7
	BL	LOT 20	LOT 8
	BM	LOT 20	LOT 9
	BN	LOT 20	LOT 10
	BO	LOT 20	LOT 11
	BP	LOT 20	LOT 12
	BQ	LOT 20	LOT 13
	BR	LOT 20	LOT 14
	BA	LOT 21	LOTS 1 - 20
RIGHT OF WAY	BC	LOT 20	LOTS 1 - 19
	G	LOT 20	LOT 21
EAVE OVERHANG & MAINTENANCE	BB	LOT 20	LOT 1
	G	LOT 20	LOT 1

### SCHEDULE OF EASEMENT IN GROSS

PURPOSE	SHOWN	SERVIENT TENEMENT	DOMINANT TENEMENT
RIGHT TO CONVEY TELECOMMUNICATIONS	G		
	BB	LOT 20	CHORUS NEW ZEALAND LIMITED
	BC		
	BD		

#### AMALGAMATION CONDITIONS

THAT LOT 20 BE HELD AS TO 19 UNDIVIDED ONE - NINETEENTH SHARE BY THE OWNERS OF LOTS 1 - 19 HERE AS TENANT IN COMMON IN THE SAID SHARES AND THAT THE INDIVIDUAL COMPUTER REGISTERS BE ISSUED IN ACCORDANCE THEREWITH.

SURVEYED			APPROVED BY	DATE
DESIGNED			JM	03/06/21
DRAWN	CJ	05/21		
TRACED				
CHECKED				
REVISION	CHANGES		CHECKED	DATE
	ORIGINAL			12/20
A	TEXT, EMNT, SCHEDULE CHANGED		JM	05/21
B	TEXT, EMNT, SCHEDULE CHANGED		JM	06/21

- NOTES
- LEVELS ARE IN TERMS OF AUCKLAND VERTICAL DATUM (MSL) 1946
  - COORDINATES ARE IN TERMS OF GEODETIC DATUM MOUNT EDEN 2000 CIRCUIT
  - CONTOURS ARE AT 0.50m INTERVALS
  - COMPRISED IN RT NA101D/827
  - RECORD OF TITLE AREA 3342m<sup>2</sup>
  - LOCAL AUTHORITY - AUCKLAND COUNCIL
  - PROPERTY BOUNDARIES HAVE BEEN SOURCED FROM THE LINZ SPATIAL DATABASE AND ARE ACCURATE FOR TOPOGRAPHICAL PURPOSES ONLY. WHERE CRITICAL, BOUNDARY DIMENSIONS SHOULD BE CONFIRMED BY LAND TRANSFER SURVEY.
  - CERTAIN DRAINAGE AND UNDERGROUND SERVICE INFORMATION HAS BEEN PLOTTED FROM SERVICE PROVIDERS RECORDS, LOCATION SHOULD BE VERIFIED ON SITE.
  - WHERE THE RELATIONSHIP OF A PROPOSED BUILDING TO COUNCIL'S HEIGHT TO BOUNDARY CONTROL RULES BECOMES CRITICAL FURTHER GROUND LEVELS SHOULD BE TAKEN ON THE BOUNDARY ADJACENT TO THE CRITICAL POSITION(S)
  - THESE NOTES ARE AN INTEGRAL PART OF THIS PLAN.

APEXONE LTD

36A EAGLEHURST ROAD  
ELLERSLIE  
AUCKLAND

SCHEME PLAN  
LOT 2 DP 167980

**Barry Satchell**

ENGINEERS SURVEYORS PLANNERS

60 NEW NORTH ROAD, EDEN TERRACE  
PO BOX 10-343  
DOMINION ROAD  
AUCKLAND  
TEL: +64-9-623-4573  
WEB: www.bscl.co.nz

THE COPYRIGHT OF THIS DESIGN AND DRAWING IS VESTED IN BARRY SATCHELL CONSULTANTS LTD, UNLESS OTHERWISE INDICATED.

CAD Ref: P/8149/CAD/813 151  
XREFS:

STATUS  
STAMP FOR RESOURCE AND BUILDING CONSENT

JOB NO.	DRAWING No.	REVISION
8149	151 SHT 1 OF 1	B





Address 36A Eaglehurst Road Ellerslie Auckland 1060  
Legal Description Lot 2 DP 167980  
Zone Mixed Housing Suburban Zone  
Wind Zone Low Wind Zone

MIXED HOUSING SUBURBAN ZONE																				
	LOT 1		LOT 2		LOT 3		LOT 4		LOT 5		LOT 6		LOT 7		LOT 8		LOT 9		LOT 10	
	(m²)	(%)	(m²)	(%)	(m²)	(%)	(m²)	(%)	(m²)	(%)	(m²)	(%)	(m²)	(%)	(m²)	(%)	(m²)	(%)	(m²)	(%)
SITE AREA (m²)	72	-	71	-	71	-	95	-	92	-	78	-	78	-	78	-	78	-	78	-
SITE COVERAGE (m²)	43	59.7%	43	60.6%	43	60.6%	43	45.3%	44	47.8%	44	56.4%	48	61.5%	48	61.5%	47	60.3%	48	61.5%
IMPERMEABLE (m²)	43	59.7%	43	60.6%	43	60.6%	43	45.3%	44	47.8%	44	56.4%	48	61.5%	48	61.5%	47	60.3%	48	61.5%
LANDSCAPE (m²)	29	40.3%	28	39.4%	28	39.4%	52	54.7%	46	50.0%	32	41.0%	30	38.5%	30	38.5%	32	41.0%	30	38.5%

MIXED HOUSING SUBURBAN ZONE																				
	LOT 11		LOT 12		LOT 13		LOT 14		LOT 15		LOT 16		LOT 17		LOT 18		LOT 19		LOT 20	
	(m²)	(%)	(m²)	(%)	(m²)	(%)	(m²)	(%)	(m²)	(%)	(m²)	(%)	(m²)	(%)	(m²)	(%)	(m²)	(%)	(m²)	(%)
SITE AREA	78	-	98	-	98	-	78	-	78	-	78	-	78	-	78	-	104	-	1225	-
SITE COVERAGE (m²)	48	61.5%	47	48.0%	47	48.0%	48	61.5%	48	61.5%	47	60.3%	48	61.5%	48	61.5%	47	45.2%	-	-
IMPERMEABLE (m²)	48	61.5%	47	48.0%	47	48.0%	48	61.5%	48	61.5%	47	60.3%	48	61.5%	48	61.5%	47	45.2%	769	62.8%
LANDSCAPE (m²)	30	38.5%	52	53.1%	52	53.1%	30	38.5%	30	38.5%	52	66.7%	30	38.5%	30	38.5%	58	55.8%	325	26.5%

LIGHT INDUSTRY ZONE		
	LOT 21	
	(m <sup>2</sup> )	(%)
SITE AREA	558	-
SITE COVERAGE	-	-
IMPERMEABLE	87	15.6%
LANDSCAPE	471	84.4%

MHS ZONE		
	OVERALL	
	(m <sup>2</sup> )	(%)
SITE AREA	2784	-
SITE COVERAGE	879	31.6%
IMPERMEABLE	1648	59.2%
LANDSCAPE	1026	36.9%
FRONT YARD AREA	99	-
FRONT YARD LANDSCAPE AREA	80	80.8%


- LEGEND
- EXPOSED AGGREGATE CONCRETE DRIVEWAY, BLACK OXIDE
  - SHARED FOOTPATH, PERMEABLE CONCRETE PAVEMENT, GREY COLOUR
  - STEPPING STONE CONCRETE PAVEMENT FOOTPATH 400MM OVERALL WIDE
  - RUBBISH BIN



## **Appendix C:**

# **Stormwater Soakage Results and Calculations**











**Hole No: SH 021**  
**Hole Dia: 100mm**  
**Hole Loc: Per Plan**  
**Cased to: 3.0 mtrs**

**RCK: 0.0m - 0.3m**  
**SL: 0.3m - 1.8m**  
**SC: 1.8m - 2.0m**  
**RCK: 2.0m - 4.3m**  
**SC: 4.3m - 4.6m**  
**RCK: 4.6m - 20.0m**  
**E.O.H**

**Flow Rate: 6.1 L/sec**  
**Test Method: Truck**  
**Water Vol: 3660 L**  
**Duration: 10min**  
**Presoak 10min: 4200 L**  
**Truck at max flow**

**Hole No: SH 022**  
**Hole Dia: 100mm 10° Angle**  
**Hole Loc: Per Plan**  
**Cased to: 3.0 mtrs**

**F: 0.0m - 0.4m**  
**RCK (Stoney): 0.4m - 1.2m**  
**RCK (Brown): 1.2m - 6.2m**  
**SC: 6.2m - 6.3m**  
**RCK: 6.3m - 20.0m**  
**CLY: 20.0m - 20.5m**  
**E.O.H.**

**Flow Rate: < 2.0 L/sec**  
**Test Method: Truck**  
**Water Vol: N/A**  
**Duration: N/A**  
**Presoak 10min: N/A**  
**Truck at max flow**

**Hole No: SH 023**  
**Hole Dia: 100mm**  
**Hole Loc: Per Plan**  
**Cased to: 3.0 mtrs**

**RCK (Gravely): 0.0m - 1.3m**  
**RCK: 1.3m - 2.7m**  
**SC: 2.7m - 2.9m**  
**RCK: 2.9m - 5.0m**  
**SC: 5.0m - 5.1m**  
**RCK: 5.1m - 20.0m**  
**SLT/W: 20.0m - 21.0m**  
**E.O.H**

**Flow Rate: 2.6 L/sec**  
**Test Method: Truck**  
**Water Vol: 1560 L**  
**Duration: 10min**  
**Presoak 10min: 1900 L**  
**Truck at max flow**

**Note: SH2, SH 021, SH023 Simultaneously Flow Tested**



**SOAKHOLE DRILLING**  
**SITE REPORT**[www.niedererdrilling.co.nz](http://www.niedererdrilling.co.nz)

5/143 Cavendish Dr Manukau

PO Box 98878 Manukau City, Auckland 2241

[niedererdrilling@xtra.co.nz](mailto:niedererdrilling@xtra.co.nz)

Ph: 09 2783108

**Client:** NZ Archiland  
**Attn:** Dylan Huang  
**Ph:** 021 1309828  
**email:** [archiland.nz@gmail.com](mailto:archiland.nz@gmail.com)

**Consultant:** Barry Satchell  
**Attn:** Peter Garriock  
**email:** [pgarriock@bscl.co.nz](mailto:pgarriock@bscl.co.nz)  
**Ph:** 022 192 6727

**Site:** 36a Eaglehurst Road  
Ellerslie

**Date:** 17/18 - 03-2021

A = Ash  
C = Cavities  
CH = Chamber  
CLY = Clay  
CRT = Concrete  
F = Fill  
F-R = Fractured Rock  
GVL = Gravels  
M-CLY = Marine Clay  
RCK = Basalt Rock  
SC = Scoria  
SL = Soils  
SLT = Silts  
T = Tuff  
V/s = Void/s  
W = Water  
E.O.H. = End of Hole

**Rockbore Soakhole**

**Hole No:** SH 01  
**Hole Dia:** 100mm  
**Hole Loc:** Marked on Site  
13.5 mtrs from Front of Boundary  
4.7 mtrs from Left Boundary  
**Cased to:** 3.0 mtrs

**SL:** 0.0m - 0.4m  
**RCK:** 1.0m - 18.5m  
**SC:** 18.5m 19.5m  
**RCK (Lightly F-R, Wet):** 19.5m - 20.5m  
**E.O.H**

**Flow Rate:** 3.1 L/sec  
**Test Method:** Truck  
**Water Vol:** 1860 L  
**Duration:** 10min  
**Presoak 10min:** 1860 L

**Hole No:** SH 02  
**Hole Dia:** 100mm - Angled  
**Hole Loc:**  
23.0 mtrs from Front Boundary  
3.4 mtrs from Left Boundary  
**Cased to:** 3.0 mtrs

**SL:** 0.0m - 0.4m  
**RCK:** 0.4m - 0.6m  
**F-R:** 0.6m - 0.7m  
**RCK:** 0.7m - 2.7m  
**SC:** 2.7m - 2.8m  
**RCK:** 2.8m - 4.5m  
**RCK (Scoriaceous):** 4.5m - 7.3m  
**RCK:** 7.3m - 18.0m  
**F-R/SL(Wet):** 18.0m - 20.0m  
**E.O.H.**

**Flow Rate:** 27.0 L/sec  
**Test Method:** Truck  
**Water Vol:** 16200 L  
**Duration:** 10min  
**Presoak 10min:** 5500 L  
**Truck at max flow**



## WORKSHEET 2. CONSTANT-HEAD PERCOLATION TEST

Site Address: 36a Eaglehurst Road, Ellerslie

Completed by: Peter Garriock

Date of test: 09.04.21

Signature: \_\_\_\_\_

## Attach the following:

- ☒ Log of borehole showing depth, geological layers and water table  
☒ Site-plan showing the location of the hole  
 (tick when attached)

- ☐ Civil Engineer  
☒ Engineering Technician  
☐ Engineering Geologist  
 (tick one)

## Ensure the following procedures are followed:

- ☒ A permit is obtained from Metrowater  
☒ Hole is pre-soaked for 10 minutes prior to test  
☒ Test is continued for 10 to 15 minutes  
☒ Rockbores are maintained full  
☐ Testpits are maintained ½ full  
☒ Bores within 10m of each other are tested simultaneously  
☐ Borehole drilling is attempted before constructing a testpit  
 (tick when complete)

## 3. Test Details

Time	Flowrate (L/s)
10m	27L/s

Time	Flowrate (L/s)

## 4. Determine capacity of rockbore/testpit :

$$(a) \text{ Capacity of bore} = P_2 = \frac{\text{Flowrate}^*}{1.3} = \frac{20.8}{1.3} = \underline{\hspace{2cm}} \text{ L/s}$$

\* Use the end-of-test flowrate.

## 6. Percolation Rate (testpit only)

(do not complete this step for rockbores)

$$(a) \text{ Soakage surface ( } \frac{1}{2} \text{ total wall area + base area) = } \underline{\hspace{2cm}} \text{ m}^2$$

$$(b) \text{ Percolation rate} = P_1 = \frac{P_2 \times 60}{(\text{soakage\_surface})} = \underline{\hspace{2cm}} \text{ L/m}^2/\text{min}$$



## WORKSHEET 4. ROCKBORE SOAKHOLE

**Site address** 36a Eaglehurst Rd SH 20  
**Job No.** 8149  
**Design by** P. Garriock Area C  
**Date** 27.04.21

### 1 Equivalent Impervious Area

Cover Type	Area (m2)	Ration, R <sub>E</sub>	Area x R <sub>E</sub> (m2)
Roof	Ar = 926	1	926
Paved	Ac = 0	1	0
Pervious (lawn etc)	Ap = 838	0.3	251.4

(a) Equivalent impervious area A<sub>E</sub>  $\Sigma$  A<sub>E</sub> = 1177.4 m<sup>2</sup>

### 2. Rockbore Capacity (if no storage provided)

a) Constant-head flow (from WORKSHEET 2) = P<sub>2</sub> = 20.8 L/s

b) Maximum area that can be served by bore =  $\frac{P_2 \times 60}{1.1}$  1134.55 m<sup>2</sup>

c) If area from b) > A<sub>E</sub>, no storage needed and step 3 does not need to be completed.

### 3. Storage Required

a) Catchment soakage ratio =  $P_3 = \frac{P_2 \times 60}{A_E}$  = 1.0599626 L/min/(m<sup>2</sup> equivalent impervious area)

b) Read of storage ratio (from CHART 2) = R<sub>2</sub> = 0.001 m<sup>3</sup>/m<sup>2</sup>


c) Calculate storage required = R<sub>2</sub> x A<sub>E</sub> = 1.2 m<sup>3</sup>

d) Compre to available storage = 1.3 m<sup>3</sup>  
 if negitve value no storage needed -0.1 m<sup>3</sup>



CHART 2 -Storage Requirements for all Soakholes

C2





## WORKSHEET 2. CONSTANT-HEAD PERCOLATION TEST

Site Address: 36a Eaglehurst Road, EllerslieCompleted by: Peter GarriockDate of test: 09.04.21

Signature: \_\_\_\_\_

## Attach the following:

- ☒ Log of borehole showing depth, geological layers and water table  
☒ Site-plan showing the location of the hole  
 (tick when attached)

- ☐ Civil Engineer  
☒ Engineering Technician  
☐ Engineering Geologist  
 (tick one)

## Ensure the following procedures are followed:

- ☒ A permit is obtained from Metrowater  
☒ Hole is pre-soaked for 10 minutes prior to test  
☒ Test is continued for 10 to 15 minutes  
☒ Rockbores are maintained full  
☐ Testpits are maintained ½ full  
☒ Bores within 10m of each other are tested simultaneously  
☐ Borehole drilling is attempted before constructing a testpit  
 (tick when complete)

## 3. Test Details

Time	Flowrate (L/s)
10m	6.1L/s

Time	Flowrate (L/s)

## 4. Determine capacity of rockbore/testpit :

$$(a) \text{ Capacity of bore} = P_2 = \frac{\text{Flowrate}^*}{1.3} = \frac{4.7}{1.3} = \underline{\hspace{2cm}} \text{ L/s}$$

\* Use the end-of-test flowrate.

## 6. Percolation Rate (testpit only)

(do not complete this step for rockbores)

$$(a) \text{ Soakage surface ( } \frac{1}{2} \text{ total wall area + base area) = } \underline{\hspace{2cm}} \text{ m}^2$$

$$(b) \text{ Percolation rate} = P_1 = \frac{P_2 \times 60}{(\text{soakage\_surface})} = \underline{\hspace{2cm}} \text{ L/m}^2/\text{min}$$



## WORKSHEET 4. ROCKBORE SOAKHOLE

**Site address** 36a Eaglehurst Rd SH 21  
**Job No.** 8149  
**Design by** P. Garriock Area A  
**Date** 27.04.21

### 1 Equivalent Impervious Area

Cover Type	Area (m2)	Ration, RE	Area x RE (m2)
Roof	Ar = 527	1	527
Paved	Ac = 0	1	0
Pervious (lawn etc)	Ap = 135	0.3	40.5

(a) Equivalent impervious area  $A_E = \sum A_E = \underline{567.5 \text{ m}^2}$

### 2. Rockbore Capacity (if no storage provided)

a) Constant-head flow (from WORKSHEET 2) =  $P_2 = \underline{4.7 \text{ L/s}}$

b) Maximum area that can be served by bore =  $\frac{P_2 \times 60}{1.1} = \underline{256.364 \text{ m}^2}$

c) If area from b) >  $A_E$ , no storage needed and step 3 does not need to be completed.

### 3. Storage Required

a) Catchment soakage ratio =  $P_3 = \frac{P_2 \times 60}{A_E} = \underline{0.49692 \text{ L/min/(m}^2 \text{ equivalent impervious area)}}$

b) Read of storage ratio (from CHART 2) =  $R_2 = \underline{0.0116 \text{ m}^3/\text{m}^2}$


c) Calculate storage required =  $R_2 \times A_E = \underline{6.6 \text{ m}^3}$

d) Compare to available storage =  $\underline{1.3 \text{ m}^3}$   
 $\underline{5.3 \text{ m}^3}$



CHART 2 -Storage Requirements for all Soakholes

C2





## WORKSHEET 2. CONSTANT-HEAD PERCOLATION TEST

Site Address: 36a Eaglehurst Road, Ellerslie

Completed by: Peter Garriock

Date of test: 09.04.21

Signature: \_\_\_\_\_

## Attach the following:

- ☒ Log of borehole showing depth, geological layers and water table  
☒ Site-plan showing the location of the hole  
 (tick when attached)

- ☐ Civil Engineer  
☒ Engineering Technician  
☐ Engineering Geologist  
 (tick one)

## Ensure the following procedures are followed:

- ☒ A permit is obtained from Metrowater  
☒ Hole is pre-soaked for 10 minutes prior to test  
☒ Test is continued for 10 to 15 minutes  
☒ Rockbores are maintained full  
☐ Testpits are maintained ½ full  
☒ Bores within 10m of each other are tested simultaneously  
☐ Borehole drilling is attempted before constructing a testpit  
 (tick when complete)

## 3. Test Details

Time	Flowrate (L/s)
10m	2.7 L/s

Time	Flowrate (L/s)

## 4. Determine capacity of rockbore/testpit :

$$(a) \text{ Capacity of bore} = P_2 = \frac{\text{Flowrate}^*}{1.3} = \frac{2.1}{1.3} \text{ L/s}$$

\* Use the end-of-test flowrate.

## 6. Percolation Rate (testpit only)

(do not complete this step for rockbores)

$$(a) \text{ Soakage surface ( } \frac{1}{2} \text{ total wall area + base area) = } \text{_____ m}^2$$

$$(b) \text{ Percolation rate} = P_1 = \frac{P_2 \times 60}{(\text{soakage\_surface})} = \text{_____ L/m}^2/\text{min}$$



## WORKSHEET 4. ROCKBORE SOAKHOLE

**Site address** 36a Eaglehurst Rd SH 23  
**Job No.** 8149  
**Design by** P. Garriock Area B  
**Date** 27.04.21

### 1 Equivalent Impervious Area

Cover Type	Area (m2)	Ration, R <sub>E</sub>	Area x R <sub>E</sub> (m2)
Roof	Ar = 360	1	360
Paved	Ac = 0	1	0
Pervious (lawn etc)	Ap = 0	0.3	0

(a) Equivalent impervious area A<sub>E</sub>  $\Sigma$  A<sub>E</sub> = 360 m<sup>2</sup>

### 2. Rockbore Capacity (if no storage provided)

a) Constant-head flow (from WORKSHEET 2) = P<sub>2</sub> = 2.1 L/s

b) Maximum area that can be served by bore =  $\frac{P_2 \times 60}{1.1}$  114.545 m<sup>2</sup>

c) If area from b) > A<sub>E</sub>, no storage needed and step 3 does not need to be completed.

### 3. Storage Required

a) Catchment soakage ratio =  $P_3 = \frac{P_2 \times 60}{A_E}$  = 0.35 L/min/(m<sup>2</sup> equivalent impervious area)

b) Read of storage ratio (from CHART 2) = R<sub>2</sub> = 0.018 m<sup>3</sup>/m<sup>2</sup>


c) Calculate storage required = R<sub>2</sub> x A<sub>E</sub> = 6.5 m<sup>3</sup>

d) Compare to available storage = 1.5m 1.3 m<sup>3</sup>  
5.2 m<sup>3</sup>



CHART 2 -Storage Requirements for all Soakholes

C2



## WORKSHEET 2. CONSTANT-HEAD PERCOLATION TEST

Site Address: 36a Eaglehurst Road, Ellerslie

Completed by: Peter Garriock

Date of test: 09.04.21

Signature: \_\_\_\_\_

## Attach the following:

- ☒ Log of borehole showing depth, geological layers and water table  
☒ Site-plan showing the location of the hole  
 (tick when attached)

- ☐ Civil Engineer  
☒ Engineering Technician  
☐ Engineering Geologist  
 (tick one)

## Ensure the following procedures are followed:

- ☒ A permit is obtained from Metrowater  
☒ Hole is pre-soaked for 10 minutes prior to test  
☒ Test is continued for 10 to 15 minutes  
☒ Rockbores are maintained full  
☐ Testpits are maintained ½ full  
☐ Bores within 10m of each other are tested simultaneously  
☐ Borehole drilling is attempted before constructing a testpit  
 (tick when complete)

## 3. Test Details

Time	Flowrate (L/s)
10m	1.7L/s SH03
	1.1L/s SH04
TOTAL	2.8L/s

Time	Flowrate (L/s)

## 4. Determine capacity of rockbore/testpit :

$$(a) \text{ Capacity of bore} = P_2 = \frac{\text{Flowrate}^*}{1.3} = \underline{2.2} \text{ L/s}$$

\* Use the end-of-test flowrate.

## 6. Percolation Rate (testpit only)

(do not complete this step for rockbores)

$$(a) \text{ Soakage surface ( } \frac{1}{2} \text{ total wall area + base area) = } \underline{\hspace{2cm}} \text{ m}^2$$

$$(b) \text{ Percolation rate} = P_1 = \frac{P_2 \times 60}{(\text{soakage\_surface})} = \underline{\hspace{2cm}} \text{ L/m}^2/\text{min}$$



## WORKSHEET 4. ROCKBORE SOAKHOLE

**Site address** 36a Eaglehurst Rd SH 03 & 04  
**Job No.** 8149  
**Design by** P. Garriock Area D  
**Date** 27.04.21

### 1 Equivalent Impervious Area

Cover Type	Area (m2)	Ration, R <sub>E</sub>	Area x R <sub>E</sub> (m2)
Roof	Ar = 334	1	334
Paved	Ac = 0	1	0
Pervious (lawn etc)	Ap = 222	0.3	66.6

(a) Equivalent impervious area A<sub>E</sub>  $\Sigma$  A<sub>E</sub> = 400.6 m<sup>2</sup>

### 2. Rockbore Capacity (if no storage provided)

a) Constant-head flow (from WORKSHEET 2) = P<sub>2</sub> = 2.2 L/s

b) Maximum area that can be served by bore =  $\frac{P_2 \times 60}{1.1}$  120 m<sup>2</sup>

c) If area from b) > A<sub>E</sub>, no storage needed and step 3 does not need to be completed.

### 3. Storage Required

a) Catchment soakage ratio =  $P_3 = \frac{P_2 \times 60}{A_E} = \frac{0.32951}{1} \text{ L/min/(m}^2 \text{ equivalent impervious area)}$


b) Read of storage ratio (from CHART 2) = R<sub>2</sub> = 0.019 m<sup>3</sup>/m<sup>2</sup>

c) Calculate storage required = R<sub>2</sub> x A<sub>E</sub> = 7.6 m<sup>3</sup>


d) Compre to available storage = 2 MH 2.6 m<sup>3</sup>  
5.0 m<sup>3</sup>

CHART 2 -Storage Requirements for all Soakholes

C2







SURVEY INFORMATION				REV		CHK	DATE	MODIFICATION	PROJECT		CLIENT		SURVEYED		DRAWN	CHECKED	APPROVED
FOR INFORMATION ONLY				-	PW		29/04/21	ORIGINAL	36A EAGLEHURST RD		FOR INFORMATION ONLY		N/A		PG	PW	
									DRAWING TITLE		THE COPYRIGHT OF THIS DESIGN AND DRAWING IS VESTED IN BARRY SATCHELL CONSULTANTS LTD, UNLESS OTHERWISE INDICATED.		SCALE		NTS (A3 ORIGINAL SIZE)		DATE
									SOAKHOLE LOCATION PLAN				JOB NO.		DRAWING No.		REVISION
													8149		701		-
													CAD Ref.		8149 soakage location.13.11.20		

**Barry Satchell**  
ENGINEERS - SURVEYORS - PLANNERS

60 NEW NORTH ROAD  
BALMORAL  
PO BOX 10-343  
DOMINION ROAD  
AUCKLAND

TEL: +64-9-623-4573  
WEB: [www.bscl.co.nz](http://www.bscl.co.nz)  
Email: [admin@bscl.co.nz](mailto:admin@bscl.co.nz)

## FORM "OSM-O&M-PLAN"

### (A) SITE & OSM DEVICE DETAILS:

(1) Site Address: 36a Eaglehurst Road, Ellerslie

(2) Owners Name: TBA

(3) Details of OSM Device(s): Residential Soakholes

Ref. No	Type	Size (eg m2 or m3)	Location	Runoff Source*
SH 20	Rockbore	1,177.4m2	accessway	roof, grass
SH03 & 04	Rockbore	400.6m2	accessway	roof, grass

\* eg roof, paved area

(4) Name & Address of Parties Responsible for Inspecting and Maintaining the Devices:

TBA

### (B) O&M PLAN PREPARED BY:

(1) Firm: Barry Satchell Consultants Limited

(2) Responsible Individuals Name: Peter Garriock

(3) Firms Address: 60 New North Road, Eden Terrace

### (C) ATTACHED FORMS:

(1) Form "OSM-O&M-Routine"

(2) Forms "DEVICE-SPECIFIC O&M DETAILS": (one for each OSM device)

Ref. No	Type
SH 20	Rockbore
SH 03 & 04	Rockbore

\_\_\_\_\_  
Signed

\_\_\_\_\_  
Date

### AC Office Use:

Reference No. \_\_\_\_\_

Checked by: \_\_\_\_\_ Date: \_\_\_\_\_

Entered by: \_\_\_\_\_ Date: \_\_\_\_\_



## FORM "OSM-O&M-ROUTINE"

### List of Routine Maintenance Requirements

#### (a) Monitoring & Inspection Programme:

Routine monitoring and inspections are required to:

- Develop a condition history
- Improve scheduling efficiency
- Apply preventative maintenance

Inspection records are to be used to:

- Determine where special maintenance conditions exist
- Determine optimal frequencies for future inspection and maintenance
- Establish scheduled and unscheduled maintenance provisions
- Assure OSM device operation and aesthetics

Specific requirements cover:

- The owner will be responsible for conducting inspections (or having them done on his/her behalf) with the OSM device "as-built" plans in hand, generally at the following intervals (noting that this may vary, depending on site-specific conditions):
  - quarterly basis for the first 2 years
  - minimum of semi-annually thereafter
- The owner will be responsible for keeping inspection records to track the progressive development of the OSM device(s) over time, covering (note that these are to be available to the maintenance contractor noted in Section 11.2 and/or the City/ACE as may be required):
  - general condition of vegetation area(s), predominant plant species, distribution, and success rate (where applicable)
  - sediment condition and depth in forebay (or other pre-treatment structure), treatment facility, bench planting zones, and other sediment removal components
  - water elevations/observations (sheen, smell, etc.)
  - condition of the inlet, outlet, and overflow structures/devices, etc
  - unscheduled maintenance needs
  - components that do not meet performance criteria and require immediate maintenance
  - common problem areas, solutions, and general observations
  - aesthetic conditions

(b) Soils in Stormwater Planters & Rain Gardens:

The following requirements apply:

- Test the pH of planting bed soils in areas where vegetation has died:
  - if the pH is below 5.2, apply limestone
  - if the pH is above 7.0, add iron sulfate plus sulfur to reduce the pH
- Use core aeration of unvegetated areas if the surface of the bed becomes clogged with fine sediments over time: redesign plantings to correct problems, and re-establish soil coverage

(c) Vegetation Management:

Vegetated stormwater facilities may require a number of control practices, especially during the 2-year establishment period. Corresponding required practices cover:

- Maintain plantings for a period of 2 years after date of the Building Consent final inspection
- During the establishment period, remove undesired vegetation with minimal (or preferably no) use of toxic herbicides and pesticides at least three times in year 1, and once or twice in the summer of year 2; replace plants that die during this period within 3 months
- At the end of the second year, healthy plant establishment shall be achieved for at least 90% of the vegetation
- Selectively irrigate if necessary during the establishment period, during times of drought, or until the vegetation becomes established: it is preferred that the facility be designed to sustain its function without a permanent irrigation system
- Replenish mulch at least annually, and specify the mulching schedule in the O&M Plan; noting also that mulching shall be done to retain topsoil, heat, and moisture, and to inhibit weed growth
- Schedule maintenance outside sensitive wildlife and vegetation seasons
- Minimise plant disturbance during maintenance activities
- Do not use fertilisers, herbicides, or pesticides for vegetation maintenance, unless it is specifically called for in the O&M Plan
- Use replacement plants that conform with the initial planting plan

(d) Sediment Management/Pollutant Control:

Sediment and other pollutants that degrade water quality will accumulate in OSM devices and require removal to ensure proper operational performance. Corresponding requirements cover:

- Remove sediment when accumulations reach 100 mm in depth, or 50% of the designed sediment storage depth, or if sediment accumulation inhibits facility operation
- Dispose of the sediment in a safe manner
- If sediment and/or other pollutants are accumulating more rapidly than assumed when the O&M Plan was formulated, investigate and rectify the cause



(e) Access and Safety:

O&M programmes must provide for safe and efficient access to a facility. The following are general requirements; specific conditions may require site-specific modifications:

- Secure easements necessary to provide facility and maintenance access (if applicable)
- Use only suitably trained personnel to access confined spaces
- Maintain ingress/egress routes to design standards, in a manner that allows efficient maintenance of the facility
- Ensure that fencing is in good repair

## FORM "OSM-O&M-CERT"

### (A) SITE & OSM DEVICE DETAILS:

Site Address: 36a Eaglehurst Road, Ellerslie

Owners Name: TBA

Device(s):

Ref. No	Type	Size (eg m2 or m3)	Date Installed
SH 20	Rockbore	1.177.4m2	
SH 03 & 04	Rockbore	400.6m2	

### (B) MAINTENANCE CONTRACTOR'S DETAILS:

Firms Name: \_\_\_\_\_

Firms Address: \_\_\_\_\_

Name of Serviceperson: \_\_\_\_\_

Date(s) of Service: \_\_\_\_\_

### (C) SERVICE DETAILS:

Device Ref. No	Checklist Completed	MAINTENANCE ACTION	
		Item	Action (describe, eg "pipe replaced")
1		(a)	
		(b)	
		(c)	
		(d)	
2		(a)	
		(b)	
		(c)	
		(d)	
3		etc....(continue on a separate sheet)	

\* on attached form "Device-Specific O&M Details"

### (D) CERTIFICATION:

I/we hereby certify that:



- The OSM device inspection and maintenance programme has been undertaken in accordance with the provision of Section 11 of the City's "OSM Manual" dated 2002
- The details above and on the attached form(s) are a full and correct record of the work performed
- The OSM device(s) are in sound working order
- The owner has been advised of the problems found (if any) and alerted as to the need to inspect for any recurrences and rectify such promptly

\_\_\_\_\_  
Signed

\_\_\_\_\_  
Date

ACE Office Use:

Reference No. \_\_\_\_\_

Checked by: \_\_\_\_\_

Date: \_\_\_\_\_

Entered by: \_\_\_\_\_

Date: \_\_\_\_\_

## FORM "OSM-O&M-PLAN"

### (A) SITE & OSM DEVICE DETAILS:

(1) Site Address: 36a Eaglehurst Road, Ellerslie

(2) Owners Name: TBA

(3) Details of OSM Device(s): Driveway and parking area Soakholes

Ref. No	Type	Size (eg m2 or m3)	Location	Runoff Source*
SH 21	Rockbore	567.5m2	accessway	paved areas
SH 23	Rockbore	360m2	accessway	paved areas

\* eg roof, paved area

(4) Name & Address of Parties Responsible for Inspecting and Maintaining the Devices:

TBA

### (B) O&M PLAN PREPARED BY:

(1) Firm: Barry Satchell Consultants Limited

(2) Responsible Individuals Name: Peter Garriock

(3) Firms Address: 60 New North Road, Eden Terrace

### (C) ATTACHED FORMS:

(1) Form "OSM-O&M-Routine"

(2) Forms "DEVICE-SPECIFIC O&M DETAILS": (one for each OSM device)

Ref. No	Type
SH 21	Rockbore
SH 23	Rockbore

\_\_\_\_\_  
Signed

\_\_\_\_\_  
Date

### AC Office Use:

Reference No. \_\_\_\_\_

Checked by: \_\_\_\_\_ Date: \_\_\_\_\_

Entered by: \_\_\_\_\_ Date: \_\_\_\_\_



## FORM "OSM-O&M-ROUTINE"

### List of Routine Maintenance Requirements

#### (a) Monitoring & Inspection Programme:

Routine monitoring and inspections are required to:

- Develop a condition history
- Improve scheduling efficiency
- Apply preventative maintenance

Inspection records are to be used to:

- Determine where special maintenance conditions exist
- Determine optimal frequencies for future inspection and maintenance
- Establish scheduled and unscheduled maintenance provisions
- Assure OSM device operation and aesthetics

Specific requirements cover:

- The owner will be responsible for conducting inspections (or having them done on his/her behalf) with the OSM device "as-built" plans in hand, generally at the following intervals (noting that this may vary, depending on site-specific conditions):
  - quarterly basis for the first 2 years
  - minimum of semi-annually thereafter
- The owner will be responsible for keeping inspection records to track the progressive development of the OSM device(s) over time, covering (note that these are to be available to the maintenance contractor noted in Section 11.2 and/or the City/ACE as may be required):
  - general condition of vegetation area(s), predominant plant species, distribution, and success rate (where applicable)
  - sediment condition and depth in forebay (or other pre-treatment structure), treatment facility, bench planting zones, and other sediment removal components
  - water elevations/observations (sheen, smell, etc.)
  - condition of the inlet, outlet, and overflow structures/devices, etc
  - unscheduled maintenance needs
  - components that do not meet performance criteria and require immediate maintenance
  - common problem areas, solutions, and general observations
  - aesthetic conditions

(b) Soils in Stormwater Planters & Rain Gardens:

The following requirements apply:

- Test the pH of planting bed soils in areas where vegetation has died:
  - if the pH is below 5.2, apply limestone
  - if the pH is above 7.0, add iron sulfate plus sulfur to reduce the pH
- Use core aeration of unvegetated areas if the surface of the bed becomes clogged with fine sediments over time: redesign plantings to correct problems, and re-establish soil coverage

(c) Vegetation Management:

Vegetated stormwater facilities may require a number of control practices, especially during the 2-year establishment period. Corresponding required practices cover:

- Maintain plantings for a period of 2 years after date of the Building Consent final inspection
- During the establishment period, remove undesired vegetation with minimal (or preferably no) use of toxic herbicides and pesticides at least three times in year 1, and once or twice in the summer of year 2; replace plants that die during this period within 3 months
- At the end of the second year, healthy plant establishment shall be achieved for at least 90% of the vegetation
- Selectively irrigate if necessary during the establishment period, during times of drought, or until the vegetation becomes established: it is preferred that the facility be designed to sustain its function without a permanent irrigation system
- Replenish mulch at least annually, and specify the mulching schedule in the O&M Plan; noting also that mulching shall be done to retain topsoil, heat, and moisture, and to inhibit weed growth
- Schedule maintenance outside sensitive wildlife and vegetation seasons
- Minimise plant disturbance during maintenance activities
- Do not use fertilisers, herbicides, or pesticides for vegetation maintenance, unless it is specifically called for in the O&M Plan
- Use replacement plants that conform with the initial planting plan

(d) Sediment Management/Pollutant Control:

Sediment and other pollutants that degrade water quality will accumulate in OSM devices and require removal to ensure proper operational performance. Corresponding requirements cover:

- Remove sediment when accumulations reach 100 mm in depth, or 50% of the designed sediment storage depth, or if sediment accumulation inhibits facility operation
- Dispose of the sediment in a safe manner
- If sediment and/or other pollutants are accumulating more rapidly than assumed when the O&M Plan was formulated, investigate and rectify the cause



(e) Access and Safety:

O&M programmes must provide for safe and efficient access to a facility. The following are general requirements; specific conditions may require site-specific modifications:

- Secure easements necessary to provide facility and maintenance access (if applicable)
- Use only suitably trained personnel to access confined spaces
- Maintain ingress/egress routes to design standards, in a manner that allows efficient maintenance of the facility
- Ensure that fencing is in good repair

## FORM "OSM-O&M-CERT"

### (A) SITE & OSM DEVICE DETAILS:

Site Address: 36a Eaglehurst Road, Ellerslie

Owners Name: TBA

Device(s):

Ref. No	Type	Size (eg m2 or m3)	Date Installed
SH 21	Rockbore	567.5m2	
SH 23	Rockbore	360m2	

### (B) MAINTENANCE CONTRACTOR'S DETAILS:

Firms Name: \_\_\_\_\_

Firms Address: \_\_\_\_\_

Name of Serviceperson: \_\_\_\_\_

Date(s) of Service: \_\_\_\_\_

### (C) SERVICE DETAILS:

Device Ref. No	Checklist Completed	MAINTENANCE ACTION	
		Item	Action (describe, eg "pipe replaced")
1		(a)	
		(b)	
		(c)	
		(d)	
2		(a)	
		(b)	
		(c)	
		(d)	
3		etc....(continue on a separate sheet)	

\* on attached form "Device-Specific O&M Details"

### (D) CERTIFICATION:

I/we hereby certify that:



- The OSM device inspection and maintenance programme has been undertaken in accordance with the provision of Section 11 of the City's "OSM Manual" dated 2002
- The details above and on the attached form(s) are a full and correct record of the work performed
- The OSM device(s) are in sound working order
- The owner has been advised of the problems found (if any) and alerted as to the need to inspect for any recurrences and rectify such promptly

\_\_\_\_\_  
Signed

\_\_\_\_\_  
Date

ACE Office Use:

Reference No. \_\_\_\_\_

Checked by: \_\_\_\_\_

Date: \_\_\_\_\_

Entered by: \_\_\_\_\_

Date: \_\_\_\_\_

**(D) RECORD KEEPING**

- Completed Form must be submitted to AC. For 2 yearly inspections, the form must be submitted with and OSM-O&M Cert" form.

- A copy of the completed form (and any additional records) is to be kept on-site and made available to the plumber/drainlayer

- A copy of the completed form (and any additional records) is to be kept on-site and made available to the plumber/drainlayer

- Site Address: 36a Eaglehurst Road, Ellerslie
- 
- Building Consent Number: \_\_\_\_\_
- Reference Number (from Form "OSM-O&M-Plan"): SH 03 & 04
- Date Installed \_\_\_\_\_

**FORM "DEVICE SPECIFIC O&M DETAIL SM005"- PAGE 2 OF 2**

**CHECKLIST – ROCKBORE SOAKHOLE**

Frequency				Action	Notes
After Storm	Quarterly	Annually	2 Yearly*		
✓	✓	✓	✓	<b>Spouting and downpipes:</b> <ul style="list-style-type: none"> <li>• Check for debris accumulation, blockages and leaks.</li> <li>• Check that the overflow is not obstructed.</li> <li>• Check that any leaf-removing devices are operating correctly.</li> <li>• Carry out maintenance as necessary.</li> </ul> <b>Rockbore and chamber:</b> <ul style="list-style-type: none"> <li>• If chamber is dry, remove sediment manually (eg using a shovel and bucket).</li> <li>• If chamber is wet, remove sediment using an air-vacuum system.</li> <li>• Check perforated pipe for clogging and correct operation. Clean and repair as necessary.</li> <li>• Remove borehole cap and check borehole is dry.</li> <li>• Carry out rockbore cleaning as required and at least every 4 years on commercial sites and 6 years on residential sites (process detailed below).</li> </ul> <b>Rockbore cleaning:</b> <ul style="list-style-type: none"> <li>• Remove accumulated sediment from borehole using an air-vacuum system.</li> <li>• Hydro-blast borehole.</li> <li>• Use the air vacuum system to remove sediment loosened by hydroblasting.</li> <li>• Check that rockbore is draining correctly (if not, it may require replacement).</li> </ul>	

\*Plumber/Drainlayer Checklist

Plumber/Drainlayer Signature

Name

Company Name

Company Address

Date

Reg No

Site Address: 36a Eaglehurst Road, Ellerslie  
 Building Consent Number:  
 Reference Number (from Form "OSM-O&M-Plan"): SH 03 & 04  
 Date Installed



**FORM "DEVICE SPECIFIC O&M DETAIL SM005"- PAGE 1 OF 2**  
**OPERATION AND MAINTENANCE OF ROCKBORE SOAKHOLE"**

Note: One form required for each OSM device on a site

**(A) DESCRIPTION OF ROCKBORE SOAKHOLE :**

The rockbore soakhole is a concrete chamber with a borehole extending down into fractured rock beneath the chamber. The chamber normally extends to the surface with a steel lid to allow access. The top of the borehole is lined with a PVC liner that ends in syphon or a coil of perforated pipe. Rainwater is piped into the concrete chamber, and flows into the borehole through the syphon or perforated pipe.

**(B) OPERATIONAL POINTS**

- Any site runoff (from paved areas) feeding to the soakhole will first pass through a pre-treatment device, such as a raingarden or a sandfilter. Maintenance of the pre-treatment device will be covered under a separate O&M form, and this will also cover maintenance of any catchpits or stormwater pipes feeding to the pre-treatment device.
- Roof runoff flows through a small chamber before entering the soakhole (does not apply to soakholes installed prior to 2003). The small chamber will be connected to the pipework between the spouting and the soakhole.

**(C) GENERAL O&M NEEDS**

- Maintenance of flow through the spouting and downpipe system.
- Removal of accumulated sediment from the chamber.
- Cleaning of the rockbore soakage surface.
- Checking the soakage capacity of the soakhole.

**(D) RECORD KEEPING**

- Completed Form must be submitted to AC. For 2 yearly inspections, the form must be submitted with and OSM-O&M Cert" form.
- A copy of the completed form (and any additional records) is to be kept on-site and made available to the plumber/drainlayer

Site Address: 36a Eaglehurst Road, Ellerslie  
Building Consent Number: \_\_\_\_\_  
Reference Number (from Form "OSM-O&M-Plan");\_ SH 20 \_\_\_\_\_  
Date Installed \_\_\_\_\_

**FORM "DEVICE SPECIFIC O&M DETAIL SM005" - PAGE 2 OF 2**  
**CHECKLIST – ROCKBORE SOAKHOLE**

Frequency				Action	Notes
After Storm	Quarterly	Annually	2 Yearly*		
✓	✓	✓	✓	<b>Spouting and downpipes:</b> <ul style="list-style-type: none"> <li>• Check for debris accumulation, blockages and leaks.</li> <li>• Check that the overflow is not obstructed.</li> <li>• Check that any leaf-removing devices are operating correctly.</li> <li>• Carry out maintenance as necessary.</li> </ul> <b>Rockbore and chamber:</b> <ul style="list-style-type: none"> <li>• If chamber is dry, remove sediment manually (eg using a shovel and bucket).</li> <li>• If chamber is wet, remove sediment using an air-vacuum system.</li> <li>• Check perforated pipe for clogging and correct operation. Clean and repair as necessary.</li> <li>• Remove borehole cap and check borehole is dry.</li> <li>• Carry out rockbore cleaning as required and at least every 4 years on commercial sites and 6 years on residential sites (process detailed below).</li> </ul>	
<b>*Plumber/Drainlayer Checklist</b> Plumber/Drainlayer Signature Name Company Name Company Address				<b>Rockbore cleaning:</b> <ul style="list-style-type: none"> <li>• Remove accumulated sediment from borehole using an air-vacuum system.</li> <li>• Hydro-blast borehole.</li> <li>• Use the air vacuum system to remove sediment loosened by hydroblasting.</li> <li>• Check that rockbore is draining correctly (if not, it may require replacement).</li> </ul>	

Date

Reg No

Site Address: 36a Eaglehurst Road, Ellerslie  
Building Consent Number:  
Reference Number (from Form "OSM-O&M-Plan"): SH 20  
Date Installed

**(D) RECORD KEEPING**

- Completed Form must be submitted to AC. For 2 yearly inspections, the form must be submitted with and OSM-O&M Cert" form.

- A copy of the completed form (and any additional records) is to be kept on-site and made available to the plumber/drainlayer

A copy of the completed form (and any additional records) is to be kept on-site and made available to the plumber/drainlayer

- Any site runoff (from paved areas) feeding to the soakhole will first pass through a pre-treatment device, such as a raingarden or a sandfilter. Maintenance of the pre-treatment device will be covered under a separate O&M form, and this will also cover maintenance of any catchpits or stormwater pipes feeding to the pre-treatment device.
- Roof runoff flows through a small chamber before entering the soakhole (does not apply to soakholes installed prior to 2003). The small chamber will be connected to the pipework between the spouting and the soakhole.

- Maintenance of flow through the spouting and downpipe system.
- Removal of accumulated sediment from the chamber.
- Cleaning of the rockbore soakage surface.
- Checking the soakage capacity of the soakhole.

Site Address: 36a Eaglehurst Road, Ellerslie

---

Building Consent Number: \_\_\_\_\_

---

Reference Number (from Form "OSM-O&M-Plan"): SH 21

---

Date Installed \_\_\_\_\_



**FORM "DEVICE SPECIFIC O&M DETAIL SM005" - PAGE 2 OF 2**

**CHECKLIST – ROCKBORE SOAKHOLE**

Frequency				Action	Notes
After Storm	Quarterly	Annually	2 Yearly*		
✓	✓	✓	✓	<b>Spouting and downpipes:</b> <ul style="list-style-type: none"> <li>• Check for debris accumulation, blockages and leaks.</li> <li>• Check that the overflow is not obstructed.</li> <li>• Check that any leaf-removing devices are operating correctly.</li> <li>• Carry out maintenance as necessary.</li> </ul> <b>Rockbore and chamber:</b> <ul style="list-style-type: none"> <li>• If chamber is dry, remove sediment manually (eg using a shovel and bucket).</li> <li>• If chamber is wet, remove sediment using an air-vacuum system.</li> <li>• Check perforated pipe for clogging and correct operation. Clean and repair as necessary.</li> <li>• Remove borehole cap and check borehole is dry.</li> <li>• Carry out rockbore cleaning as required and at least every 4 years on commercial sites and 6 years on residential sites (process detailed below).</li> </ul> <b>Rockbore cleaning:</b> <ul style="list-style-type: none"> <li>• Remove accumulated sediment from borehole using an air-vacuum system.</li> <li>• Hydro-blast borehole.</li> <li>• Use the air vacuum system to remove sediment loosened by hydroblasting.</li> <li>• Check that rockbore is draining correctly (if not, it may require replacement).</li> </ul>	

\*Plumber/Drainlayer Checklist

Plumber/Drainlayer Signature

Name

Company Name

Company Address

Date

Reg No

Site Address: 36a Eaglehurst Road, Ellerslie  
 Building Consent Number:  
 Reference Number (from Form "OSM-O&M-Plan"): SH 21  
 Date Installed

**(D) RECORD KEEPING**

- Completed Form must be submitted to AC. For 2 yearly inspections, the form must be submitted with and OSM-O&M Cert" form.

- A copy of the completed form (and any additional records) is to be kept on-site and made available to the plumber/drainlayer

- A copy of the completed form (and any additional records) is to be kept on-site and made available to the plumber/drainlayer

- Site Address: 36a Eaglehurst Road, Ellerslie
- Building Consent Number: \_\_\_\_\_
- Reference Number (from Form "OSM-O&M-Plan"): SH 23
- Date Installed \_\_\_\_\_

Site Address: 36a Eaglehurst Road, Ellerslie

Building Consent Number: \_\_\_\_\_

Reference Number (from Form "OSM-O&M-Plan"): SH 23

Date Installed \_\_\_\_\_

**FORM "DEVICE SPECIFIC O&M DETAIL SM005"- PAGE 2 OF 2**

**CHECKLIST – ROCKBORE SOAKHOLE**

Frequency				Action	Notes
After Storm	Quarterly	Annually	2 Yearly*		
✓	✓	✓	✓	<b>Spouting and downpipes:</b> <ul style="list-style-type: none"> <li>• Check for debris accumulation, blockages and leaks.</li> <li>• Check that the overflow is not obstructed.</li> <li>• Check that any leaf-removing devices are operating correctly.</li> <li>• Carry out maintenance as necessary.</li> </ul> <b>Rockbore and chamber:</b> <ul style="list-style-type: none"> <li>• If chamber is dry, remove sediment manually (eg using a shovel and bucket).</li> <li>• If chamber is wet, remove sediment using an air-vacuum system.</li> <li>• Check perforated pipe for clogging and correct operation. Clean and repair as necessary.</li> <li>• Remove borehole cap and check borehole is dry.</li> <li>• Carry out rockbore cleaning as required and at least every 4 years on commercial sites and 6 years on residential sites (process detailed below).</li> </ul> <b>Rockbore cleaning:</b> <ul style="list-style-type: none"> <li>• Remove accumulated sediment from borehole using an air-vacuum system.</li> <li>• Hydro-blast borehole.</li> <li>• Use the air vacuum system to remove sediment loosened by hydroblasting.</li> <li>• Check that rockbore is draining correctly (if not, it may require replacement).</li> </ul>	
*Plumber/Drainlayer Checklist					

Date

Plumber/Drainlayer Signature

Name Reg No

Company Name

Company Address

Site Address: 36a Eaglehurst Road, Ellerslie  
 Building Consent Number:  
 Reference Number (from Form "OSM-O&M-Plan"): SH 23  
 Date Installed



## **Appendix D:**

### **Stormwater pipe run calculations**

AKC STORMWATER EXIST. PIPERUN CALCULATION

SW line A to Soakhole 20, CP 1 to Soakhole 21, CP 2 to Soakhole 23  
Lot 21 to Soakhole 03 & 04

Project: 36a Eaglehurst Road  
Job No. 8149  
Storm Frequency = 10 Year  
Duration=10min Ks=0.6mm  
ARI i  
climate change + 13.2 %

TP108 STORMWATER RUNOFF

ARC April 1999

120  
136



ENGINEERS · SURVEYORS · PLANNERS

PROJECT	5 Crosbie Road Pukekohe	8149
	Calculated Peter Garriock	24.05.21
	Reviewed P Wilson	24.05.21

MH	MH	Catchment Area (m2) Incr.	Total Area	Comments (Contrib Area)	TP108 Curve No.	Daily Rainfall Depth ARI	Total Equiv. Area (ha)	Depression Storage (S) mm	Specific flow rate fig5.1	Catchment Runoff Q (m3/s)	This line only (l/s)	Total Flow Q (l/s)	L (m)	Design S %	Ks	Kv	Pipe D (mm)	Q/c Full (l/s)	Velocity Full (m/s) (4.5 max.) (2.0 outlet)	Pipe Capacity (%)
END A	MH D	138	138	Impervious	98.00	136	0.014	5.2	0.160	0.003										
		107	107	Pervious	74.00	136	0.011	89.2	0.114	0.002	5	5	5.00	0.55	0.60	1.14E-06	150	13.3	0.75	0.35
MH D	MH C	89	334	Impervious	98.00	136	0.009	5.2	0.160	0.002										
		66	66	Pervious	74.00	136	0.007	89.2	0.114	0.001	3	8	34.55	0.55	0.60	1.14E-06	150	13.3	0.75	0.57
END B	MHC	640	1040	Impervious	98.00	136	0.064	5.2	0.160	0.014										
		639	639	Road/Res	74.00	136	0.064	89.2	0.114	0.010	24	24	42.24	2.40	0.60	1.14E-06	150	27.8	1.57	0.86
MHC	SETT	58	1737	Impervious	98.00	136	0.006	5.2	0.160	0.001										
		96	96	Road/Res	74.00	136	0.010	89.2	0.114	0.001	3	34	35.85	0.47	0.60	1.14E-06	225	35.7	0.90	0.96
SETT	SH20	0	1833	Impervious	75.00	136	0.000	84.7	0.140	0.000										
		0	0	Road/Res	76.00	136	0.000	80.2	0.114	0.000	0	34	2.00	0.45	0.60	1.14E-06	225	34.9	0.88	0.98
CP1	SH21	527	527	Impervious	98.00	136	0.053	5.2	0.160	0.011										
		135	135	Pervious	74.00	136	0.014	89.2	0.114	0.002	14	14	31.64	0.55	0.60	1.14E-06	150	13.3	0.75	1.02
CP2	SH23	360	0	Impervious	98.00	136	0.036	5.2	0.160	0.008										
		0	0	Pervious	74.00	136	0.000	89.2	0.114	0.000	8	8	23.75	0.55	0.60	1.14E-06	150	13.3	0.75	0.59
Lot 21	SH03&04	334	861	Impervious	98.00	136	0.033	5.2	0.160	0.007										
		222	222	Pervious	74.00	136	0.022	89.2	0.114	0.003	11	11	34.99	0.55	0.60	1.14E-06	150	13.3	0.75	0.81

## **Appendix E:**

### **Wastewater catchment and capacity calculations**



PROJECT	Eaglehurst Road	8149
	Ellerslie	
	Calculated	Peter Garriock 05.03.21
	Reviewed	P Wilson 05.03.21



## WATERCARE WASTEWATER CAPACITY CALCULATIONS

### Design Parameters

Watercare services: Water and Wastewater code of practice

V 2.2

Nov-19

### Residential

COP

Number of Dwellings / Lots		20.0		
People per dwelling		3.0		
Average Dry Weather Flow	ADWF	180.0	l / person / day	5.3.5.1
Dry Weather peaking factor	PDWF	3.0		
Peak Wet Weather factor	PWWF	6.7		
Residential	ADWF	0.1	l/s	
Residential	PDWF	0.4	l/s	
Residential	PWWF	0.8	l/s	

### Catchment Wastewater flow 1st MH downstream 510212

Number of Dwellings / Lots		42.0		
People per dwelling		3.0		
Average Dry Weather Flow	ADWF	180.0	l / person / day	5.3.5.1
Dry Weather peaking factor	PDWF	3.0		
Peak Wet Weather factor	PWWF	6.7		
Residential	ADWF	0.3	l/s	
Residential	PDWF	0.8	l/s	
Residential	PWWF	1.8	l/s	

TOTAL	Peak Dry Weather flow	PDWF	1.2	l/s	V > self cleansing 0.75 m/s if half fu
	Residential	PWWF	2.6	l/s	V < 3.0 m/s max

### Pipe Flow Capacity

$$V = 1/n (A/P)^{2/3} S^{1/2}$$

Pipe		Concrete	PVC
Pipe Diameter		150	mm
Mannings	n	0.013	0.011
Slope	S	3.0%	%
Area	A	0.018	m <sup>2</sup>
Wetted P	P	0.471	

Full Flow Velocity	V	1.5	m/s
Full Flow Pipe	Q = V A	26.3	l/s

Capacity %	Development / Total capacity	3.2%
------------	------------------------------	------





Scale @ A3  
= 1:1,000

Date Printed:  
8/01/2021



**36A EAGELHURST WW CATCHMENT**

**DISCLAIMER:**  
This map/plan is illustrative only and all information should be independently verified on site before taking any action. Copyright Auckland Council. Land Parcel Boundary information from LINZ (Grown Copyright Reserved). Whilst due care has been taken, Auckland Council gives no warranty as to the accuracy and plan completeness of any information on this map/plan and accepts no liability for any error, omission or use of the information.  
Height datum: Ausl 1946.





## 36A EAGELHURST WW CATCHMENT

**DISCLAIMER:**  
This map/plan is illustrative only and all information should be independently verified on site before taking any action. Copyright Auckland Council. Land Parcel Boundary information from LINZ (Crown Copyright Reserved). Whilst due care has been taken, Auckland Council gives no warranty as to the accuracy and plan completeness of any information on this map/plan and accepts no liability for any error, omission or use of the information.  
Height datum: Auckland 1946.






## **Appendix F:**

### **Drainage, Accessway and Water design plans**







- ## NOTES

1. LEGAL AND FORMED WIDTHS SHALL BE IN ACCORDANCE WITH THE UNITARY PLAN OR APPROVED CONSENT. (REFER TABLES E27.6.4.3.2 AND E38.8.1.2.1)
2. CONCRETE CONSTRUCTION IS TO BE IN ACCORDANCE WITH NZS 3109 AND NZS 3114.  
(NZS 3109 - Concrete construction)  
(NZS 3114 - Specification for concrete surface finishes)
3. ALL DIMENSIONS ARE IN MILLIMETRES (UNLESS OTHERWISE SPECIFIED)
4. BELOW THE 50mm AP20  
  
AP 40 OR GAP 65 SUB-BASE MAY BE REQUIRED  
MINIMUM 150MM THICK IF SUBGRADE CBR < 3  
MINIMUM 100MM THICK IF SUBGRADE CBR >= 3 TO < 7  
NOT REQUIRED IF SUBGRADE CBR >= 7
5. MAXIMUM GRADE 1 in 5. WHERE THE UNITARY PLAN MAY ALLOW A STEEPER GRADE SPECIFIC DESIGN IS REQUIRED.
6. AN APPROPRIATE SIZED CESSPIST OR OTHER COLLECTION DEVICE IS REQUIRED FOR SURFACE WATER RUNOFF. THE SITE AND DESIGN IS TO BE BASED ON THE CATCHMENT AREA AND SLOPE.
7. THE USE OF REINFORCING OR OTHER DESIGN ALTERNATIVES WILL BE CONSIDERED.
8. THE USE OF REINFORCING FIBRE OR MESH IN THE UPPER LAYER (FIXED WITH 30MM COVER) IS RECOMMENDED TO REDUCE SHRINKAGE CRACKING.
9. THIS DETAIL IS ACCEPTABLE SOLUTION ONLY. AT TIMES SPECIFIC DESIGN MAY BE REQUIRED.

## REGULATORY ENGINEERING



DWG : RE 01

ISSUED : MARCH 2019

## DRIVEWAYS

FOR RESIDENTIAL DEVELOPMENTS SERVICING  
NINE OR LESS PARKING SPACES  
OR FIVE AND LESS REAR SITES

[illegible]

## NOTES

1. LEVELS ARE IN TERMS OF AUCKLAND VERTICAL DATUM (MSL) 1946  
ORIGIN = RM3982 S054493
2. COORDINATES ARE IN TERMS OF GEODETIC DATUM MOUNT EDEN 2000 CIRCUIT
3. CONTOURS ARE AT 0.25m INTERVALS
4. COMPRISED IN CT NA101D/827
5. CERTIFICATE OF TITLE AREA 3342m<sup>2</sup>
6. LOCAL AUTHORITY - AUCKLAND COUNCIL
7. PROPERTY BOUNDARIES HAVE BEEN SOURCED FROM THE LINZ SPATIAL DATABASE AND ARE ACCURATE FOR TOPOGRAPHICAL PURPOSES ONLY. WHERE CRITICAL, BOUNDARY DIMENSIONS SHOULD BE CONFIRMED BY LAND TRANSFER SURVEY.
8. CERTAIN DRAINAGE AND UNDERGROUND SERVICE INFORMATION HAS BEEN PLOTTED FROM SERVICE PROVIDERS RECORDS, LOCATION SHOULD BE VERIFIED ON SITE.
9. WHERE THE ROAD OPENING NOTICE IS TO BE APPLIED FOR AND OBTAINED BY CONTRACTOR PRIOR TO ANY WORK COMMENCING ON ROAD RESERVE.
10. V SHAPE 200mm 20MPa CONCRETE ACCESS DRIVEWAY.

APEXONE LTD

36A EAGLEHURST ROAD  
ELLERSLIE  
AUCKLAND

COMMON ACCESS WAY  
PLAN 02 & PAVEMENT  
DETAIL DP 167980



**ENGINEERS • SURVEYORS • PLANNERS**

60 NEW NORTH ROAD, EDEN TERRACE  
PO BOX 10-343  
DOMINION ROAD  
AUCKLAND

TEL: +64-9-623-4573  
WEB: [www.bscl.co.nz](http://www.bscl.co.nz)

THE COPYRIGHT OF THIS DESIGN AND DRAWING IS  
VESTED IN BARRY SATCHELL CONSULTANTS LTD,  
UNLESS OTHERWISE INDICATED.

CAD Ref: P/8193/CAD/8193 301  
XREFS:

STATUS  
STAMP FOR RESOURCE CONSENT

SCALES (A1) 1: 125 (A3) 1: 250


JOB NO. 8149	DRAWING No. 302 SHT 1 OF 1	REVISION -
-----------------	----------------------------------	---------------

DRAWING NO.  
302  
SHEET 1 OF 1

REVISION  
-



- NOTES
6. PROPERTY BOUNDARIES HAVE BEEN SOURCED FROM THE LINZ SPATIAL DATABASE AND ARE ACCURATE FOR TOPOGRAPHICAL PURPOSES ONLY. WHERE CRITICAL, BOUNDARY DIMENSIONS SHOULD BE CONFIRMED BY LAND TRANSFER SURVEY.
7. CERTAIN DRAINAGE AND UNDERGROUND SERVICE INFORMATION HAS BEEN PLOTTED FROM SERVICE PROVIDERS RECORDS, LOCATION SHOULD BE VERIFIED ON SITE.
8. WHERE THE ROAD OPENING NOTICE IS TO BE APPLIED FOR AND OBTAINED BY CONTRACTOR PRIOR TO ANY WORK COMMENCING ON ROAD RESERVE.
9. V SHAPE 200mm 20MPa CONCRETE ACCESS DRIVEWAY.




MATCH IN WITH EXISTING GROUND WITH A 1:8 GRADE

Datum R.L.	30.00
FILL	0.77
CUT	0.69
FINISHED	34.58
NATURAL	35.35
Chainage	93.28

Scale Horizontal 1:200 Vertical 1:200 @ A3

EAGLEHURST	FRONT BOUNDARY	FIRST 4m	CAW CP 1	CROSS-SECTION A-A	1:177	CROSS-SECTION B-B	CAW CP 2	CROSS-SECTION C-C
Datum R.L.	30.00	1.92	1.99					
FILL						0.51		0.77
CUT	0.00	0.00	0.12	0.17				
FINISHED	34.00	34.04	33.98	33.94		34.20	34.23	34.56
NATURAL	34.00	34.04	34.10	34.11		34.71	34.71	35.31
Chainage	0.00	3.66	7.66	13.51		59.49	62.54	91.13

Scale Horizontal 1:200 Vertical 1:200 @ A3

SURVEY INFORMATION		REV	CHK	DATE	MODIFICATION	PROJECT	CLIENT	 <b>Barry Satchell</b> ENGINEERS - SURVEYORS - PLANNERS 60 NEW NORTH ROAD BALMORAL PO BOX 10-343 DOMINION ROAD AUCKLAND TEL: +64-9-623-4573 WEB: www.bscl.co.nz Email: admin@bscl.co.nz	SURVEYED	DRAWN	CHECKED	APPROVED
1. LEVELS ARE IN TERMS OF AUCKLAND VERTICAL DATUM (MSL) 1946 ORIGIN = RM3982 S054493 COORDINATES ARE IN TERMS OF GEODETIC DATUM MOUNT EDEN 2000 CIRCUIT CONTOURS ARE AT 0.25m INTERVALS COMPRISED IN CT NA101D/827 CERTIFICATE OF TITLE AREA 3342m²			PW	05/21	ORIGINAL	36a EAGLEHURST ROAD ELLERSLIE	APEXONE LTD		OTHERS	PG	PG	DATE 19/05/24
						DRAWING TITLE	THE COPYRIGHT OF THIS DESIGN AND DRAWING IS VESTED IN BARRY SATCHELL CONSULTANTS LTD, UNLESS OTHERWISE INDICATED.		SCALE AS SHOWN (A3 ORIGINAL SIZE)	JOB NO. 8149	DRAWING No. 303	REVISION -
						COMMON ACCESS WAY LONG & CROSS SECTION			CAD Ref: P/B149/CAD/B149 301			



ORIGINAL SIZE A1  
0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150 160 170 180 190 200  
DO NOT SCALE - IF IN DOUBT, ASK



EAGLEHURST ROAD

**KEY:**

— SW —	NEW - STORMWATER
— SW —	EXIST - STORMWATER
— WW —	NEW - WASTEWATER
— WW —	EXIST - WASTEWATER
— WM —	WATER MAIN
●	MANHOLE - SW NEW
○	MANHOLE - SW EXISTING
●	MANHOLE - WW NEW
○	MANHOLE - WW EXISTING
■	CESSPIT
⊠	WATER METER FIRE
⊠	HYDRANT
⊠	SLUICE VALVE

SURVEYED			APPROVED BY	DATE
DESIGNED	-	-		
DRAWN	PG	05/21		
TRACED				
CHECKED	PW	05/21		
REVISION	CHANGES		CHECKED	DATE
-	ORIGINAL		PW	05/21
A	STROAGE TANK 01 RELOCATED, TEXT		PW	05/21
B	MOVE WATER OUT ROOT ZONE		PW	05/21

- NOTES**
- LEVELS ARE IN TERMS OF AUCKLAND VERTICAL DATUM (MSL) 1946  
ORIGIN = RM3982 SO 54493
  - COORDINATES ARE IN TERMS OF GEODETIC DATUM 2000
  - CONTOURS ARE AT 0.25m INTERVALS
  - COMPRISED IN CT NA 101D/827
  - CERTIFICATE OF TITLE AREA 3342m²
  - LOCAL AUTHORITY - AUCKLAND COUNCIL
  - ALL WORKS TO BE CARRIED OUT IN ACCORDANCE WITH AUCKLAND COUNCIL STANDARDS. ALL SEDIMENT CONTROL MEASURES TO BE IN PLACE PRIOR TO ANY WORK COMMENCING. WORKS ONLY TO COMMENCE UPON ENGINEERS WRITTEN ACCEPTANCE.
  - CONTRACTOR TO SEARCH, LOCATE AND CONFIRM ALL EXISTING SERVICES BEFORE COMMENCEMENT OF WORKS WHETHER SHOWN ON DRAWING OR NOT AND MAINTAIN RESPONSIBILITY FOR ALL SERVICES.
  - CONTRACTOR TO REINSTATE ALL AREAS TO ENGINEER/OWNERS SATISFACTION. MAINTAIN ACCESS TO SITE AT ALL TIMES.
  - ROAD OPENING NOTICE IS TO BE APPLIED FOR AND OBTAINED BY CONTRACTOR PRIOR TO ANY WORK COMMENCING ON ROAD RESERVE.

APEXONE LTD

36A EAGLEHURST ROAD  
ELLERSLIE  
AUCKLAND

PUBLIC WASTEWATER,  
SOAKHOLE STORMWATER  
AND WATER PLAN 01

**Barry Satchell**

60 NEW NORTH ROAD, EDEN TERRACE  
PO BOX 10-343  
DOMINION ROAD  
AUCKLAND  
TEL: +64-9-623-4573  
WEB: www.bscl.co.nz


THE COPYRIGHT OF THIS DESIGN AND DRAWING IS VESTED IN BARRY SATCHELL CONSULTANTS LTD, UNLESS OTHERWISE INDICATED.

CAD Ref: P/8149/CAD/8149 401  
XREFS:


STATUS  
STAMP FOR RESOURCE CONSENT

SCALES (A1) 1: 125 (A3) 1: 250














JOB NO.	DRAWING No.	REVISION
8149	401 SHT 1 OF 1	B







KEY:

	NEW - STORMWATER
	EXIST - STORMWATER
	NEW - WASTEWATER
	EXIST - WASTEWATER
	WATER MAIN
	MANHOLE - SW NEW
	MANHOLE - SW EXISTING
	MANHOLE - WW NEW
	MANHOLE - WW EXISTING
	CESSPIT
	WATER METER FIRE
	HYDRANT
	SLUICE VALVE

[illegible]

1. LEVELS ARE IN TERMS OF AUCKLAND VERTICAL DATUM (MSL) 1946  
ORIGIN = RM3982 SO 54493
2. COORDINATES ARE IN TERMS OF GEODETIC DATUM 2000
3. CONTOURS ARE AT 0.25m INTERVALS
4. COMPRISED IN CT NA 101D/827
5. CERTIFICATE OF TITLE AREA 3342m<sup>2</sup>
6. LOCAL AUTHORITY - AUCKLAND COUNCIL
7. ALL WORKS TO BE CARRIED OUT IN ACCORDANCE WITH AUCKLAND COUNCIL STANDARDS. ALL SEDIMENT CONTROL MEASURES TO BE IN PLACE PRIOR TO ANY WORK COMMENCING  
WORKS ONLY TO COMMENCE UPON ENGINEERS WRITTEN ACCEPTANCE.
12. CONTRACTOR TO SEARCH, LOCATE AND CONFIRM ALL EXISTING SERVICES BEFORE COMMENCEMENT OF WORKS  
WHETHER SHOWN ON DRAWING OR NOT AND MAINTAIN RESPONSIBILITY FOR ALL SERVICES.
13. CONTRACTOR TO REINSTATE ALL AREAS TO ENGINEER/OWNERS SATISFACTION. MAINTAIN ACCESS TO SITE AT ALL TIMES.
14. ROAD OPENING NOTICE IS TO BE APPLIED FOR AND OBTAINED BY CONTRACTOR PRIOR TO ANY WORK COMMENCING ON ROAD RESERVE.

APEXONE LTD

36A EAGLEHURST ROAD  
ELLERSLIE  
AUCKLAND

ELLERSLIE

AUCKLAND

PUBLIC WASTEWATER.  
SOAKHOLE STORMWATER  
AND WATER PLAN 02

## SOAKHOLE STORMWATER

AND WATER PLAN 02



60 NEW NORTH ROAD, EDEN TERRACE  
PO BOX 10-343  
DOMINION ROAD  
AUCKLAND

TEL: +64-9-623-4573  
WEB: [www.bscl.co.nz](http://www.bscl.co.nz)

THE COPYRIGHT OF THIS DESIGN AND DRAWING IS VESTED IN  
BARRY SATCHELL CONSULTANTS LTD, UNLESS OTHERWISE  
INDICATED.

CAD Ref: P/8149/CAD/8149 401  
XREFS:

STATUS  
STAMP FOR RESOURCE CONSENT

SCALES (A1) 1: 125 (A3) 1: 250

(A3) 1: 250

JOB NO.	DRAWING No.	REVISION
8149	402	A

8149

DRAWING No  
402

402





SHT 1.05

REVISION
A

A



ORIGINAL SIZE A1 0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150 160 170 180 190 200  
DO NOT SCALE - IF IN DOUBT, ASK



SURVEYED			APPROVED BY	DATE
DESIGNED	-	-		
DRAWN	PG	05/21		
TRACED				
CHECKED	PW	05/21		
REVISION	CHANGES		CHECKED	DATE
-	ORIGINAL		PW	05/21
A	SW LINE C, LENGTH, TEXT		PW	05/21

- NOTES
- LEVELS ARE IN TERMS OF AUCKLAND VERTICAL DATUM (MSL) 1946  
ORIGIN = RM3982 SO 54493
  - COORDINATES ARE IN TERMS OF GEODETIC DATUM 2000
  - CONTOURS ARE AT 0.25m INTERVALS
  - COMPRISED IN CT NA 101D/827
  - CERTIFICATE OF TITLE AREA 3342m<sup>2</sup>
  - LOCAL AUTHORITY - AUCKLAND COUNCIL
  - ALL WORKS TO BE CARRIED OUT IN ACCORDANCE WITH AUCKLAND COUNCIL STANDARDS. ALL SEDIMENT CONTROL MEASURES TO BE IN PLACE PRIOR TO ANY WORK COMMENCING. WORKS ONLY TO COMMENCE UPON ENGINEERS WRITTEN ACCEPTANCE.
  - CONTRACTOR TO SEARCH, LOCATE AND CONFIRM ALL EXISTING SERVICES BEFORE COMMENCEMENT OF WORKS WHETHER SHOWN ON DRAWING OR NOT AND MAINTAIN RESPONSIBILITY FOR ALL SERVICES.
  - CONTRACTOR TO REINSTATE ALL AREAS TO ENGINEER/OWNERS SATISFACTION. MAINTAIN ACCESS TO SITE AT ALL TIMES.
  - ROAD OPENING NOTICE IS TO BE APPLIED FOR AND OBTAINED BY CONTRACTOR PRIOR TO ANY WORK COMMENCING ON ROAD RESERVE.

APEXONE LTD

36A EAGLEHURST ROAD  
ELLERSLIE  
AUCKLAND

DRIVEWAY TO SOAKHOLE  
LONGSECTIONS

 **Barry  
Satchell**

60 NEW NORTH ROAD, EDEN TERRACE  
PO BOX 10-343  
DOMINION ROAD  
AUCKLAND  
TEL: +64-9-623-4573  
WEB: www.bscl.co.nz


THE COPYRIGHT OF THIS DESIGN AND DRAWING IS VESTED IN BARRY SATCHELL CONSULTANTS LTD, UNLESS OTHERWISE INDICATED.

CAD Ref: P/8149/CAD/8149 401  
XREFS:


STATUS  
STAMP FOR RESOURCE CONSENT




SCALES (A1) 1: 100 (A3) 1: 200

JOB NO.	DRAWING No.	REVISION
8149	403	A
	SHT 1 OF 1	




- NOTES
7. ALL WORKS TO BE CARRIED OUT IN ACCORDANCE WITH AUCKLAND COUNCIL STANDARDS. ALL SEDIMENT CONTROL MEASURES TO BE IN PLACE PRIOR TO ANY WORK COMMENCING. WORKS ONLY TO COMMENCE UPON ENGINEERS WRITTEN ACCEPTANCE.
12. CONTRACTOR TO SEARCH, LOCATE AND CONFIRM ALL EXISTING SERVICES BEFORE COMMENCEMENT OF WORKS WHETHER SHOWN ON DRAWING OR NOT AND MAINTAIN RESPONSIBILITY FOR ALL SERVICES.
13. CONTRACTOR TO REINSTATE ALL AREAS TO ENGINEER/OWNERS SATISFACTION. MAINTAIN ACCESS TO SITE AT ALL TIMES.
14. ROAD OPENING NOTICE IS TO BE APPLIED FOR AND OBTAINED BY CONTRACTOR PRIOR TO ANY WORK COMMENCING ON ROAD RESERVE.



SURVEY INFORMATION				REV	CHK	DATE	MODIFICATION	PROJECT		CLIENT		 <b>Barry Satchell</b> ENGINEERS - SURVEYORS - PLANNERS		SURVEYED	DRAWN	CHECKED	APPROVED
1. LEVELS ARE IN TERMS OF AUCKLAND VERTICAL DATUM (MSL) 1946 ORIGIN = RM3982 SO 54493				-	PW	05/21	ORIGINAL	36a EAGLEHURST ROAD ELLERSLIE		APEONE LTD		 <b>Barry Satchell</b> ENGINEERS - SURVEYORS - PLANNERS  60 NEW NORTH ROAD BALMORAL PO BOX 10-343 DOMINION ROAD AUCKLAND  TEL: +64-9-623-4573 WEB: www.bscl.co.nz Email: admin@bscl.co.nz  THE COPYRIGHT OF THIS DESIGN AND DRAWING IS VESTED IN BARRY SATCHELL CONSULTANTS LTD, UNLESS OTHERWISE INDICATED.		OTHERS	PG	PW	
2. COORDINATES ARE IN TERMS OF GEODETIC DATUM 2000										SCALE 1:200 (A3 ORIGINAL SIZE)				DATE 16/05/21			
3. CONTOURS ARE AT 0.25m INTERVALS								DRAWING TITLE		JOB NO. 8149				DRAWING No. 404		REVISION -	
4. COMPRISED IN CT NA 101D/827								STORMWATER LINES A & B LONGSECTIONS									
5. CERTIFICATE OF TITLE AREA 3342m²																	
6. LOCAL AUTHORITY - AUCKLAND COUNCIL																	





SURVEY INFORMATION

1. LEVELS ARE IN TERMS OF AUCKLAND VERTICAL DATUM (MSL) 1946  
ORIGIN = RM3982 SO 54493  
2. COORDINATES ARE IN TERMS OF GEODETIC DATUM 2000  
3. CONTOURS ARE AT 0.25m INTERVALS  
4. COMPRISED IN CT NA 101D/827  
5. CERTIFICATE OF TITLE AREA 3342m²  
6. LOCAL AUTHORITY - AUCKLAND COUNCIL

REV	CHK	DATE	MODIFICATION
-	PW	05/21	ORIGINAL

PROJECT

36a EAGLEHURST ROAD  
ELLERSLIE

DRAWING TITLE

PUBLIC WASTEWATER  
LINES 1 & 2 LONGSECTIONS

CLIENT

APEXONE LTD

THE COPYRIGHT OF THIS DESIGN AND DRAWING IS  
VESTED IN BARRY SATCHELL CONSULTANTS LTD,  
UNLESS OTHERWISE INDICATED.

Barry  
Satchell

ENGINEERS - SURVEYORS - PLANNERS

60 NEW NORTH ROAD  
BALMORAL  
PO BOX 10-343  
DOMINION ROAD  
AUCKLAND

TEL: +64-9-623-4573  
WEB: www.bscl.co.nz  
Email: admin@bscl.co.nz

SURVEYED	DRAWN	CHECKED	APPROVED
OTHERS	PG	PW	<div><div></div><div>18/05/24</div></div>
SCALE	1:200 (A3 ORIGINAL SIZE)		
JOB NO. 8149	DRAWING No. 405	REVISION -	
CAD Ref: P/B149/CAD/8149 401			



DO NOT SCALE - IF IN DOUBT, ASK

ORIGINAL SIZE A1

## GENERAL CONSTRUCTION NOTES

### STANDARDS RELATING TO WORKS

Works shall be carried out to the requirements of the Health & Safety at Work in Employment Act 2015

Works shall be completed to Watercare Construction Standards.

### MANUFACTURERS SPECIFICATIONS

Materials shall be installed to the Manufacturers requirements unless otherwise specified.

### WELDING & FIXINGS

All steelwork shall be workshop fabricated.

Steelwork and fixings shall be hot-dip galvanized to AS/NZS 4680 unless otherwise stated.

A Nickel anti-seize free of copper, lead, sulphides, chlorides & carbons (graphite) shall be used on bolts.

### REINFORCING STEEL


Reinforcing shall be centrally placed with the specified minimum cover.

Bends shall be cold formed.

### JOINT SEALS

Flanges : Per WSL Material Standard.


Manhole Joints : Concrete manhole with flexible joint seal such as rubber or butyl.  
All joints must be externally wrapped with an accepted tape wrapped system.  
Alternative materials to suppliers' specifications.



### NOTES

1. Applies to concrete, V-bond, or PVC pipe saddle connections only. For other materials refer WWS 1.
2. The maximum lateral pipe size shall be less than half of the manhole.
3. For pipe lateral to main runs outside the above parameters, refer to WWS15, or a manhole shall be constructed where approved.
4. If the existing sewer pipe has PE or CPSP liner, specific design & approval required from Watercare.
5. Refer to Watercare Point-of-Supply Policy.

## SADDLE CONNECTIONS TO GRAVITY PUBLIC WASTEWATER





### TYPICAL SECTION A-A THROUGH MANHOLE

1. L10 supplied to WWS-10-72 loading and compliance certified.
2. When the throat depth is greater than 450mm, a new manhole riser is required with a new adjustment ring.
3. Refer drawing WWS for manhole details deeper than 1.5m.
4. Refer drawing WWS for manhole details.
5. Approved Safety Grille below access manhole cover.
6. Manhole covers in the road shall be constructed so that the cover hinges in at 90 degrees from the ladder. Other side, (Refer Fig 2).
7. For all other covers the orientation should be so that the cover hinge is at 90 degrees from the ladder. Other side, (Refer Fig 2).

### Fig 1

### Fig 2

## TYPICAL MANHOLE THROAT AND COVER DETAILS



SURVEYED		APPROVED BY	DATE
DESIGNED	PG	05/21	16/05/21
TRACED			
CHECKED	PW	05/21	
REVISION	CHANGES	CHECKED	DATE
-	ORIGINAL	PW	05/21

### NOTES

1. LEVELS ARE IN TERMS OF AUCKLAND VERTICAL DATUM (MSL) 1946  
ORIGIN = RM3982 SO 54493
2. COORDINATES ARE IN TERMS OF GEODETIC DATUM 2000
3. CONTOURS ARE AT 0.25m INTERVALS
4. COMPRISED IN CT NA 101D/827
5. CERTIFICATE OF TITLE AREA 3342m²
6. LOCAL AUTHORITY - AUCKLAND COUNCIL
7. ALL WORKS TO BE CARRIED OUT IN ACCORDANCE WITH AUCKLAND COUNCIL STANDARDS. ALL SEDIMENT CONTROL MEASURES TO BE IN PLACE PRIOR TO ANY WORK COMMENCING. WORKS ONLY TO COMMENCE UPON ENGINEERS WRITTEN ACCEPTANCE.
12. CONTRACTOR TO SEARCH, LOCATE AND CONFIRM ALL EXISTING SERVICES BEFORE COMMENCEMENT OF WORKS WHETHER SHOWN ON DRAWING OR NOT AND MAINTAIN RESPONSIBILITY FOR ALL SERVICES.
13. CONTRACTOR TO REINSTATE ALL AREAS TO ENGINEER/OWNERS SATISFACTION. MAINTAIN ACCESS TO SITE AT ALL TIMES.
14. ROAD OPENING NOTICE IS TO BE APPLIED FOR AND OBTAINED BY CONTRACTOR PRIOR TO ANY WORK COMMENCING ON ROAD RESERVE.

APEXONE LTD

36A EAGLEHURST ROAD  
ELLERSLIE  
AUCKLAND

WASTEWATER AND WATER  
TYPICAL DETAILS

Barry Satchell

60 NEW NORTH ROAD, EDEN TERRACE  
PO BOX 10-343  
DOMINION ROAD  
AUCKLAND  
TEL: +64-9-623-4573  
WEB: www.bscl.co.nz

THE COPYRIGHT OF THIS DESIGN AND DRAWING IS VESTED IN BARRY SATCHELL CONSULTANTS LTD, UNLESS OTHERWISE INDICATED.

CAD Ref: P/8149/CAD/8149.401  
XREFS:

STATUS  
STAMP FOR RESOURCE CONSENT

SCALES (A1) 1: AS SHOWN (A3) 1: AS SHOWN

JOB NO. 8149 DRAWING No. 406 REVISION -  
SHT 1 OF 1

## GENERAL CONSTRUCTION NOTES

### STANDARDS RELATING TO WORKS

Works shall be carried out to the requirements of the Health & Safety at Work in Employment Act 2015

Works shall be completed to Watercare Construction Standards.

### MANUFACTURERS SPECIFICATIONS

Materials shall be installed to the Manufacturers requirements unless otherwise specified.

### WELDING & FIXINGS

All steelwork shall be workshop fabricated.

Steelwork and fixings shall be hot-dip galvanized to AS/NZS 4680 unless otherwise stated.

A Nickel anti-seize free of copper, lead, sulphides, chlorides & carbons (graphite) shall be used on bolts.

### REINFORCING STEEL


Reinforcing shall be centrally placed with the specified minimum cover.

Bends shall be cold formed.

### JOINT SEALS


Couplings & Flanges : Per WSL Material Standard.

Concrete joints around pipe penetrations through chambers shall be made with a suitable hydrophilic sealant to the manufacturer's requirements. Concrete repair shall be reinforced and box-cast to prevent cracking from sealant forces.




## DOMESTIC WATER METER CONNECTION

15mm, 20mm & 25mm DIAMETER




## FLANGED SLUICE VALVE DETAIL



## **Appendix G:**

### **Firefighting supply data, WaterCare connections**





**DISCLAIMER:**  
This map/plan is illustrative only and all information should be independently verified on site before taking any action.  
Copyright Auckland Council. Land Parcel Boundary information from LINZ (Crown Copyright Reserved). Whilst due care has been taken, Auckland Council gives no warranty as to the accuracy and plan completeness of any information on this map/plan and accepts no liability for any error, omission or use of the information. Height datum: Auckland 1946.

36A Eaglehurst Rd

0 1.5 3 4.5  
Meters

Scale @ A4  
= 1:250


Date Printed:  
2/12/2020



## **Appendix H**

### **Earthworks and GIS Overland Flowpath**





**KEY:**

MIXED HOUSING SUBURBAN ZONE	CUT AREA = 2551m <sup>2</sup>
	CUT VOLUME = 545m <sup>3</sup>
LIGHT INDUSTRY ZONE	CUT AREA = 179m <sup>2</sup>
	CUT VOLUME = 165m <sup>3</sup>
<b>TOTAL</b>	<b>CUT AREA = 2730m<sup>2</sup></b>
	<b>CUT VOLUME = 710m<sup>3</sup></b>
---	SILT FENCE

- STAGES**
1. INSTALL SUPER SILT FENCE (GD05), STABILISED CONSTRUCTION ENTRANCE & WHEEL WASH IF REQUIRED.
  2. REMOVE EXISTING BUILDINGS.
  3. INSTALL WW PUBLIC LINES AND SW SOAKHOLE AND LINES AND SW, WW CONNECTIONS TO EACH SITE.
  4. UNDERTAKE SUBDIVISION SITE WORKS, STRUCTURES, ROW AND SERVICES INSTALLATIONS
  5. KEEP ALL SILT AND SEDIMENT MEASURES IN PLACE UNTIL THE SITE HAS BEEN FULLY STABILISED
  6. ENSURE SUPER SILT FENCE IS WELL MAINTAINED THROUGHOUT WORKS


SURVEYED			APPROVED BY	DATE
DESIGNED				
DRAWN	PG	12/20		
TRACED				
CHECKED	PW	12/20		
REVISION	CHANGES		CHECKED	DATE
-	ORIGINAL		PW	12/20
A	TEXT, HATCHING, LINES UPDATED		PW	06/21

- NOTES**
1. LEVELS ARE IN TERMS OF AUCKLAND VERTICAL DATUM (MSL) 1946
  2. COORDINATES ARE IN TERMS OF GEODETIC DATUM MOUNT EDEN 2000 CIRCUIT
  3. CONTOURS ARE AT 0.25m INTERVALS
  4. COMPRISED IN CT NA101D1827
  5. CERTIFICATE OF TITLE AREA 3342m<sup>2</sup>
  6. LOCAL AUTHORITY - AUCKLAND COUNCIL
  7. PROPERTY BOUNDARIES HAVE BEEN SOURCED FROM THE LINZ SPATIAL DATABASE AND ARE ACCURATE FOR TOPOGRAPHICAL PURPOSES ONLY. WHERE CRITICAL, BOUNDARY DIMENSIONS SHOULD BE CONFIRMED BY LAND TRANSFER SURVEY.
  8. CERTAIN DRAINAGE AND UNDERGROUND SERVICE INFORMATION HAS BEEN PLOTTED FROM SERVICE PROVIDERS RECORDS, LOCATION SHOULD BE VERIFIED ON SITE.
  9. WHERE THE ROAD OPENING NOTICE IS TO BE APPLIED FOR AND OBTAINED BY CONTRACTOR PRIOR TO ANY WORK COMMENCING ON ROAD RESERVE.
  10. V SHAPE 200mm 20MPa CONCRETE ACCESS DRIVEWAY.

APEXONE LTD

36A EAGLEHURST ROAD  
ELLERSLIE  
AUCKLAND

SILT AND SEDIMENT  
EARTHWORKS PLAN 01  
DP 167980



**Barry Satchell**

ENGINEERS • SURVEYORS • PLANNERS

60 NEW NORTH ROAD, EDEN TERRACE  
PO BOX 10-343  
DOMINION ROAD  
AUCKLAND

TEL: +64-9-623-4573  
WEB: www.bscl.co.nz

THE COPYRIGHT OF THIS DESIGN AND DRAWING IS VESTED IN BARRY SATCHELL CONSULTANTS LTD, UNLESS OTHERWISE INDICATED.

CAD Ref: P/193/CAD/193 301  
XREFS:

STATUS  
STAMP FOR RESOURCE CONSENT

SCALES (A1) 1: 125 (A3) 1: 250

JOB NO.	DRAWING No.	REVISION
8149	201	A
SHT 1 OF 1		









0 5 10 15  
Meters

Scale @ A3  
= 1:500

Date Printed:  
2/12/2020

36A Eaglehurst Rd

**DISCLAIMER:**  
This map/plan is illustrative only and all information should be independently verified on site before taking any action. Copyright Auckland Council. Land Parcel Boundary information from LINZ (Crown Copyright Reserved). Whilst due care has been taken, Auckland Council gives no warranty as to the accuracy and plan completeness of any information on this map/plan and accepts no liability for any error, omission or use of the information.  
Height datum: Auckland 1946.