

Drainage, Earthworks and Overland Flowpath Report

**22 and 22a SUMMIT DRIVE,
MOUNT ALBERT, AUCKLAND**

For

A&Y CONTRACTOR LIMITED
MAY 2025-Rev A

Report Prepared by:
Shehan Attanayaka
Civil Engineer

Reviewed By:
Chong Jin Khaw
Director

Anchor Consultants Limited

PO Box 34810, Birkenhead
Auckland 0746
New Zealand

This document is the property of Anchor Consultants Limited.
© Anchor Consultants Limited 2013

TABLE OF CONTENTS

1.0	Introduction	3
2.0	Site Description	3
2.1	Site Location and Legal Description	3
2.2	Site Description	4
2.3	Topography	5
3.0	Development Proposal	5
4.0	Earthworks Management	8
4.1	Stability	8
4.2	Erosion and Sediment Control	8
5.0	Stormwater Management	8
5.1	Stormwater Discharge	8
5.2	Overland Flowpath	9
6.0	AUP Considerations	10
6.1	Earthworks	10
6.2	Flooding	14
7.0	Conclusion	14

APPENDIX A - Anchor Consulting Ltd – Engineering Plans

APPENDIX B - Soakage Calculations

APPENDIX C - Detention Tank Calculations

APPENDIX D - OLFP Calculation

1.0 Introduction

Anchor Consulting Ltd has been engaged by A&Y Contractor Limited to prepare a Drainage and Overland Flowpath Report to assess proposed earthworks and to inform the design of excavations and retaining systems. It also assesses the suitability of proposed utility services and the impact of an overland flow path that is shown as running through the site on construction of two new dwellings at 22 and 22a Summit Drive, Mount Albert.

This report has been prepared in support of a land use consent application to Auckland Council to construct two new houses on two recently created freehold allotments. The assessment is based on a site inspection, topographical survey data as well as publicly available information from Auckland Council. The information provided herein is also informed by a geotechnical site investigation prepared by Geostudio and Architectural Design Plans prepared by 10x10 Architecture.

2.0 Site Description

2.1 Site Location and Legal Description

The 'site' that is the subject of the resource consent application for construction of two houses, which this Drainage, Earthworks and Overland Flowpath Report has been prepared to support is Lot 1 DP 603808 (22 Summit Drive) and Lot 2 DP 603808 (22a Summit Drive). The location of the site (22 & 22a Summit Drive, Mt Albert, Auckland) is identified on the map below.




Figure 1.0 – Locality Plan.

The site area is 932m² (gross), being 597m² (net) within 22 Summit Drive and 616m² (Net/Gross) within 22a Summit Drive, more or less. DP 603808 has been deposited and Records of Title for 22 and 22a Summit Drive have been issued.

2.2 Site Description

The site is shown on the aerial image below. Neighbouring buildings and properties are also shown on the below image. Our site visit established that the site is currently vacant.



Figure 2.0 – Nearmaps March 2025 Aerial

2.3 Topography

The land within the site is slopes downward from its south-western boundary towards the north-eastern boundary.

Refer to Appendix B, which contains a topographical survey plan prepared by Anchor Consulting Ltd. The plan shows ground levels and contours within the site.

3.0 Development Proposal

This report is prepared to support a land use consent application to construct the proposed residential buildings, as noted above. The proposed development comprises construction of two new houses as well as underground services and access.

The resource consent application is for consent to construct two houses on two recently created properties/titles. While this report addresses earthworks as they will occur across the two properties, for consistency with the resource consent application, 22 and 22a Summit Drive fall within the AUP definition of separate sites, as each is contained in a single lot on an approved survey plan and has a separate Record of Title. Therefore, reference to the site as being/comprising both allotments is an application of the interpretation of 'site' that is being applied for consistency only. Furthermore, any consent that is required for earthworks across two sites is limited to a consent for technical non-compliance only.

Earthworks

It is proposed to undertake and complete the necessary earthworks in one stage. The work undertaken would include cut/fill, topsoil spreading as well as the sowing/germination of grass. The completion date will depend on weather conditions.

A suitably qualified and experienced Geotechnical Engineer will be engaged by the client to check and monitor the earthworks. A Structural Engineer will be engaged by the client to monitor construction of the retaining walls and building foundations.

The earthworks will be managed and mitigated as per GD-05 erosion and sediment control design guidelines.

Below is a summary of the proposed earthworks.

The proposed Lot 1 earthworks will affect approximately 405m² of the site. The approximate earthworks volumes are provided below:

Bulk Cut (solid measure)	150m ³
Bulk Fill (solid measure)	40m ³
Net Cut – to be exported (solid measure)	110m ³

The proposed Lot 2 earthworks will affect approximately 405m² of the site. The approximate earthworks volumes are provided below:

Bulk Cut (solid measure)	100m ³
Bulk Fill (solid measure)	20m ³
Net Cut – to be exported (solid measure)	80m ³

Below is the combined earthworks area and volumes.

Earthworks Area = 810m²

Bulk Cut (solid measure)	250m ³
Bulk Fill (solid measure)	60m ³
Net Cut – to be exported (solid measure)	190m ³

Access and Utilities

Vehicular access to the proposed buildings will be provided via the existing shared driveway.

Individual electricity, telecommunication, and water lines have already been installed beneath the shared driveway to service the development.

Sewage Drainage

Auckland Council's GIS (Geomaps) indicates the presence of an existing public sewer line which runs beneath the access leg into the site (22 Summit Dr) and adjacent to the north-west boundary, within the developable part of the site. Individual sewer stub connections were installed during the recently completed subdivision (DP 603808).

The proposal is to utilise the existing individual sewer connections. Separate private laterals will be installed from these stub connections to serve the two dwellings within the proposed development.

The position of the existing public sewer manhole and line and individual private connections/laterals is shown on Anchor Consulting Drainage Plan RC-107 (see Appendix A).

Stormwater Drainage

The site has been investigated to determine the feasibility of stormwater disposal via deep bore soakage. Two borehole tests - one within each lot - have been carried out. The results indicate that the site is underlain by suitable soil conditions, confirming that it is well-suited for this type of stormwater management system.

Individual deep bore soakage systems will be constructed to serve each lot.

Roof-water runoff from the dwellings will be directed into proposed settling chambers before discharging into the soakage chambers. Surface-water runoff from the driveway will be collected and treated as required before being conveyed to the same soakage system, ensuring compliance with stormwater management guidelines.

The proposed stormwater drainage layout is shown on Anchor Consulting Drainage Plans (See Appendix A).

Other Aspects of Proposal

The enabling works required to facilitate the development include site clearing and earthworks for the construction of the proposed buildings, private driveway, retaining walls, and sealed surfaces.

The proposal includes introduction of an additional ROW easement, which will be created under s348 of the LGA and will be over Lot 1 in favour of Lot 2. The proposed easement will be created to support and protect access rights over the driveway to Lot 2 for the owners/occupants of that property.

The proposed right of way easement, as shown on Anchor proposed right of way plan RC-101 will be registered on the property titles prior to occupation of the proposed dwellings.

4.0 Earthworks Management

4.1 Stability

The client engaged GeoStudio Ltd to conduct a preliminary geotechnical investigation. The geotechnical report prepared by Geostudio Ltd concludes that the land is generally suitable for the proposed development. The report includes recommendations for the design of building foundations, which will be complied with.

Refer to geotechnical report by GeoStudio Ltd for further detail.

4.2 Erosion and Sediment Control

As per GD-05, any sediment laden runoff that is generated from the works area will be controlled. In order to control sediment/silt runoff, silt fences, and an entrance stabiliser are proposed to control sediment that is generated during construction.

Further to the control measures discussed above, it is proposed that:-

The installed sediment control measures will be inspected by an appropriately qualified and experienced engineer to certify that all proposed methods/structures have been constructed and are operating in accordance with the erosion and sediment control plan.

An appropriately qualified and experienced engineer will be engaged to monitor the sediment control measures on a regular basis (fortnightly) and after every significant rainfall event to ensure that the measures are maintained to the correct standard and are in accordance with the erosion and sediment control plan.

Contact details for the site manager will be displayed on site. The site manager will be contactable in the event of an emergency.

Please refer to Appendix A, which contains the proposed earthworks and erosion and sediment control plans (Anchor Erosion and Sediment Control Plans RC-102 and RC-103).

5.0 Stormwater Management

5.1 Stormwater Discharge

It is proposed to install soakage chambers (Deep Bore Soakage) within each lot to service the proposed development. Two deep bore soakage tests have been undertaken, both of which produced favourable results, indicating that the underlying soil conditions are suitable for a soakage-based stormwater solution. For the location of the soakage holes, refer to Anchor Consulting Plan RC-107 (Appendix B).

Intorock Drilling was engaged to carry out site investigations and perform the soakage testing. A summary of the borehole flow rates recorded during the initial test is provided below.

Borehole Number (BH)	Flows (l/s)
1 (Lot 1-22 Summit Drive)	8.0
3 (Lot 2-22a Summit Drive)	8.7

GD-07 has been used to calculate the borehole capacity.

Below is a tabulated summary of the peak discharge and the borehole capacity (with factor of safety).

Lot Number	BH Capacity w/ Factor of Safety Applied (l/s)	Site Peak Discharge 10 ARI (l/s)	Additional Storage Min (l/s)
1	6.7	11.75	1.26m ³
2	7.25	12.75	1.71m ³

Based on the information provided above, the two soak holes tested do not have sufficient capacity to service the development on their own. As a result, additional detention storage is proposed to supplement the system. With this added storage, the two proposed soakage manholes will have adequate capacity to contain and dispose of stormwater runoff from the proposed development.

Please refer to Appendix B for soakage test results and calculations.

Please refer to Appendix C for tank calculations.

5.2 Overland Flowpath

A site walk-over was conducted to verify the location of the Overland Flow Path (OLFP) as shown on Auckland Council's GIS (Geomaps). The inspection confirmed that the OLFP is minor flow and that the actual alignment of the flow path is consistent with what is shown on the Council GIS.

The proposed development will maintain the existing ground level along the south-eastern boundary to preserve the OLFP entry point. A V-shaped channel is proposed to divert flows toward the OLFP exit point, ensuring that overland flow is appropriately managed.

The contributing catchment area used in our assessment to determine the 100-year storm water level was derived from Council's GIS records. A summary of our assessment is provided below.

The design parameters used to calculate water depths within the proposed channel are as follows:

$$Q_{100} = 0.1 \text{ m}^3/\text{s} \text{ (Based From GIS)}$$

V Channel = 1.5mWx0.25mD

The Flowmaster program was used to determine water depths along the OLFP channel. Below is a summary table of the 100-year flood levels within the overland flow path.

The below tables also present the OLFP details as identified in Anchor OLFP RC-115 (Section A-A), along with the projected water depths within the flow path during a 100-year storm event.

A summary of the calculated flows and water levels within the OLFP channel is provided within the tables.

Section	Width (m)	Top of Overland Flowpath Channel (Assume)	Bottom of Overland Flowpath Channel (Assume)
A-A	1.5m	10.0m	9.75m

Section	100yr Water Level (R.L)	Depth of 100yr Water Level (mm)
A-A	9.86m	110

Based on the above analysis, the 100-year flood level will be fully contained within the proposed V-shaped channel and will not impact the proposed building.

Please refer to Appendix D for OLFP calculations.

6.0 AUP Considerations

6.1 Earthworks

Rule E12.4.1 (A48) provides for earthworks affecting greater than 500m² but less than 1,000m² of land in a residential zone as a restricted discretionary activity and E12.4.1(A8) provides for earthworks in the residential zone which result in the disturbance of greater than 250m³ and less than 1000m³ of material as a restricted discretionary activity.

Separately the earthworks within 22 and 22a Summit Drive do not exceed the permitted limits, but combined the maximum limits are exceeded.

Activity Table E12.4.2 sets out earthworks rules for sites in an overlay area, except sites in an Outstanding Natural Features Overlay. This site is subject to several overlays, including the Outstanding Natural Features Overlay and these rules appear not to apply to this proposal. However, the site is also affected by a number of other overlays. If it is Councils view that the proposal must be assessed against rules in Activity Table E12.4.2 then consent should be granted under those rules.

The site is in the Special Character Areas Overlay Residential and Business - Mt Albert, Residential Isthmus C. Rule E12.4.2 (32) and (33) both require that

earthworks in this overlay area that either exceed 5m³ and are up to 250m² or are in excess of 250m³ require consent as a discretionary activity. The earthworks as measured within both separately within each lot or in the combined overall site exceed 5m³ so consent would be required as a discretionary activity under these rules.

Activity Table E12.4.3 sets out rules for earthworks in an Outstanding Natural Features Overlay area. Rule E12.4.3 (A41) requires that earthworks exceeding 50m³ require consent as a restricted discretionary activity.

If the proposal is assessed as a discretionary activity, we understand that Council is not limited in the matters that it can consider in its assessment of the proposal. The limitation on assessment matters notwithstanding, we believe the assessment matters in rule E12.8.2 for restricted discretionary activities should be considered, as they cover effects that are relevant to this proposal.

For an assessment of the full range of effects that will be created by this proposal please refer to the assessment of environmental effects provided within the associated resource consent application.

(a) Whether applicable standards are complied with;

All earthworks will comply with standard council construction requirements, i.e., the period of the day in which the works can be undertaken and maximum permissible noise levels for construction machinery.

(b) The extent to which the earthworks will generate adverse noise, vibration, odour, dust, lighting and traffic effects on the surrounding environment and the effectiveness of proposed mitigation measures;

All earthworks will comply with standard council construction noise, vibration etc. requirements.

The site is located in a good soakage area. The maximum proposed cut at this site is 1.4m (Lot 1 building). Log reports by Intorock Drilling indicate that the depth of basalt rock is 2.5m below the ground surface; as the deepest excavation proposed is 1.4m there is no requirement for rock breaking.

Vibration and noise for general earthworks activities will therefore be able to be managed so as to be within AUP required limits. Noise will be monitored as per best practice.

(c) Whether the earthworks and any associated retaining structures are designed and located to avoid adverse effects on the stability and safety of surrounding land, buildings, and structures.

The civil contractor will work with the Geotech engineer during the earthworks phase. The combined approach to the management of the construction works will

ensure that the works are completed in accordance with the recommendations of the geotechnical report. The Geotech Engineer will monitor the work and will provide additional recommendations if any soil stability or other issues are identified during the construction stage.

(d) Whether the earthworks and final ground levels will adversely affect overland flow paths or increase potential volume or frequency of flooding within the site or surrounding sites.

An overland flow path (2,000m² to 4,000m² flow path catchment) is shown as entering the site via the south-east boundary and exiting toward the north. The entry and exit points of the flow path will not change and the earthworks will not otherwise adversely impact on the OLFP, as assessed below and shown on Anchor OLFP Plan RC-115.

(e) Whether the protocol for the accidental discovery of koiwi, archaeology and artefacts of Māori origin has been provided and the effectiveness of the protocol in managing the impact on Mana Whenua cultural heritage if discovery is made.

An accidental discovery condition is nominated to support the application for consent for the proposed earthworks. An archaeological report supporting the application identifies no specific pre-colonial features within the subject land and consultation with Mana Whenua has been undertaken as part of the overall application.

(f) Whether the extents or impacts of adverse effects from the land disturbance can be mitigated by managing the duration, season or staging of such works;

Sediment control devices are proposed to control sediment within the site during construction (see Erosion and Sediment Control Plans RC-102 and RC-103 in Appendix A). The silt and sediment control system has been designed taking account of the nature and scale of the proposed earthworks and will be effective in controlling sediment within the site.

It is expected that the earthworks will be completed in one stage. In the event that the works extend into the winter season, the mitigation measures being utilised will be upgraded, and monitoring frequencies will be increased where necessary.

(g) The extent to which the area of the land disturbance is minimised, consistent with the scale of development being undertaken;

The proposed earthworks have been designed as part of the development and are therefore consistent with the scale of the development.

(h) The extent to which the land disturbance is necessary to provide for the functional or operational requirements of the network utility installation, repair or maintenance.

The utility ducts/cables required for the operational requirements of the houses within the proposed lots will be located within a single trench, where possible. Other earthworks for the installation of services will be limited to just that which is required to meet servicing requirements. The extent of land disturbance has, therefore, been kept to a minimum.

(i) The extent or risk associated with natural hazards and whether the risks can be reduced or not increased;

No potential hazards were identified during our site visit. Construction of the proposed buildings is not, therefore, likely to increase the risk associated with natural or manmade hazards.

(j) Whether the land disturbance and final ground levels will adversely affect the existing utility services.

The civil contractor will undertake an appropriate investigation (potholing) in consultation with the utility company(s) to identify the exact location of the utility services located beneath the road berm. All necessary safety precautions and protections will be implemented during construction to avoid damage to public utility services.

(k) The extent to which the land disturbance is necessary to accommodate development otherwise provided for by the Plan ... including development proposed in a relevant operative reserve management plan or parks management plan;

The extent of land disturbance is contained within the site. The land disturbance is necessary to accommodate the proposed development. The residential use of the land is an activity that is provided for by the AUP in this zone.

(l) For land disturbance near Transpower New Zealand Limited Transmission towers:

(i) The outcome of any consultation with Transpower ... and

(ii) The risk to the structural integrity of transmission lines.

The proposed development is not close to transmission lines.

(m) The extent to which the earthworks avoid, minimise, or mitigate adverse effects on any archaeological sites that have been identified in the assessment of effects.

The site is not known to have special natural or historic heritage values.

6.2 Flooding


The proposed activity will not divert the entry or exit points of the flow paths or reduce their capacity. The proposed activity is therefore a Permitted Activity, as provided in activity table E36.4.1 (A39 & A40) - Development of new or redevelopment of existing impervious areas.

7.0 Conclusion

This report assesses the capacity of the public wastewater and stormwater networks to service the proposed development. It also evaluates the design of the proposed stormwater management system for compliance with the Council's Code of Practice. The OLFP (Overland Flow Path) entry and exit points will remain unchanged. The 100-year flood level will be safely contained within the proposed V-shaped channel, which is designed to divert the OLFP away from the proposed buildings.

It is noted that building consents will be required for the soakage device, storage tanks, private wastewater and stormwater lines, and individual lot driveway access. All necessary approvals will be obtained prior to the commencement of construction.

APPENDIX A - Anchor Consulting Ltd – Engineering Plans



REVISION				CHKD	DWN
ISSUE	DATE	DETAILS		CK	CL
A	09/05/25	RC APPLICATION			

NOTE:
 DATUM: GEODETIC 2000, MT EDEN
 ORIGIN: RM 6563 SO 53238 798952.044mN
 395863.772mE

LEVELS ARE IN TERMS OF NEW ZEALAND
 VERTICAL DATUM

ORIGIN OF LEVELS: RM 6563 SO 53238
 @ RL=93.52

CONTOURS SHOWN ARE AT 0.20 m INTERVALS.

ALL EASEMENTS, COVENANTS AND OTHER
 LEGAL INSTRUMENTS REGISTERED ON THIS SITE
 MAY NOT BE SHOWN ON THIS PLAN.
 INVESTIGATION IS REQUIRED TO BE UNDERTAKEN
 PRIOR TO DESIGN AND CONSTRUCTION.

SERVICES (EITHER OVERHEAD OR
 UNDERGROUND) SHOWN ON THIS PLAN MAY
 HAVE BEEN OBTAINED FROM THIRD PARTY
 RECORDS AND SHOULD BE VERIFIED ON SITE.

DRAWING TITLE
A & Y CONTRACTOR LIMITED

CLIENT
A & Y CONTRACTOR LIMITED

PROJECT
**22&22A SUMMIT DRIVE,
 MOUNT ALBERT, AUCKLAND**



ANCHOR CONSULTING LTD
 Tel: 021 66 99 46
 PO Box 34810, Birkenhead 0746, Auckland


SCALE:	1 : 100 @ A1	1 : 200 @ A3
DATE:	SEPTEMBER 2024	
SURVEYED BY:	CL&AV	DESIGNED BY: N/A
DRAWN BY:	CL	CHECKED BY: CK
PROJECT No.	DWG No.	REV.
A15-0082	RC-100	A



REVISION				
ISSUE	DATE	DETAILS	CHKD	DWN
A	09/05/25	RC APPLICATION	CK	SA

NOTES:

1. ALL DIMENSIONS & AREAS ARE APPROXIMATE AND MAY VARY UPON COMPLETION OF FINAL SURVEY.
2. EASEMENTS TO BE CREATED WHERE NECESSARY
3. EASEMENTS SUCH AS RIGHT TO OVERHANG, RIGHT FOR MAINTENANCE AND RIGHT TO CONVEY SW WILL BE CREATED WHEN NECESSARY ON ANY PARTS OF BUILDING / FOOT STRUCTURE THAT CROSS OVER FROM ONE LOT TO THE OTHER.



DRAWING TITLE
PROPOSED ROW PLAN TO BE GRANTED UNDER S348 OF THE LOCAL GOVERNMENT ACT 1974

CLIENT
A & Y CONTRACTOR LIMITED


PROJECT
22&22A SUMMIT DRIVE, MOUNT ALBERT, AUCKLAND



ANCHOR CONSULTING LTD
 Tel: 021 66 99 46
 PO Box 34810, Birkenhead 0746, Auckland


SCALE:	1 : 100 @ A1	1 : 200 @ A3
DATE:	APRIL 2025	
SURVEYED BY:	CL&AV	DESIGNED BY: N/A
DRAWN BY:	SA	CHECKED BY: CK
PROJECT No.	DWG No.	REV.
A15-0082	RC-101	A

PROPOSED EASEMENTS			
PURPOSE	SHOWN	SERVIENT TEN (BURDENED LAND)	DOMINANT TEN BENEFITED LAND
RIGHT OF WAY	X	LOT 1 DP 603808	LOT 2 DP 603808



REVISION				CHKD	DWN
ISSUE	DATE	DETAILS		CK	SA
A	09/05/25	RC APPLICATION			

NOTE:
 1. ALL TREES WITHIN THE SITE TO BE CUT & REMOVED OFFSITE

- LEGEND
-  ENTRANCE STABILIZER (INDICATIVE LOCATION)
 -  PROP SILT FENCE

DRAWING TITLE
EROSION AND SEDIMENT CONTROL PLAN


CLIENT
A & Y CONTRACTOR LIMITED

PROJECT
**22&22A SUMMIT DRIVE,
 MOUNT ALBERT, AUCKLAND**



ANCHOR CONSULTING LTD
 Tel: 021 66 99 46
 PO Box 34810, Birkenhead 0746, Auckland

SCALE :	1 : 150 @ A1	1 : 300 @ A3
DATE:	APRIL 2025	
SURVEYED BY :	CL&AV	DESIGNED BY: N/A
DRAWN BY:	SA	CHECKED BY: CK
PROJECT No.	DWG No.	REV.
A15-0082	RC-102	A



SIDE ELEVATION

STABILISED CONSTRUCTION ENTRANCE – SPECIFICATIONS: APPLICATION


USE A STABILISED CONSTRUCTION ENTRANCE AT ALL POINTS OF CONSTRUCTION SITE INGRESS AND EGRESS WITH A CONSTRUCTION PLAN LIMITING TRAFFIC TO THESE ENTRANCES ONLY. THEY ARE PARTICULARLY USEFUL ON SMALL CONSTRUCTION SITES BUT CAN BE UTILISED FOR ALL PROJECTS.

DESIGN:

1. CLEAR THE ENTRANCE AND EXIT AREA OF ALL VEGETATION, ROOTS AND OTHER UNSUITABLE MATERIAL AND PROPERLY GRADE IT.
2. PROVIDE DRAINAGE TO CARRY RUNOFF FROM THE STABILISED CONSTRUCTION ENTRANCE TO A SEDIMENT CONTROL MEASURE.
3. PLACE AGGREGATE TO THE SPECIFICATIONS BELOW AND SMOOTH IT.

STABILISED CONSTRUCTION ENTRANCE AGGREGATE SPECIFICATIONS:

AGGREGATE SIZE	50-75mm WASHED AGGREGATE
THICKNESS	150mm MINIMUM
LENGTH	10m MINIMUM
WIDTH	4m MINIMUM




PLAN VIEW
STABILISED CONSTRUCTION ENTRANCE

MAINTENANCE


1. MAINTAIN THE STABILISED CONSTRUCTION ENTRANCE IN A CONDITION TO PREVENT SEDIMENT FROM LEAVING THE CONSTRUCTION SITE. AFTER EACH RAINFALL INSPECT ANY STRUCTURE USED TO TRAP SEDIMENT FROM THE STABILISED CONSTRUCTION ENTRANCE AND CLEAN OUT AS NECESSARY.

NOTES:


1. ALL EROSION AND SEDIMENT CONTROL MEASURES MUST BE OPERATIONAL PRIOR TO ANY OTHER WORKS COMMENCING ON SITE. THE CONTRACTOR SHALL ARRANGE FOR AND ATTEND A PRELIMINARY SEDIMENT CONTROL MEETING ON-SITE WITH THE ENGINEER AND THE COUNCIL REPRESENTATIVE.
2. A COPY OF THE EROSION MANAGEMENT PLAN SHALL BE AVAILABLE ON THE SITE DURING WORK HOURS AND ALL PERSONNEL INVOLVED IN EARTHWORK ACTIVITIES ON THE SITE (INCLUSIVE OF SUB-CONTRACTORS) SHALL BE FAMILIAR WITH THE CONSENT AND PLAN REQUIREMENTS AS THEY RELATE TO EROSION AND SEDIMENT CONTROL.
3. THAT ALL "CLEANWATER" RUNOFF FROM STABILISED SURFACES INCLUDING CATCHMENT AREAS ABOVE THE SITE SHALL BE DIVERTED AWAY FROM EARTHWORK AREAS VIA STABILISED SYSTEM, SO AS TO PREVENT SURFACE EROSION.
4. ALL EROSION AND SEDIMENT CONTROL SHALL COMPLY WITH THE "EROSION AND SEDIMENT CONTROL GUIDELINES FOR LAND DISTURBING ACTIVITIES" GD05
5. FURTHER SEDIMENT CONTROL WORKS MAY BE REQUIRED BY THE ENGINEER AS THE PROJECT ADVANCES. THESE WILL BE INSTALLED AS AND WHERE DIRECTED BY THE ENGINEER.



ELEVATION



CROSS SECTION



PERSPECTIVE VIEW
SILT FENCE CONSTRUCTION

REVISION				
ISSUE	DATE	DETAILS	CHKD	DWN
A	09/05/25	RC APPLICATION	CK	SA

DRAWING TITLE
EROSION AND SEDIMENT CONTROL STANDARD DETAILS

CLIENT
A & Y CONTRACTOR LIMITED

PROJECT
22&22A SUMMIT DRIVE, MOUNT ALBERT, AUCKLAND



ANCHOR CONSULTING LTD
Tel: 021 66 99 46
PO Box 34810, Birkenhead 0746, Auckland

SCALE :	1 : 100 @ A1	1 : 200 @ A3
DATE:	APRIL 2025	
SURVEYED BY :	CL&AV	DESIGNED BY: N/A
DRAWN BY:	SA	CHECKED BY: CK
PROJECT No.	DWG No.	REV.
A15-0082	RC-103	A



REVISION				
ISSUE	DATE	DETAILS	CHKD	DWN
A	09/05/25	RC APPLICATION	CK	SA

LEGEND

	FILL AREA
	CUT AREA
	EARTHWORKS AREA
+RL -1.40	CUT DEPTH
+RL 1.00	FILL DEPTH

EARTHWORKS VOLUME

BULK CUT (SOLID MEASURE)	150 m3
BULK FILL (SOLID MEASURE)	40 m3
NET CUT (SOLID MEASURE)	110 m3

EARTHWORKS AREA = 405m2

DRAWING TITLE
CUT & FILL (LOT 1)


CLIENT
A & Y CONTRACTOR LIMITED

PROJECT
**22&22A SUMMIT DRIVE,
MOUNT ALBERT, AUCKLAND**



ANCHOR CONSULTING LTD
Tel: 021 66 99 46
PO Box 34810, Birkenhead 0746, Auckland

SCALE :	1 : 100 @ A1	1 : 200 @ A3
DATE:	APRIL 2025	
SURVEYED BY :	CL&AV	DESIGNED BY: N/A
DRAWN BY:	SA	CHECKED BY: CK
PROJECT No.	DWG No.	REV.
A15-0082	RC-105	A



LOT 20 DEEDS REG 376

LOT 21 DEEDS REG 376

LAND ON DP 28219

LOT 1 DP 481174

LOT 2 DP 481174

LOT 2

LOT 1

FFL=80.200

FFL=80.540

FFL=81.415

FFL=84.000

FFL=84.210

FFL=85.150

+RL 0.26

+RL 0.15

+RL 0.12

+RL 0.32

+RL 0.21

+RL -0.15

+RL -0.69

+RL -0.31

+RL -0.40

+RL 1.02

+RL 0.51

+RL 0.80

+RL 0.16

+RL -0.19

+RL -0.16

+RL -0.21

+RL -0.16

220°20'
(38.15)

19.00

310°20'
30.48

1.20

17.85

26.09

19.00

130°20'
(30.47)

2.02

2.22

40°20'
(43.18)

(78.38)

25.92

22.98



REVISION				CHKD	DWN
ISSUE	DATE	DETAILS		CK	SA
A	09/05/25	RC APPLICATION			

LEGEND

	FILL AREA
	CUT AREA
	EARTHWORKS AREA
+RL -1.40	CUT DEPTH
+RL 1.00	FILL DEPTH

EARTHWORKS VOLUME

BULK CUT (SOLID MEASURE)	100 m3
BULK FILL (SOLID MEASURE)	20 m3
NET CUT (SOLID MEASURE)	80 m3

EARTHWORKS AREA = 405m2

DRAWING TITLE
CUT & FILL (LOT 2)


CLIENT
A & Y CONTRACTOR LIMITED

PROJECT
**22&22A SUMMIT DRIVE,
MOUNT ALBERT, AUCKLAND**



ANCHOR CONSULTING LTD
Tel: 021 66 99 46
PO Box 34810, Birkenhead 0746, Auckland

SCALE :	1 : 100 @ A1	1 : 200 @ A3
DATE:	APRIL 2025	
SURVEYED BY :	CL&AV	DESIGNED BY: N/A
DRAWN BY:	SA	CHECKED BY: CK
PROJECT No.	DWG No.	REV.
A15-0082	RC-106	A




LAND ON DP 28219

LOT 20 DEEDS REG 376

LOT 21 DEEDS REG 376

LOT 1 DP 481174

LOT 2 DP 481174



REVISION				
ISSUE	DATE	DETAILS	CHKD	DWN
A	09/05/25	RC APPLICATION	CK	SA

LEGEND	
	EXISTING SEWER MANHOLE AND LINE
	PROP. 1200mmØ PRE CAST MANHOLE RISER (SOAKAGE CHAMBER)
	PROP. SETTLING CHAMBER 675Øx900mm DEEP (INDICATIVE LOCATION)
	PROP 100mmØ uPVC SW LINE
	PROP PRIVATE 150mmØ uPVC SW PIPE
	EX. 100mmØ uPVC SS LOT CONNECTION
	PROP 100mmØ uPVC SW LOT CONNECTION
	EX. FIELD CESSPIT
	PROP. FIELD CESSPIT
	PROP GRATED CHANNEL
	UNDERGROUND DETENTION TANK (AQUACOMB PODS) INDICATIVE LOCATION


DRAWING TITLE
DRAINAGE & DRIVEWAY PLAN

CLIENT
A & Y CONTRACTOR LIMITED

PROJECT
**22&22A SUMMIT DRIVE,
MOUNT ALBERT, AUCKLAND**



ANCHOR CONSULTING LTD Tel: 021 66 99 46 PO Box 34810, Birkenhead 0746, Auckland		
SCALE:	1 : 100 @ A1	1 : 200 @ A3
DATE:	APRIL 2025	
SURVEYED BY:	CL&AV	DESIGNED BY: N/A
DRAWN BY:	SA	CHECKED BY: CK
PROJECT No.	DWG No.	REV.
A15-0082	RC-107	A





REVISION				
ISSUE	DATE	DETAILS	CHKD	DWN
A	09/05/25	RC APPLICATION	CK	SA



DRAWING TITLE
**SOAKAGE CATCHMENT PLAN
 (LOT 1)**

CLIENT
A & Y CONTRACTOR LIMITED

PROJECT
**22&22A SUMMIT DRIVE,
 MOUNT ALBERT, AUCKLAND**



ANCHOR CONSULTING LTD
 Tel: 021 66 99 46
 PO Box 34810, Birkenhead 0746, Auckland

SCALE :	1 : 100 @ A1	1 : 200 @ A3
DATE:	APRIL 2025	
SURVEYED BY :	CL&AV	DESIGNED BY: N/A
DRAWN BY:	SA	CHECKED BY: CK
PROJECT No.	DWG No.	REV.
A15-0082	RC-108	A



BORE LOG SHEET

DATE: 24.11.15

CLIENT: Anchor Consulting
 DESCRIPTION OF WORK: Drill bore for soakage & test
 LOCATION: 22 Summit Drive, Mt Albert
 METHOD OF BORING: Percussion (DTH)
 BOREHOLE NO: One BOREHOLE DIA: 100mm
 BOREHOLE LD: BOREHOLE LOC: 6m x 5m from front right corner

Depth	Description	FLOW TEST		
		Meter Start	Meter Finish	Duration
1m	Ash			
2m	2.5m Boulders & Ash			
3m	3.4m			
4m				
5m				
6m				
7m				
8m				
9m				
10m	Scoria			
11m				
12m				
13m				
14m		Pro	Soak	10mins
15m		N/A	N/A	10mins
16m	15.5m	E.O.B	4,800L	/600sec 8.0L/sec
17m				
18m			Full	Hydrant
19m				Flow
20m				

Flow test result is only relevant to the actual time of testing.

Phone: 09 294 6181 Fax: 09 294 6182 Email: info@intorockdrilling.co.nz
 www.intorockdrilling.co.nz PO Box 79 DRURY 2247

9H1

APPENDIX B - WORKSHEETS

B9

Worksheet 3: Rockbore Constant Head Percolation Test (page 2 of 2)

Borehole number: One Test number: 1 of total no. 1

1. Capacity of test borehole (use minimum value recorded in test interval)
 Unfactored bore capacity = $P \times \text{Min Flowrate}$ = 8.0 L/s

FoS for consequences of failure = $F_{(c)}$ = 1.0

FoS for testing uncertainty = $F_{(t)}$ = 1.2

Total Factor of Safety $F_{(total)} = F_{(c)} \times F_{(t)}$ = 1.2

Factored percolation rate $P_{(factored)} = \frac{P}{F_{(total)}}$ = 6.7 L/s

General comments (indications of waterlogging, rock structure, etc.):

Name of test operator: Intorock Drilling Ltd Date: 15/11/24
 Qualification: _____ Signature: _____

Notes:
 1 mBGL = metres below ground level
 2 Use lowest tested flowrate (usually last interval). Repeat the test at least twice until the end of test flow rate is consistent to $\pm 10\%$.
 3 See Section B.4.0 Table 3 for factors of safety.
 4 See Section B.4.0 Table 8 for factors of safety.

Auckland Council Guidelines Document 602021007

8H1

STORMWATER SOAKAGE AND GROUNDWATER RECHARGE IN THE AUCKLAND REGION

B10

Appendix B1.4 Worksheet 4: Rockbore design summary

Site Address: 22 Summit Drive
 Designer: Shehan Attanayaka Date: 01/05/2025
 Qualification: BE (Civil) Signed: [Signature]
 Reviewer: Cheng Jin Khaw Date: _____
 Qualification: Licensed Cadastral Surveyor Signed: _____

Step 1. Site assessment
 Number of boreholes (Manhole 1): 1
 Manhole 1 diameter: 100 mm
 Number of boreholes (Manhole 2) - where required: _____
 Manhole 2 diameter - where required: _____ mm

Step 2. Hydrological requirement
 Peak discharge rate (Use TP108 Method), Q₅: 11.8 L/s

Step 3. Soakage rate (after factor of safety is applied)
 Borehole Factored Soakage Rate Details

Manhole 1		Manhole 2	
Bore 1, p ₁	6.7 L/s	Bore 5, p ₅	L/s
Bore 2, p ₂	L/s	Bore 6, p ₆	L/s
Bore 3, p ₃	L/s	Bore 7, p ₇	L/s
Bore 4, p ₄	L/s	Bore 8, p ₈	L/s
Total soakage rate with factor of safety applied (Q ₅)	6.7 L/s		

Provide Q₅? YES NO
 If yes, design is complete, if no, consider drilling more bores or using multiple devices.

1 Attach TP108 worksheet while submitting this worksheet for approval
 2 The soakage rate of every borehole shall be determined in L/s
 3 The designer may choose to have an extra borehole drilled for future development. The bore should be tested, but the soakage rate that it contributes should not be included in the Total Factored Soakage Rate for rockbore sizing.

8H1

ARC Guidelines for Stormwater Runoff Modelling

22




Figure 5.1 - Specific Peak Flow Rate

Worksheet 1: Graphical Peak Flow Rate

Project: A15-0082 By: SA Date: 2025May01
 Location: 22 Summit Drive Checked: ME Date: 2025May01
 Circle one: Pre-development Post-development

Data: Percentage Km²

Lot Area (m2)=	595.48	0.00059548
Imperv Area (m2)=	265.88	0.45
Perv Area (m2)=	329.6	0.55

ARI (Yr) =	10yr
P ₂₄ (mm) =	141
TC (Hr) =	0.17
CN =	74

TP 108 Include Climate Change

1. Weighted Average Curve Number =	(74 x Pervious %) + (98 x Impervious%)	= 84.7
2. Initial Abstraction I _a (mm)	(5 x Pervious %) + (0 x Impervious%)	= 2.8
3. Soil Storage S (mm)	((1000/CN)-10) x 25.4	= 45.8
4. Runoff Index C*	$\frac{P_{24} - 2I_a}{P_{24} - 2I_a + 2S}$	= 0.60
5. Specific Flow Rate q*	Using TP108 Figure 5.1	= 0.140
6. Peak Runoff q _p	q* x A x P ₂₄	= 0.011754775 m3/s (A=km2)
		= 11.7547752 l/s

REVISION				CHKD	DWN
ISSUE	DATE	DETAILS		CK	SA
A	09/05/25	RC APPLICATION			

DRAWING TITLE
SOAKAGE CALCULATION (LOT 1)

CLIENT
A & Y CONTRACTOR LIMITED


PROJECT
22&22A SUMMIT DRIVE, MOUNT ALBERT, AUCKLAND

ANCHOR CONSULTING LTD
 Tel: 021 66 99 46
 PO Box 34810, Birkenhead 0746, Auckland

SCALE: NTS
 DATE: APRIL 2025

SURVEYED BY: CL&AV	DESIGNED BY: N/A
DRAWN BY: SA	CHECKED BY: CK
PROJECT No. A15-0082	DWG No. RC-109
	REV. A

Detention Tank Calculation Summary				
22 Summit Drive				
1 Detention Purpose 4x350l Aquacomb (4x1.1mLx1.1mWx0.3mD)				
Pre Dev Imperv Area=	0 m ²			
Imperv Area=	266 m ²	Additional Impervious Area only		
Impervious Area to be use for 22 Summit Drive tank calculations=	270 m ²	Tank to be upsized to compensate the driveway area.		
2 Temporary Storage for 10 ARI Storm				
		I=141mm/day	TP 108 Includes Climate Change Factor	
Orifice diameter	=	0.085 m	(input in HEC-HMS)	
Cross sectional area (A)	=	0.005674502 m ²		
Orifice centre elevation	=	0.143 m	(bottom+100mm+half orifice diameter)	
Post development peak flow	=	0.00553 m ³ /s	(from HEC-HMS)- Soakage Rate with factor of safety applied = 6.7 l/s	
Soakage Flowrate	<	0.00670 m ³ /s	Q _{post} is less than soakgae flowrate therefore O.K.	
10 year peak storage = min tank size	=	1.26 m ³	(from HEC-HMS)	
Peak elevation	=	0.269 m	(from HEC-HMS)	



UNDERGROUND DETENTION TANK DETAILS

NTS

REVISION				
ISSUE	DATE	DETAILS	CHKD	DWN
A	09/05/25	RC APPLICATION	CK	SA

DRAWING TITLE
**DETENTION TANK DETAILS
(LOT 1)**

CLIENT
A & Y CONTRACTOR LIMITED

PROJECT
**22&22A SUMMIT DRIVE,
MOUNT ALBERT, AUCKLAND**




ANCHOR CONSULTING LTD
Tel: 021 66 99 46
PO Box 34810, Birkenhead 0746, Auckland

SCALE :	NTS		
DATE:	APRIL 2025		
SURVEYED BY :	CL&AV	DESIGNED BY:	N/A
DRAWN BY:	SA	CHECKED BY :	CK
PROJECT No.	DWG No.	REV.	
A15-0082	RC-110	A	



REVISION				
ISSUE	DATE	DETAILS	CHKD	DWN
A	09/05/25	RC APPLICATION	CK	SA



DRAWING TITLE
**SOAKAGE CATCHMENT PLAN
(LOT 2)**

CLIENT
A & Y CONTRACTOR LIMITED

PROJECT
**22&22A SUMMIT DRIVE,
MOUNT ALBERT, AUCKLAND**



ANCHOR CONSULTING LTD
Tel: 021 66 99 46
PO Box 34810, Birkenhead 0746, Auckland

SCALE :	1 : 100 @ A1	1 : 200 @ A3
DATE:	APRIL 2025	
SURVEYED BY :	CL&AV	DESIGNED BY: N/A
DRAWN BY:	SA	CHECKED BY: CK
PROJECT No.	DWG No.	REV.
A15-0082	RC-111	A



BORE LOG SHEET

DATE: 24.11.15

CLIENT: Anchor Consulting
 DESCRIPTION OF WORK: Drill bore for soakage & test
 LOCATION: 22a Summit Drive, Mt Albert
 METHOD OF BORING: Percussion DTH
 BOREHOLE NO: Three BOREHOLE DIA: 100mm
 BOREHOLE I.D.:
 BOREHOLE LOC: 5m x 3m from front left corner

Depth	Description	FLOW TEST		
		Meter Start	Meter Finish	Duration
1m				
2m	Stiff Ash			
3m	2.5m Basalt Rock			
4m	3.4m Broken Rock			
5m	4.0m → 4.7m Basalt Rock	Pre	Soak	10mins
6m	Broken Rock	N/A	N/A	10mins
7m	6.5m E.O.B	=	5,220L	/600sec
8m				
9m			Full	Hydrant
10m				Flow
11m				
12m				
13m				
14m				
15m				
16m				
17m				
18m				
19m				
20m				

Flow test result is only relevant to the actual time of testing.

Phone: 09 294 6181 Fax: 09 294 6182 Email: info@intorockdrilling.co.nz
 www.intorockdrilling.co.nz PO Box 79 DRURY 2247

Appendix B1.4 Worksheet 4: Rockbore design summary

Site Address: 22A Summit Drive
 Designer: Shehan Attanayake Date: 01/10/2025
 Qualification: GE (Civil) Signed: CA
 Reviewer: Cheng Jin Khaw Date:
 Qualification: Licensed Cadastral Surveyor Signed:

Step 1. Site assessment
 Number of boreholes (Manhole 1): 1
 Manhole 1 diameter: 100 mm
 Number of boreholes (Manhole 2) - where required:
 Manhole 2 diameter - where required:

Step 2. Hydrological requirement
 Peak discharge rate (Use TP108 Method): Q_{p1} 12.75 L/s

Step 3. Soakage rate (after factor of safety is applied)
 Borehole Factored Soakage Rate Details

Manhole 1		Manhole 2	
Bore 1, q_p	7.25 L/s	Bore 5, q_p	L/s
Bore 2, q_p	L/s	Bore 6, q_p	L/s
Bore 3, q_p	L/s	Bore 7, q_p	L/s
Bore 4, q_p	L/s	Bore 8, q_p	L/s
Total soakage rate with factor of safety applied (please)	7.25 L/s		

Do you have a soakage test? YES NO
 If yes, design is complete. If no, consider drilling more bores or using multiple devices.

*Attach TP108 worksheet while submitting this worksheet for approval

The soakage rate of every borehole shall be determined in L/s

The designer may choose to have an extra borehole drilled for future development. The bore should be tested, but the soakage rate that it contributes should not be included in the Total Factored Soakage Rate for rockbore sizing.

* provide 1.4 m² under ground tank for stormwater mitigation

Worksheet 1: Graphical Peak Flow Rate

Project: A15-0082 By: SA Date: 2025May01
 Location: 22A Summit Drive Checked: ME Date: 2025May01
 Circle one: Pre-development Post-development

Data:	Percentage	Km ²
Lot Area (m2)=	615	0.000615
Imperv Area (m2)=	325	0.53
Perv Area (m2)=	290	0.47

ARI (Yr) =	10yr
P ₂₄ (mm) =	141
TC (Hr) =	0.17
CN =	74

TP 108 Include Climate Change

1. Weighted Average Curve Number =	(74 x Pervious %) + (98 x Impervious%)	= 86.7
2. Initial Abstraction I _a (mm)	(5 x Pervious %) + (0 x Impervious%)	= 2.4
3. Soil Storage S (mm)	((1000/CN)-10) x 25.4	= 39.0
4. Runoff Index C*	$\frac{P_{24} - 2I_a}{P_{24} - 2I_a + 2S}$	= 0.64
5. Specific Flow Rate q*	Using TP108 Figure 5.1	= 0.147
6. Peak Runoff q _p	$q^* \times A \times P_{24}$	= 0.012747105 m ³ /s (A=km ²)
		= 12.747105 l/s

REVISION				CHKD	DWN
ISSUE	DATE	DETAILS		CK	SA
A	09/05/25	RC APPLICATION			

Worksheet 3: Rockbore Constant Head Percolation Test (page 2 of 2)

Borehole number: Three Test number: 1 of total no. 1

1. Capacity of test borehole (use minimum value recorded in test interval)
 Unfactored bore capacity = $q_p = \text{Min Flow rate}$ = 8.7 L/s
 FoS for consequences of failure = 1.0
 FoS for testing uncertainty = 1.2
 Total Factor of Safety = $F_{(total)} = F_{(c)} \times F_{(u)}$ = 1.2
 Factored percolation rate = $q_{p(factored)} = \frac{q_p}{F_{(total)}}$ = 7.25 L/s

General comments (indications of waterlogging, rock structure, etc.):

Name of test operator: Intorock Drilling Ltd Date: 15/11/2025
 Qualification:
 Signature:
 Notes:
 1 m BGL = metres below ground level
 2 Use lowest tested flow rate (usually last interval). Repeat the test at least twice until the end of test flow rate is consistent to ±10%.
 3 See Section B.4.0 Table 5 for factors of safety.
 4 See Section B.4.0 Table 6 for factors of safety.




Figure 5.1 - Specific Peak Flow Rate

DRAWING TITLE
SOAKAGE CALCULATION (LOT 2)


CLIENT
A & Y CONTRACTOR LIMITED

PROJECT
22&22A SUMMIT DRIVE, MOUNT ALBERT, AUCKLAND

ANCHOR CONSULTING LTD
 Tel: 021 66 99 46
 PO Box 34810, Birkenhead 0746, Auckland

SCALE:	NTS		
DATE:	APRIL 2025		
SURVEYED BY:	CL&AV	DESIGNED BY:	N/A
DRAWN BY:	SA	CHECKED BY:	CK
PROJECT No.	A15-0082	DWG No.	RC-112
		REV.	A

Detention Tank Calculation Summary				
22A Summit Drive				
1	Detention Purpose 5x350l Aquacomb (5x1.1mLx1.1mWx0.3mD)			
	Pre Dev Imperv Area=	0	m ²	
	Imperv Area=	325	m ²	Additional Impervious Area only
	Impervious Area to be use for 22 Summit Drive tank calculations=	330	m ²	Tank to be upsized to compensate the driveway area.
2	Temporary Storage for 10 ARI Storm		I=141mm/day	TP 108 Includes Climate Change Factor
	Orifice diameter	=	0.090	m (input in HEC-HMS)
	Cross sectional area (A)	=	0.006361725	m ²
	Orifice centre elevation	=	0.145	m (bottom+100mm+half orifice diameter)
	Post development peak flow	=	0.00674	m ³ /s (from HEC-HMS)- Soakage Rate with factor of safety applied = 7.3 l/s
	Soakage Flowrate	<	0.00730	m ³ /s Q _{post} is less than soakgae flowrate therefore O.K.
	10 year peak storage = min tank size	=	1.71	m ³ (from HEC-HMS)
	Peak elevation	=	0.29	m (from HEC-HMS)




UNDERGROUND DETENTION TANK DETAILS
NTS

REVISION				
ISSUE	DATE	DETAILS	CHKD	DWN
A	09/05/25	RC APPLICATION	CK	SA

DRAWING TITLE	
DETENTION TANK DETAILS (LOT 2)	
CLIENT	
A & Y CONTRACTOR LIMITED	
PROJECT	
22&22A SUMMIT DRIVE, MOUNT ALBERT, AUCKLAND	
 ANCHOR CONSULTING LTD ANCHOR CONSULTING LTD Tel: 021 66 99 46 PO Box 34810, Birkenhead 0746, Auckland	
SCALE :	NTS
DATE:	APRIL 2025
SURVEYED BY :	CL&AV
DESIGNED BY :	N/A
DRAWN BY :	SA
CHECKED BY :	CK
PROJECT No.	DWG No.
A15-0082	RC-113
REV.	A


REVISION				
ISSUE	DATE	DETAILS	CHKD	DWN
A	09/05/25	RC APPLICATION	CK	SA



NOTES:

- MINIMUM MANHOLE DIAMETER SIZED TO ACCOMMODATE AN ADDITIONAL BOREHOLE TO BE COMMISSIONED AT A LATER DATE.
- FLOW TESTING OF ROCKBORES TO BE CARRIED OUT BEFORE AND AFTER CAGE INSTALLATION.
- NEW ROCKBORE MINIMUM DEPTH OF MANHOLE 1.5m. MANHOLES DEEPER THAN 1.5m WILL NEED DISCUSSION AS ACCESSIBILITY FOR MAINTENANCE BECOMES AN ISSUE.
- MINIMUM DEPTH OF BOREHOLE FROM CONCRETE BASE OF MANHOLE IS 2.0m.
- ACCESS RUNGS SHALL BE PROVIDED FOR MANHOLE ACCESS. REFER TO DRAWING IN STORMWATER CODE OF PRACTICE FOR DETAILS.
- BOREHOLE POSITIONS RELATIVE TO MANHOLE LID NOT SHOWN TO ACCURATELY TO AID CLARITY. POSITION SHOULD BE AS PER DRAWING G007_02.
- SETBACK REQUIREMENTS BUILDINGS AND PROPERTY BOUNDARIES:
 - A SETBACK DISTANCE OF 3m IS RECOMMENDED FOR BUILDINGS AND PROPERTY BOUNDARIES. SPECIFIC GEOTECHNICAL DESIGN WILL BE REQUIRED WHERE THE DEVICE MAY AFFECT ADJACENT STRUCTURES (SUBJECT TO COUNCIL APPROVAL).
 - WHERE THIS IS NOT PRACTICALLY POSSIBLE A SITE-SPECIFIC GEOTECHNICAL DESIGN MUST BE COMPLETED TAKING INTO ACCOUNT THE EFFECTS OF THE SOAKAGE DEVICE ON BUILDING FOUNDATIONS AND POTENTIAL FOR FLOODING OF NEIGHBOURING PROPERTIES. THIS MUST BE DONE BY A CHARTERED GEOTECHNICAL ENGINEER OR A PROFESSIONAL ENGINEERING GEOLOGIST.
 - DEVICES SHALL NOT BE PLACED BELOW BUILDINGS AND BUILDINGS SHALL NOT BE BUILT OVER SOAKAGE DEVICES.
- RETAINING WALLS:
 - FOR WALLS < 2m HIGH, THE SETBACK MUST NOT BE LESS THAN THE HEIGHT OF THE RETAINING WALL + 1.5m AND WHERE THE SOAKAGE DEVICE IS UP SLOPE OF THE WALL THEN THE WALL MUST HAVE BEEN DESIGNED TO TAKE FULL WATER LOADING.
 - THE ROCK BORE MUST BE DESIGNED TO DISCHARGE IN A ZONE THAT IS BELOW THE TOE OF ANY WALL WITHIN 10 M.
 - FOR WALLS > 2m HIGH, A SITE-SPECIFIC DESIGN MUST BE CARRIED OUT BY A GEOTECHNICAL ENGINEER, CONSIDERING RELEVANT GEOTECHNICAL ISSUES AND CUT-OFF DRAINAGE OF THE RETAINING WALL.
- UNDERGROUND INFRASTRUCTURE:
 - A SETBACK DISTANCE OF 2m IS REQUIRED FROM ANY EXISTING WATER AND WASTEWATER PIPES.
- DEVICES THAT WILL BE VESTED TO AUCKLAND TRANSPORT SHALL BE DESIGNED IN ACCORDANCE WITH THE AUCKLAND TRANSPORT CODE OF PRACTICE.
- PIPE EMBEDMENT DETAILS FOR PRIVATE DRAINAGE SHALL COMPLY WITH BUILDING CODE AS PER NZS 7643.
- PIPE EMBEDMENT DETAILS FOR THE PUBLIC DRAINAGE SHALL COMPLY WITH STORMWATER CODE OF PRACTICE (SWCOP) DRAWINGS.


SOAKAGE GUIDELINE DOCUMENT STANDARD DETAILS	AUCKLAND COUNCIL		ENVIRONMENTAL-SW ORIGINAL SCALE A3 SCALE: N.T.S.
REVISION: 0 REV DATE: 21/06/2021 CAD FILENAME: G007_01.DWG	TYPICAL ROCKBORE FOR FRACTURED ROCK (SECTION)		DRAWING SET SHEET 1 OF 1 DRAWING No. G007_01 REV 0



NOTES:

- REFER TO DRAWING G007_01 NOTES 1.
- ALLOWANCE SHALL BE MADE FOR 1 ADDITIONAL BORE TO BE DRILLED FOR REDUNDANCY DUE TO BLOCKAGE OR INCREASED FLOW.
- ALL RESIDENTIAL ROOF WATER SHALL DISCHARGE TO SEDIMENT CHAMBER / CATCHPIT AND NOT DIRECTLY INTO THE DEVICE.
- ALL RUNOFF FROM ROADS, CAR PARKS OR OTHER CONTAMINANT SOURCES MUST INCLUDE PRE-TREATMENT OF RUNOFF PRIOR TO ENTERING ROCKBORE. REFER TO G007 AND DRAWING G007_11 FOR PRE-TREATMENT OPTIONS AND EXAMPLES.
- LEAF TRAP TO BE INSTALLED IN ROOF GUTTERS.

SOAKAGE GUIDELINE DOCUMENT STANDARD DETAILS	AUCKLAND COUNCIL		ENVIRONMENTAL-SW ORIGINAL SCALE A3 SCALE: N.T.S.
REVISION: 0 REV DATE: 21/06/2021 CAD FILENAME: G007_02.DWG	TYPICAL ROCKBORE FOR FRACTURED ROCK (PLAN)		DRAWING SET SHEET 1 OF 1 DRAWING No. G007_02 REV 0



NOTES:

- HOT DIP GALVANISE WHOLE CAGE AND SLEEVE AFTER FABRICATION. (APPROXIMATE WEIGHT OF WHOLE CAGE 16 TO 18kg)
- RETROFIT TO EXISTING ROCKBORE: CAGE HEIGHT = MANHOLE DEPTH - 1.0m. MINIMUM CAGE HEIGHT TO BE 1.0m.

SOAKAGE GUIDELINE DOCUMENT STANDARD DETAILS	AUCKLAND COUNCIL		ENVIRONMENTAL-SW ORIGINAL SCALE A3 SCALE: N.T.S.
REVISION: 0 REV DATE: 21/06/2021 CAD FILENAME: G007_03.DWG	TYPICAL ROCKBORE FILTER CAGE (DETAILS) FOR FRACTURED ROCK		DRAWING SET SHEET 1 OF 1 DRAWING No. G007_03 REV 0

DRAWING TITLE
SOAKAGE STANDARD DETAILS


CLIENT
A & Y CONTRACTOR LIMITED

PROJECT
**22&22A SUMMIT DRIVE,
MOUNT ALBERT, AUCKLAND**



ANCHOR CONSULTING LTD
Tel: 021 66 99 46
PO Box 34810, Birkenhead 0746, Auckland



SCALE:	NTS		
DATE:	APRIL 2025		
SURVEYED BY:	CL&AV	DESIGNED BY:	N/A
DRAWN BY:	SA	CHECKED BY:	CK
PROJECT No.	A15-0082	DWG No.	RC-114
		REV.	A



REVISION				
ISSUE	DATE	DETAILS	CHKD	DWN
A	09/05/25	RC APPLICATION	CK	SA
B	09/12/25	SWALE SPECS CHANGED TO ROCK RIP RAP	CK	ME

LEGEND:

OLFP DIRECTION.



DRAWING TITLE

POST DEVELOPMENT OLFP PLAN

CLIENT

A & Y CONTRACTOR LIMITED


PROJECT

**22&22A SUMMIT DRIVE,
MOUNT ALBERT, AUCKLAND**



ANCHOR CONSULTING LTD
Tel: 021 66 99 46
PO Box 34810, Birkenhead 0746, Auckland

SCALE:	1:100 @ A1	1:200 @ A3
DATE:	APRIL 2025	
SURVEYED BY:	CL&AV	DESIGNED BY: N/A
DRAWN BY:	SA	CHECKED BY: CK
PROJECT No.	DWG No.	REV.
A15-0082	RC-115	B



REVISION				CHKD	DWN
ISSUE	DATE	DETAILS		CK	SA
A	09/05/25	RC APPLICATION			

DRAWING TITLE
**CLOSEST BUILDING
 ROOF HEIGHTS PLAN**

CLIENT
A & Y CONTRACTOR LIMITED

PROJECT
**22&22A SUMMIT DRIVE,
 MOUNT ALBERT, AUCKLAND**



ANCHOR CONSULTING LTD
 Tel: 021 66 99 46
 PO Box 34810, Birkenhead 0746, Auckland

SCALE :	1 : 100 @ A1	1 : 200 @ A3
DATE:	MAY 2025	
SURVEYED BY :	CL&AV	DESIGNED BY: N/A
DRAWN BY:	SA	CHECKED BY: CK
PROJECT No.	DWG No.	REV.
A15-0082	RC-200	A

Property Address	Highest Ridge RL (m)
26 Summit Drive	102.24
20 Summit Drive	91.07
18A Summit Drive	88.37
16 Summit Drive	86.07
1 Sadgrove Terrace	80.97
3A Sadgrove Terrace	80.55
7 Sadgrove Terrace	86.92
9 Sadgrove Terrace	84.39

APPENDIX C - Detention Tank Calculations

BORE LOG SHEET

DATE: 24.11.15

CLIENT:	Anchor Consulting		
DESCRIPTION OF WORK:	Drill bore for soakage & test		
LOCATION:	22 Summit Drive, Mt Albert		
METHOD OF BORING:	Percussion DTH		
BOREHOLE NO:	One	BOREHOLE DIA:	100mm
BOREHOLE I.D:			
BOREHOLE LOC:	6m x 5m from front right corner		

STRATA		FLOW TEST			
Depth	Description	Meter Start	Meter Finish	Duration	Lts / sec
1m	Ash				
2m	Boulders & Ash				
3m					
3.4m					
4m					
5m					
6m					
7m					
8m					
9m					
10m	Scoria				
11m					
12m					
13m					
14m		Pre	Soak	10mins	
15m		N/A	N/A	10mins	
15.5m		=	4,800L	/600sec	8.0L/sec
16m	E.O.B				
17m					
18m			Full	Hydrant	Flow
19m					
20m					

Flow test result is only relevant to the actual time of testing.

Worksheet 3: Rockbore Constant Head Percolation Test (page 2 of 2)

Borehole number: one Test number: 1 of total no. 1

1. Capacity of test borehole (use minimum value recorded in test interval)			
Unfactored bore capacity ²	$= P = \text{Min Flowrate}$	=	<u>8.0</u> L/s
FoS for consequences of failure ³	$= F_{(c)}$	=	<u>1.0</u>
FoS for testing uncertainty ⁴	$= F_{(u)}$	=	<u>1.2</u>
Total Factor of Safety	$F_{(total)} = F_{(c)} \times F_{(u)}$	=	<u>1.2</u>
Factored percolation rate	$P_{(factored)} = \frac{P}{F_{(total)}}$	=	<u>6.7</u> L/s

General comments (indications of waterlogging, rock structure, etc.):

Name of test operator: Intorock Drilling Ltd Date: 15/11/24

Qualification: _____ Signature: _____

Notes:

¹ mBGL = metres below ground level

² Use lowest tested flowrate (usually last interval). Repeat the test at least twice until the end of test flow rate is consistent to ±10%.

³ See Section B.4.0 Table 5 for factors of safety.

⁴ See Section B.4.0 Table 6 for factors of safety.

Appendix B1.4 Worksheet 4: Rockbore design summary

Site Address: 22 Summit Drive
 Designer: Shehan Attanayaka Date: 01/05/2025
 Qualification: BE (civil) Signed: [Signature]
 Reviewer: Chong Jin Khaw Date: _____
 Qualification: Licensed Cadastral Surveyor Signed: _____

Step 1. Site assessment	
Number of boreholes (Manhole 1):	1
Manhole 1 diameter:	100 mm
Number of boreholes (Manhole 2) – where required:	
Manhole 2 diameter – where required:	mm

Step 2. Hydrological requirement	
Peak discharge rate (Use TP108 Method), $Q_{(s)}$ ¹	11.8 L/s

Step 3. Soakage rate (after factor of safety is applied)			
Borehole Factored Soakage Rate Details ²			
Manhole 1		Manhole 2	
Bore 1, p ₁	6.7 L/s	Bore 5, p ₅	L/s
Bore 2, p ₂	L/s	Bore 6, p ₆	L/s
Bore 3, p ₃	L/s	Bore 7, p ₇	L/s
Bore 4, p ₄ ³	L/s	Bore 8, p ₈ ³	L/s
Total soakage rate with factor of safety applied $p_{(factored)}$		6.7	L/s
$p_{(factored)} \geq Q_{(s)}$? ³		<input type="checkbox"/> YES	<input checked="" type="checkbox"/> NO
If yes, design is complete. If no, consider drilling more bores or using multiple devices.			

* provide 1.4 m³ under ground tank for stormwater mitigation.

¹Attach TP108 worksheet while submitting this worksheet for approval

²The soakage rate of every borehole shall be determined in L/s

³The designer may choose to have an extra borehole drilled for future development. The bore should be tested, but the soakage rate that it contributes should not be included in the Total Factored Soakage Rate for rockbore sizing.




Figure 5.1 - Specific Peak Flow Rate

Worksheet 1: Graphical Peak Flow Rate

Project:	A15-0082	By:	SA	Date:	2025May01
Location:	22 Summit Drive	Checked:	ME	Date:	2025May01
Circle one:	Pre-development		Post-development		

Data:	Percentage	Km ²
Lot Area (m2)=	595.48	0.00059548
Imperv Area (m2)=	265.88	0.45
Perv Area (m2)=	329.6	0.55

ARI (Yr) =	10yr
P ₂₄ (mm) =	141
TC (Hr) =	0.17
CN =	74

TP 108 Include Climate Change

1. Weighted Average Curve Number =	(74 x Pervious %) + (98 x Impervious%)	
	=	84.7
2. Initial Abstraction I _a (mm)	(5 x Pervious %) + (0 x Impervious%)	
	=	2.8
3. Soil Storage S (mm)	((1000/CN)-10) x 25.4	
	=	45.8
4. Runoff Index C*	$\frac{(P_{24} - 2I_a)}{(P_{24} - 2I_a + 2s)}$	
	=	0.60
5. Specific Flow Rate q*	Using TP108 Figure 5.1	
	=	0.140
6. Peak Runoff q _p	= q* x A x P ₂₄	(A=km2)
	= 0.011754775	m3/s
	= 11.7547752	l/s

BORE LOG SHEET

DATE: 24.11.15

CLIENT:	Anchor Consulting		
DESCRIPTION OF WORK:	Drill bore for soakage & test		
LOCATION:	22 Summit Drive, Mt Albert		
METHOD OF BORING:	Percussion DTH		
BOREHOLE NO:	Three	BOREHOLE DIA:	100mm
BOREHOLE I.D.:			
BOREHOLE LOC:	5m x 3m from front left corner		

STRATA		FLOW TEST			
Depth	Description	Meter Start	Meter Finish	Duration	Lts / sec
1m					
2m	Stiff Ash				
2.5m					
3m	Basalt Rock				
3.4m					
4m	Broken Rock				
4.0m					
5m	→ 4.7m Basalt Rock	Pre	Soak	10mins	
6m	Broken Rock	N/A	N/A	10mins	
6.5m	E.O.B	=	5,220L	/600sec	8.7L/sec
7m					
8m					
9m			Full	Hydrant	Flow
10m					
11m					
12m					
13m					
14m					
15m					
16m					
17m					
18m					
19m					
20m					

Flow test result is only relevant to the actual time of testing.

Worksheet 3: Rockbore Constant Head Percolation Test (page 2 of 2)

Borehole number: Three Test number: 1 of total no. 1

1. Capacity of test borehole (use minimum value recorded in test interval)			
Unfactored bore capacity ²	$= P = \text{Min Flowrate}$	=	<u>8.7</u> L/s
FoS for consequences of failure ³	$= F_{(c)}$	=	<u>1.0</u>
FoS for testing uncertainty ⁴	$= F_{(u)}$	=	<u>1.2</u>
Total Factor of Safety	$F_{(total)} = F_{(c)} \times F_{(u)}$	=	<u>1.2</u>
Factored percolation rate	$P_{(factored)} = \frac{P}{F_{(total)}}$	=	<u>7.25</u> L/s

General comments (indications of waterlogging, rock structure, etc.):

Name of test operator: Intorock Drilling Ltd Date: 15/11/2024

Qualification: _____ Signature: _____

Notes:

¹ mBGL = metres below ground level

² Use lowest tested flowrate (usually last interval). Repeat the test at least twice until the end of test flow rate is consistent to ±10%.

³ See Section B.4.0 Table 5 for factors of safety.

⁴ See Section B.4.0 Table 6 for factors of safety.

Appendix B1.4 Worksheet 4: Rockbore design summary

Site Address: 22A Summit Drive

Designer: Shehan Attanayaka Date: 01/05/2025

Qualification: BE (Civil) Signed: Yh

Reviewer: Chong Jin Khaw Date: _____

Qualification: Licensed Cadastral Surveyor Signed: _____

Step 1. Site assessment	
Number of boreholes (Manhole 1):	<u>1</u>
Manhole 1 diameter:	<u>100</u> mm
Number of boreholes (Manhole 2) – where required:	
Manhole 2 diameter – where required:	mm

Step 2. Hydrological requirement	
Peak discharge rate (Use TP108 Method), $Q_{(s)}$ ¹	<u>12.75</u> L/s

Step 3. Soakage rate (after factor of safety is applied)			
Borehole Factored Soakage Rate Details ²			
Manhole 1		Manhole 2	
Bore 1, p_1	<u>7.25</u> L/s	Bore 5, p_5	L/s
Bore 2, p_2	L/s	Bore 6, p_6	L/s
Bore 3, p_3	L/s	Bore 7, p_7	L/s
Bore 4, p_4 ³	L/s	Bore 8, p_8 ³	L/s
Total soakage rate with factor of safety applied $p_{(factored)}$		<u>7.25</u>	L/s
$p_{(factored)} \geq Q_{(s)}$? ³		<input type="checkbox"/> YES	<input checked="" type="checkbox"/> NO
If yes, design is complete. If no, consider drilling more bores or using multiple devices.			

* provide 1.4 m³ under ground tank for stormwater mitigation.

¹Attach TP108 worksheet while submitting this worksheet for approval

²The soakage rate of every borehole shall be determined in L/s

³The designer may choose to have an extra borehole drilled for future development. The bore should be tested, but the soakage rate that it contributes should not be included in the Total Factored Soakage Rate for rockbore sizing.




Figure 5.1 - Specific Peak Flow Rate

Worksheet 1: Graphical Peak Flow Rate

Project:	A15-0082	By:	SA	Date:	2025May01
Location:	22A Summit Drive	Checked:	ME	Date:	2025May01
Circle one:	Pre-development		Post-development		

Data:	Percentage	Km ²
Lot Area (m2)=	615	0.000615
Imperv Area (m2)=	325	0.53
Perv Area (m2)=	290	0.47

ARI (Yr) =	10yr
P ₂₄ (mm) =	141
TC (Hr) =	0.17
CN =	74

TP 108 Include Climate Change

1. Weighted Average Curve Number =	(74 x Pervious %) + (98 x Impervious%)	
	=	86.7
2. Initial Abstraction I _a (mm)	(5 x Pervious %) + (0 x Impervious%)	
	=	2.4
3. Soil Storage S (mm)	((1000/CN)-10) x 25.4	
	=	39.0
4. Runoff Index C*	$\frac{(P_{24} - 2I_a)}{(P_{24} - 2I_a + 2s)}$	
	=	0.64
5. Specific Flow Rate q*	Using TP108 Figure 5.1	
	=	0.147
6. Peak Runoff q _p	= q* x A x P ₂₄	(A=km2)
	= 0.012747105	m3/s
	= 12.747105	l/s

APPENDIX C - Detention Tank Calculations

Detention Tank Calculation Summary

22 Summit Drive

1 Detention Purpose 4x350l Aquacomb (4x1.1mLx1.1mWx0.3mD)

Pre Dev Imperv Area= 0 m²

Imperv Area= 266 m²

Additional Impervious Area only

Impervious Area to be use for 22 Summit Drive
tank calculations= 270 m²

Tank to be upsized to compensate the driveway area.

2 Temporary Storage for 10 ARI Storm

I=141mm/day

TP 108 Includes Climate Change Factor

Orifice diameter = 0.085 m (input in HEC-HMS)

Cross sectional area (A) = 0.005674502 m²

Orifice centre elevation = 0.143 m (bottom+100mm+half orifice diameter)

Post development peak flow = 0.00553 m³/s (from HEC-HMS)- Soakage Rate with factor of safety applied = 6.7 l/s

Soakage Flowrate < 0.00670 m³/s Q_{post} is less than soakgae flowrate therefore O.K.

10 year peak storage = min tank size = 1.26 m³ (from HEC-HMS)

Peak elevation = 0.269 m (from HEC-HMS)




HEC-HMS

Project : 22 SUMMIT DRIVE

Basin Model : 10 year

May 02 12:06:17 NZST 2025



22 Summit Drive

Project: Road Detention Tank Simulation Run: 10 Year

Start of Run: 01Jan2000, 00:00 Basin Model: 10 year
 End of Run: 02Jan2000, 00:00 Meteorologic Model: 10 year RF
 Compute Time: 02May2025, 12:05:54 Control Specifications: Control 1

Hydrologic Element	Drainage Area (KM2)	Peak Discharge (M3/S)	Time of Peak	Volume (1000 M3)
10 year post imperv	0.000270	0.00654	01Jan2000, 12:10	0.03690
Detention Tank	0.000270	0.00553	01Jan2000, 12:20	0.03603
post flows	0.000270	0.00654	01Jan2000, 12:10	0.03690
10 year pre perv	0.000270	0.00427	01Jan2000, 12:10	0.02232

Project: Road Detention Tank **22 SUMMIT DRIVE**

Simulation Run: 10 Year Reservoir: Detention Tank


Start of Run: 01Jan2000, 00:00 Basin Model: 10 year
End of Run: 02Jan2000, 00:00 Meteorologic Model: 10 year RF
Compute Time: 02May2025, 12:05:54 Control Specifications: Control 1

Volume Units: 1000 M3

Computed Results

Peak Inflow :	0.00654 (M3/S)	Date/Time of Peak Inflow :	01Jan2000, 12:10
Peak Outflow :	0.00553 (M3/S)	Date/Time of Peak Outflow :	01Jan2000, 12:20
Total Inflow :	0.03690 (1000 M3)	Peak Storage :	0.00126 (1000 M3)
Total Outflow :	0.03603 (1000 M3)	Peak Elevation :	0.269 (M)

22 Summit Drive
 Reservoir "Detention Tank" Results for Run "10 Year"



- Run:10 Year Element:DETENTION TANK Result:Storage
- Run:10 Year Element:DETENTION TANK Result:Pool Elevation
- Run:10 Year Element:DETENTION TANK Result:Outflow
- Run:10 Year Element:DETENTION TANK Result:Combined Flow

Detention Tank Calculation Summary

22A Summit Drive

1 Detention Purpose 5x350l Aquacomb (5x1.1mLx1.1mWx0.3mD)

Pre Dev Imperv Area= 0 m²

Imperv Area= 325 m²

Additional Impervious Area only

Impervious Area to be use for 22 Summit Drive
tank calculations= 330 m²

Tank to be upsized to compensate the driveway area.

2 Temporary Storage for 10 ARI Storm

I=141mm/day

TP 108 Includes Climate Change Factor

Orifice diameter = 0.090 m (input in HEC-HMS)

Cross sectional area (A) = 0.006361725 m²

Orifice centre elevation = 0.145 m (bottom+100mm+half orifice diameter)

Post development peak flow = 0.00674 m³/s (from HEC-HMS)- Soakage Rate with factor of safety applied = 7.3 l/s

Soakage Flowrate < 0.00730 m³/s Q_{post} is less than soakgae flowrate therefore O.K.

10 year peak storage = min tank size = 1.71 m³ (from HEC-HMS)

Peak elevation = 0.29 m (from HEC-HMS)





HEC-HMS

Project : 22A SUMMIT DRIVE

Basin Model : 10 year

May 02 12:20:38 NZST 2025



22A SUMMIT DRIVE

Project: Road Detention Tank Simulation Run: 10 Year

Start of Run: 01Jan2000, 00:00 Basin Model: 10 year
 End of Run: 02Jan2000, 00:00 Meteorologic Model: 10 year RF
 Compute Time: 02May2025, 12:19:27 Control Specifications: Control 1

Hydrologic Element	Drainage Area (KM2)	Peak Discharge (M3/S)	Time of Peak	Volume (1000 M3)
10 year post imperv	0.000330	0.00799	01Jan2000, 12:10	0.04510
Detention Tank	0.000330	0.00674	01Jan2000, 12:20	0.04430
post flows	0.000330	0.00799	01Jan2000, 12:10	0.04510
10 year pre perv	0.000330	0.00522	01Jan2000, 12:10	0.02728

22A SUMMIT DRIVE

Project: Road Detention Tank
Simulation Run: 10 Year Reservoir: Detention Tank

Start of Run: 01Jan2000, 00:00 Basin Model: 10 year
End of Run: 02Jan2000, 00:00 Meteorologic Model: 10 year RF
Compute Time: 02May2025, 12:19:27 Control Specifications: Control 1


Volume Units: 1000 M3

Computed Results

Peak Inflow :	0.00799 (M3/S)	Date/Time of Peak Inflow :	01Jan2000, 12:10
Peak Outflow :	0.00674 (M3/S)	Date/Time of Peak Outflow :	01Jan2000, 12:20
Total Inflow :	0.04510 (1000 M3)	Peak Storage :	0.00171 (1000 M3)
Total Outflow :	0.04430 (1000 M3)	Peak Elevation :	0.294 (M)

22A SUMMIT DRIVE

Reservoir "Detention Tank" Results for Run "10 Year"



- - - Run:10 Year Element:DETENTION TANK Result:Storage
 - - - Run:10 Year Element:DETENTION TANK Result:Pool Elevation
 - - - Run:10 Year Element:DETENTION TANK Result:Outflow
 - - - Run:10 Year Element:DETENTION TANK Result:Combined Flow

APPENDIX D - OLFP Calculation

22 Summit Drive OLFP Channel

Project Description	
Worksheet	Section A-A
Flow Element	Irregular Channel
Method	Manning's Formula
Solve For	Channel Depth

Input Data	
Slope	0.300000 m/m
Discharge	0.1000 m ³ /s

Options	
Current Roughness Method	Improved Lotter's Method
Open Channel Weighting Method	Improved Lotter's Method
Closed Channel Weighting Method	Horton's Method

Results	
Mannings Coefficient	0.030
Water Surface Elevation	9.86 m
Elevation Range	9.75 to 10.00
Flow Area	3.8e-2 m ²
Wetted Perimeter	0.72 m
Top Width	0.68 m
Actual Depth	0.11 m
Critical Elevation	9.94 m
Critical Slope	0.020873 m/m
Velocity	2.60 m/s
Velocity Head	0.34 m
Specific Energy	10.21 m
Froude Number	3.49
Flow Type	Supercritical


Roughness Segments		
Start Station	End Station	Mannings Coefficient
0+00.00	0+01.50	0.030

Natural Channel Points		
Station (m)	Elevation (m)	
	0+00.00	10.00
	0+00.75	9.75
	0+01.50	10.00

22 Summit Drive OLFP Channel

Project Description	
Worksheet	Section A-A
Flow Element	Irregular Channel
Method	Manning's Formula
Solve For	Channel Depth

Section Data	
Mannings Coefficient	0.030
Slope	0.300000 m/m
Water Surface Elevation	9.86 m
Elevation Range	9.75 to 10.00
Discharge	0.1000 m ³ /s



v:1
H:1
NTS